

SUMMARY OF QUANTITIES			URBAN CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE							
CODE NO	ITEM	UNIT	TOTAL QUANTITIES 90% FED. 10% STATE	1000						CODE NO	ITEM	UNIT	TOTAL QUANTITIES						
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	5	5															
40600300	AGGREGATE (PRIME COAT)	TON	22	22															
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	33	33															
40600895	CONSTRUCTING TEST STRIP	EACH	1	1															
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	545	545															
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	1219	1219															
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	10881	10881															
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6															
67100100	MOBILIZATION	L SUM	1	1															
70300530	PAVEMENT MARKING TAPE, TYPE III 5"	FOOT	11701	11701															
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	4876	4876															
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	25893	25893															
*78004220	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 5"	FOOT	11701	11701															
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1171	1171															
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1171	1171															
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1															
* SPECIALTY ITEM																			

FILE NAME = c:\pw\work\pwl\pwl\green\pwl\025109\Design.dgn	USER NAME = wlgreendp	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	I-55 (STEVENS ON EXPRESSWAY) SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
		DRAWN -	REVISED -			55	2007-0181	COOK	14	3		
		CHECKED -	REVISED -			CONTRACT NO. 60C73						
		DATE -	REVISED -			SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. 1