

PROJECT: FAP 389 - CONGRESS PARKWAY OVER SOUTH BRANCH OF CHICAGO RIVER - CONTRACT NO. 60D61 COOK COUNTY

X075-2A

CODE NO.	ITEM	UNIT	SUMMARY OF QUANTITIES					
			URBAN TOTAL QUANTITY	ROADWAY 80% FED 20% STATE I000-2A	ROADWAY LIGHTING 80% FED 20% STATE Y03D-HE	CONSTRUCTION TYPE CODE		
						80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE
50500505	STUD SHEAR CONNECTORS	EACH	6302			6302		
50501120	STRUCTURAL STEEL REMOVAL	L SUM	1			1		
50501130	STRUCTURAL STEEL REPAIR	POUND	137,850			137,850		
50600300	CLEANING AND PAINTING STEEL BRIDGE	L SUM	1			1		
50600400	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES	L SUM	1			1		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	87,600	1,400		86,200		
50800600	CONTAINMENT AND DISPOSAL OF NON-LEAD PAINT CLEANING RESIDUES	L SUM	1			1		
50900200	STEEL RAILING, TYPE 2399	FOOT	161			161		
50900500	ALUMINUM RAILING	FOOT	553			553		
50901705	TUBULAR THRIE BEAM RETROFIT RAIL FOR BRIDGES	FOOT	150	150				
51500100	NAME PLATES	EACH	2			2		
52000110	PREFORMED JOINT STRIP SEAL	FOOT	129			129		
58000100	MEMBRANE WATERPROOFING	SQ FT	1,946			1,946		
59000200	EPOXY CRACK INJECTION	FOOT	144			144		
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	308	308				
60623714	CONCRETE MEDIAN (SPECIAL)	SQ FT	1,451	1,451				
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1	1				
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	1	1				
* 63100215	TRAFFIC BARRIER TERMINAL, TYPE 6 (SPECIAL)	EACH	1	1				
63200310	GUARDRAIL REMOVAL	FOOT	178	178				
63801200	MODULAR GLARE SCREEN SYSTEM	FOOT	3,570	3,570				
66400505	CHAIN LINK FENCE, 8'	FOOT	380	380				
66409300	CHAIN LINK GATES 8'X10' DOUBLE	EACH	1	1				
67100100	MOBILIZATION	L SUM	1	0.5		0.5		
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1				
70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	4	4				
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	50	50				
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	280	280				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	15,783	15,783				
70400100	TEMPORARY CONCRETE BARRIER	FOOT	3,084	3,084				
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1,375	1,375				
* 72000100	SIGN PANEL, TYPE 1	SQ FT	162	162				
* 72000200	SIGN PANEL, TYPE 2	SQ FT	84	84				
* 72400710	RELOCATE SIGN PANEL- TYPE 1	SQ FT	27	27				
* 72400900	REMOVE SIGN PANEL	EACH	15	15				
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	80	80				
* 73100100	BASE FOR TELESCOPING STEEL SIGN SUPPORT	EACH	6	6				

*Specialty Items

PB Americas, Inc.
230 WEST MONROE STREET,
SUITE 900
CHICAGO, IL. 60606

USER NAME = #USER#
FILE NAME = #FILENAME#
PLOT SCALE = #SCALE#
PLOT DATE = 5/7/2009

DESIGNED - DM
DRAWN - MS
CHECKED - DS
DATE - 5/08/09

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

CONGRESS PARKWAY OVER SOUTH BRANCH OF THE CHICAGO RIVER
SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 5 OF 83 SHEETS STA. 377+01.00 TO STA. 382+45.28

Rev.
F.A.P. SECTION COUNTY TOTAL SHEETS SHEET NO.
389 2424-2B-R COOK 398 5
CONTRACT NO. 60D61
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT