

PROJECT: FAP 389 - CONGRESS PARKWAY OVER SOUTH BRANCH OF CHICAGO RIVER - CONTRACT NO. 60D61 COOK COUNTY

X075-2A

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					
CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY	ROADWAY LIGHTING				
				80% FED 20% STATE 1000	80% FED 20% STATE Y030-1E	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1	1					
X0322185	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/4 INCHES	SQ YD	1,040			1,040			
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	1,805	1,805					
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH ^{EQUAL TO OR} LESS THAN 5 INCHES)	SQ FT	57			57			
X0325702	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1					
X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	25,720	25,720					
X0325840	WET REFLECTIVE TEMPORARY TAPE TYPE III, 12 INCH	FOOT	190	190					
X0325841	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 24 INCH	FOOT	76	76					
X0325842	WET REFLECTIVE TEMPORARY TAPE, TYPE III, LETTERS AND SYMBOLS	SQ FT	55	55					
X0325876	WET REFLECTIVE TEMPORARY TAPE TYPE III, 8 INCH	FOOT	7,110	7,110					
X0326107	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 5 INCH	FOOT	2,460	2,460					
X0350800	BOLLARDS	EACH	10	10					
81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	750						750
81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	50						50
X4400198	CONCRETE BARRIER REMOVAL (SPECIAL)	FOOT	737	737					
X4403300	CONCRETE MEDIAN REMOVAL	SQ FT	1,451	1,451					
X6700410	ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)	CAL MO	30	30					
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1					
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	630	630					
X7240205	REMOVE SIGN COMPLETE	EACH	2	2					
X8700210	ELECTRIC CABLE ASSEMBLY IN CONDUIT, 600V (EPR-TYPE TC) 3/C NO. 4/0 AND NO. 4 GROUND	FOOT	261						261
XX003988	TEMPORARY CONCRETE BARRIER REMOVAL	FOOT	3,136	3,136					
NP XX005656	INLET FILTER CLEANING	EACH	22	22					
XX006677	TREE WELL	EACH	6	6					
XX007763	TEMPORARY FENCE (SPECIAL)	FOOT	300	300					
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.5		0.5			
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	50			50			
Z0029999	IMPACT ATTENUATOR REMOVAL	EACH	4	4					
Z0030070	IMPACT ATTENUATORS (SEVERE USE, NARROW), TEST LEVEL 3	EACH	2	2					
Z0030280	IMPACT ATTENUATORS, TEMPORARY (SEVERE USE, NARROW), TEST LEVEL 3	EACH	1	1					
Z0030290	IMPACT ATTENUATORS, TEMPORARY (SEVERE USE, WIDE), TEST LEVEL 3	EACH	1	1					
Z0034100	MASONRY WALL CONSTRUCTION	SQ FT	385			385			
Z0053800	RIVET REMOVAL AND REPLACEMENT	EACH	2,888			2,888			
Z0006900	BRIDGE FLOOR REMOVAL	SQ YD	2,171			2,171			
Z0076600	TRAINEES	HOUR	1500	1500					
X7011012	TRAFFIC CONTROL AND PROTECTION FOR ALTERNATE ROUTE	L SUM	1	1					

* SPECIALTY ITEMS

© Y080
NP= Non-participating

PB Americas, Inc.
230 WEST MONROE STREET,
SUITE 900
CHICAGO, IL. 60606

USER NAME = #USER#
FILE NAME = #FILENAME#
PLOT SCALE = #SCALE#
PLOT DATE = 5/7/2009

DESIGNED - DM
DRAWN - MS
CHECKED - DS
DATE - 5/08/09

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

CONGRESS PARKWAY OVER SOUTH BRANCH OF THE CHICAGO RIVER
SUMMARY OF QUANTITIES

SCALE: SHEET NO. 7 OF 83 SHEETS STA. 377+01.00 TO STA. 382+45.28

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
389	2424-2B-R	COOK	398	7
CONTRACT NO. 60D61				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

Rev.