

PROJECT: FAP 389 - CONGRESS PARKWAY OVER SOUTH BRANCH OF CHICAGO RIVER - CONTRACT NO. 60D61 COOK COUNTY

X075-2A

SUMMARY OF QUANTITIES					CONSTRUCTION TYPE CODE				
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	URBAN	ROADWAY	ROADWAY LIGHTING	80% FED	80% FED	80% FED
					80% FED	80% FED	20% STATE	20% STATE	20% STATE
					1000	Y03D-1E			
X0326560	REPLACEMENT OF TRUNNION THRUST COLLAR ASSEMBLIES	EACH	16						16
X0326561	REPLACEMENT OF TRUNNION BEARING AND ANCHOR BOLTS	L SUM	1						1
X0326562	REFURBISHING OF LIVE LOAD BEARINGS	EACH	8						8
X0326563	SPAN BALANCE	L SUM	1						1
X0326546	TRAFFIC GATES	EACH	8						8
X0326565	REPLACEMENT OF BARRIER GATES	EACH	2						2
X0326566	REPLACEMENT OF SUMP PUMPS	EACH	4						4
X0326568	1600A MCB, 65KAIC, SWITCHBOARD	EACH	1						1
X0326569	EMERGENCY GENERATOR, 800KW, 0.8PF, 3PHASE, 4 WIRE, 480 VOLT	EACH	1						1
X0326570	WEATHERPROOF GENERATOR ENCLOSURE	EACH	1						1
X0326571	1600A 480Y/277 VOLT, 3PH, 4W AUTOMATIC TRANSFER SWITCH	EACH	1						1
X0326572	208/120V 3PH, 4W, 225AF MCB, 42-CIRCUIT PANEL, ⁶⁵ KAIC	EACH	2						2
X0326573	208/120V 3PH, 4W, 100AF MCB, 30-CIRCUIT PANEL, ⁶⁵ KAIC	EACH	2						2
X0326574	3HP, 480V VARIABLE FREQUENCY DRIVE	EACH	4						4
X0326575	NEMA 4X STAINLESS STEEL DOUBLE ENCLOSURE FOR 3 HP VARIABLE FREQUENCY DRIVES	EACH	2						2
X0326576	800A, 480Y/277V, 3PH, 4W, 65KAIC, (6) 20 INCH SECTIONS MOTOR CONTROL CENTER WITH MISC. CONTROLS AND BREAKERS	EACH	2						2
X0326577	ELECTRIC CABLE ASSEMBLY IN CONDUIT, 600V (EPR-TYPE TC) 3/C NO. 10 AND NO. 12 GROUND	FOOT	2,008						2,008
X0326578	ELECTRIC CABLE ASSEMBLY IN CONDUIT, 600V (EPR-TYPE TC) 4/C NO. 6 AND NO. 8 GROUND	FOOT	40						40
X0326579	ELECTRIC CABLE ASSEMBLY IN CONDUIT, 600V (EPR-TYPE TC) 3/C NO. 4 AND NO. 8 GROUND	FOOT	45						45
X0326580	ELECTRIC CABLE ASSEMBLY IN CONDUIT, 600V (EPR-TYPE TC) 3/C NO. 1/0 AND NO. 6 GROUND	FOOT	374						374
X0326581	ELECTRIC CABLE ASSEMBLY IN CONDUIT, 600V (EPR-TYPE TC) 4/C NO. 1/0 AND NO. 4 GROUND	FOOT	45						45
X0326582	ELECTRIC CABLE ASSEMBLY IN CONDUIT, 600V (EPR-TYPE TC) 3/C NO. 2/0 AND NO. 4 GROUND	FOOT	824						824
X0326583	ELECTRIC CABLE ASSEMBLY IN CONDUIT, 600V (EPR-TYPE TC) 4/C NO. 4/0 AND NO. 2 GROUND	FOOT	150						150
X0326584	ELECTRIC CABLE ASSEMBLY IN CONDUIT, 600V (EPR-TYPE TC) 3/C-250kcm AND NO. 2 GROUND	FOOT	883						883
X0326585	ELECTRIC CABLE ASSEMBLY IN CONDUIT, 600V (EPR-TYPE TC) 3/C-350kcm AND NO. 2 GROUND	FOOT	971						971
X0326591	ELECTRIC CABLE ASSEMBLY IN CONDUIT, 600V (EPR-TYPE TC) 4/C-350kcm AND NO. 1/0 GROUND	FOOT	1,620						1,620
X0326586	PULL BOX ATTACHED TO STRUCTURE, AISI TYPE 316 STAINLESS STEEL NEMA 4X, 60"X60"X16" (HXWXD), FIRE RATED	EACH	1						1
X0326588	PULL BOX ATTACHED TO STRUCTURE, AISI TYPE 316 STAINLESS STEEL NEMA 4X, 48"X36"X20" (HXWXD)	EACH	3						3
X0326587	PULL BOX ATTACHED TO STRUCTURE, AISI TYPE 316 STAINLESS STEEL NEMA 4X, 36"X48"X16" (HXWXD)	EACH	3						3
X0326589	PULL BOX ATTACHED TO STRUCTURE, AISI TYPE 316 STAINLESS STEEL NEMA 4X, 36"X36"X36" (HXWXD)	EACH	1						1
X0326590	PULL BOX ATTACHED TO STRUCTURE, AISI TYPE 316 STAINLESS STEEL NEMA 4X, 24"X24"X16" (HXWXD)	EACH	2						2
X0326567	PULL BOX ATTACHED TO STRUCTURE, AISI TYPE 316 STAINLESS STEEL NEMA 4X, 16"X12"X6" (HXWXD)	EACH	8						8
X0326551	TERMINAL CABINET ATTACHED TO STRUCTURE, AISI TYPE 316 STAINLESS STEEL NEMA 4X, 48"X36"X20" (HXWXD) WITH HARDWARE	EACH	4						4
X0326614	TERMINAL CABINET ATTACHED TO STRUCTURE, AISI TYPE 316 STAINLESS STEEL NEMA 4X, 24"X24"X16" (HXWXD) WITH HARDWARE	EACH	2						2
X0326592	FLEXIBLE LIQUID TIGHT STAINLESS STEEL CONDUIT, 3/4" DIAMETER, 6 FOOT LENGTH	EACH	4						4
X0326593	FLEXIBLE LIQUID TIGHT STAINLESS STEEL CONDUIT, 1" DIAMETER, 6 FOOT LENGTH	EACH	32						32
X0326594	FLEXIBLE LIQUID TIGHT STAINLESS STEEL CONDUIT, 1-1/2" DIAMETER, 6 FOOT LENGTH	EACH	2						2
X0326595	FLEXIBLE LIQUID TIGHT STAINLESS STEEL CONDUIT, 2-1/2" DIAMETER, 6 FOOT LENGTH	EACH	6						6
X0326596	FLEXIBLE LIQUID TIGHT STAINLESS STEEL CONDUIT, 3" DIAMETER, 6 FOOT LENGTH	EACH	4						4
X0326605	GALVANIZED STEEL SLEEVE 1-1/2", INCLUDING CORING, PATCH, FIREPROOFING	EACH	12						12
X0326606	GALVANIZED STEEL SLEEVE 2", INCLUDING CORING, PATCH, FIREPROOFING	EACH	6						6

*Specialty Items

PB Americas, Inc.
230 WEST MONROE STREET,
SUITE 900
CHICAGO, IL. 60606

USER NAME = #USER#
FILE NAME = #FILENAME#
PLOT SCALE = #SCALE#
PLOT DATE = 5/7/2009

DESIGNED - DM
DRAWN - MS
CHECKED - DS
DATE - 5/08/09

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

CONGRESS PARKWAY OVER SOUTH BRANCH OF THE CHICAGO RIVER
SUMMARY OF QUANTITIES

SCALE: SHEET NO. 9 OF 83 SHEETS STA. 377+01.00 TO STA. 382+45.28

F.A.P. RTE. 389	SECTION 2424-2B-R	COUNTY COOK	TOTAL SHEETS 398	SHEET NO. 9
CONTRACT NO. 60D61				
FED. ROAD DIST. NO. 1 [ILLINOIS] FED. AID PROJECT				