

PROJECT: FAP 389 - CONGRESS PARKWAY OVER SOUTH BRANCH OF CHICAGO RIVER - CONTRACT NO. 60D61 COOK COUNTY

X075-2A

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE				
CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY	ROADWAY LIGHTING			
				80% FED 20% STATE 1000	80% FED 20% STATE Y030-1E	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE
* X0326496	TOGGLE SWITCH 20AMP	EACH	14					14
* X0326497	600W 120V DIMMER	EACH	2					2
* X0326498	GFCI 20 AMP DUPLEX RECEPTACLE	EACH	47					47
X0326499	BRIDGE TEMPORARY POWER AND CONTROLS DURING CONSTRUCTION	L SUM	1					1
X0326500	BRIDGE OPERATION AND MAINTENANCE DURING CONSTRUCTION	L SUM	1					1
* X0326503	CCTV SYSTEM	L SUM	1					1
* X0326618	ADDRESSABLE FIRE ALARM SYSTEM	L SUM	1					1
* X0326501	ACCEPTANCE TESTING	L SUM	1					1
80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1					1
80400100	ELECTRIC SERVICE INSTALLATION	EACH	1					1
X0326504	FIBER OPTIC CABLE, SINGLE MODE	L SUM	1					1
X0326502	FIBER OPTIC SPLICE	L SUM	1					1
X0326505	CONTROL CABLES, CONDUITS, AND RACEWAY SYSTEM	L SUM	1					1
X0326506	ELECTRIC CABLE ASSEMBLY IN CABLE, 600V (SUBMERSIBLE) 16/C NO. 8 AND NO. 10 GROUND (CABLE A)	FOOT	475					475
X0326507	ELECTRIC CABLE ASSEMBLY IN CABLE, 600V (SUBMERSIBLE) 6/C - 250 KCMIL AND NO. 2 GROUND (CABLE B)	FOOT	475					475
X0326508	ELECTRIC CABLE ASSEMBLY IN CABLE, 600V (SUBMERSIBLE) 6/C NO. 8, 16/C NO. 6 AND NO. 10 GROUND (CABLE C)	FOOT	475					475
X0326509	ELECTRIC CABLE ASSEMBLY IN CABLE, 600V (SUBMERSIBLE) 3/C NO. 1/0, 3/C NO. 4/0 AND NO. 4 GROUND (CABLE D)	FOOT	475					475
X0326510	ELECTRIC CABLE ASSEMBLY IN CABLE, 600V (SUBMERSIBLE) 3/C NO. 4/0 AND NO. 4 GROUND (CABLE E)	FOOT	475					475
X0326511	ELECTRIC CABLE ASSEMBLY IN CABLE, 600V (SUBMERSIBLE) 6/C - 250 KCMIL AND NO. 2 GROUND (CABLE F)	FOOT	475					475
X0326512	ELECTRIC CABLE ASSEMBLY IN CABLE, 600V (SUBMERSIBLE) 22/C NO. 8 AND NO. 10 GROUND (CABLE G)	FOOT	475					475
X0326513	ELECTRIC CABLE ASSEMBLY IN CABLE, 600V (SUBMERSIBLE) 18/C NO. 6, 3/C NO. 4/0 AND NO. 4 GROUND (CABLE H)	FOOT	475					475
X0326514	ELECTRIC CABLE ASSEMBLY IN CABLE, 600V (SUBMERSIBLE) 54/C NO. 10, 13/C NO. 8 AND 13/C NO. 4 (CABLE C99)	FOOT	475					475
* X0326515	ELECTRIC CABLE ASSEMBLY IN CABLE, 600V (SUBMERSIBLE) 25/C NO. 12 TSP, 2/C NO. 18 AND 3 COAX RG6 (CABLE C100)	FOOT	475					475
X0326516	ELECTRIC CABLE ASSEMBLY IN CABLE, 600V (SUBMERSIBLE) 25/C NO. 12 TSP, 2/C NO. 18 AND 3 COAX RG6 (CABLE C294)	FOOT	475					475
X0326517	ELECTRIC CABLE ASSEMBLY IN CABLE, 600V (SUBMERSIBLE) 56/C NO. 10, 9/C NO. 8 AND 6/C NO. 4 (CABLE C294)	FOOT	475					475
X0326518	ELECTRIC CABLE ASSEMBLY IN CABLE, 600V (SUBMERSIBLE) FIBER OPTIC CABLE, 96 FIBER = 3 ^{NO.} 10 AWG	FOOT	475					475
X0326635	PERMANENT LIGHT POLE, ALUMINUM, TRANSFORMER BASE, M.H. TO MATCH EXISTING, 3 FT. DAVIT ARM - TWIN	EACH	3			3		
X0326636	LUMINAIRE, HIGH PRESSURE SODIUM VAPOR, HORIZONTAL MOUNT, 200 WATT WITH REFRACTOR	EACH	18			18		
X0326637	BRIDGE LTG LIGHT POLE, ALUMINUM, TRANSFORMER BASE, 47.5 FT. M.H., 3 FT. DAVIT ARM - TWIN	EACH	6			6		
X0326638	MOUNTING BRACKET- TRAFFIC SIGNAL POLE TO EXISTING STRUCTURE	EACH	2	2				
X0326639	MOUNTING BRACKET- TEMPORARY LIGHTING POLE TO EXISTING STRUCTURE	EACH	9	9				
X0326640	MOUNTING BRACKET- PERMANENT LIGHTING POLE TO EXISTING STRUCTURE	EACH	3	3				

*Specialty Items