

# SUMMARY OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(57-22)BR-2	MCLEAN	42	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT	CONTRACT NO. 70671	

**X071-2A**  
**RURAL**  
**STA. 1035+00 TO STA. 1043+00**  
**100% FED.**  
**TOTAL**  
**QUANTITY**

CODE NO.	DESCRIPTION	UNIT	QUANTITY
20400800	FURNISHED EXCAVATION	CU YD	25.0
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	39.0
28000400	PERIMETER EROSION BARRIER	FOOT	120.0
28000500	INLET AND PIPE PROTECTION	EACH	2.0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	364.0
40603245	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N105	TON	174.0
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N105	TON	140.0
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	277.0
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	54.0
44000196	HOT-MIX ASPHALT SURFACE REMOVAL, SPECIAL	SQ YD	954.0
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	1,431.0
44000700	APPROACH SLAB REMOVAL	SQ YD	267.0
48101200	AGGREGATE SHOULDERS, TYPE B	TON	32.0
48203100	HOT-MIX ASPHALT SHOULDERS	TON	81.0
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1.0
50102400	CONCRETE REMOVAL	CU YD	30.1
50104650	SLOPE WALL REMOVAL	SQ YD	120.0
50200100	STRUCTURE EXCAVATION	CU YD	39.0
50300225	CONCRETE STRUCTURES	CU YD	26.1
50300255	CONCRETE SUPERSTRUCTURE	CU YD	260.0
50300260	BRIDGE DECK GROOVING	SQ YD	1,058.0
50300300	PROTECTIVE COAT	SQ YD	1,293.0
50500305	ERECTING STRUCTURAL STEEL	L SUM	1.0
50500505	STUD SHEAR CONNECTORS	EACH	4,500.0
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	63,740.0
50800515	BAR SPLICERS	EACH	88.0
51100300	SLOPE WALL 6 INCH	SQ YD	120.0
51500100	NAME PLATES	EACH	1.0
52100210	ERECTING ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	12.0
52100220	ERECTING ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	6.0
			<b>RURAL</b>