

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 100% STATE				
X0321772	PRECAST CONCRETE PAVEMENT SLABS 10"	SO FT	14016	14016				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	390	390				
25200110	SODDING, SALT TOLERANT	SO YD	390	390				
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SO YD	125	125				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	131	131				
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2798	2798				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	393	393				
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SO YD	1158	1158				
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	502	502				
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	15	15				
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	7731	7731				* SPECIALTY ITEM

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 100% STATE				
42101300	PROTECTIVE COAT	SO YD	1649	1649				
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SO YD	125	125				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	225	225				
42400800	DETECTABLE WARNINGS	SO FT	75	75				
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	250	250				
44000600	SIDEWALK REMOVAL	SO FT	225	225				
44003100	MEDIAN REMOVAL	SO FT	230	230				
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SO FT	70326	70326				
X440	PARTIAL DEPTH REMOVAL 3"	SO YD	2985	2985				
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SO YD	1509	1509				
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SO YD	344	344				
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SO YD	1347	1347				
44201299	DOWEL BARS 1 1/2"	EACH	4210	4210				
44213204	TIE BARS 3/4"	EACH	466	466				
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	2129	2129				* SPECIALTY ITEM
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	1713	1713				

FILE NAME :	USER NAME : delfin	DESIGNED -	REVISED -
PROJECT :	DATE :	DRAWN -	REVISED -
PLOT SCALE : 100,000' / 1"	CHECKED -	REVISED -	REVISED -
PLOT DATE : 6/13/2014	DATE -	REVISED -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**US RTE. 30 (LINCOLN HWY.) (CICERO AVE. TO WESTERN AVE.)
SUMMARY OF QUANTITIES**

F.A.P. RTE. 353	SECTION 23R-RS	COUNTY COOK	TOTAL SHEETS 66	SHEET NO. 3
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

Rev.