

URBAN

URBAN

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE 0005			
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	1340	1340			
* 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	2950	2950			
* 88600100	DETECTOR LOOP, TYPE I	FOOT	318	318			
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	2726	2726			
* 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	90	90			
K1004595	PRUNING FOR SAFETY AND EQUIPMENT CLEARANCE	L SUM	1	1			
X0301242	PIEZO AXLE SENSOR, CLASS II	FOOT	44	44			
X2020110	GRADING AND SHAPING SHOULDERS	UNIT	345	345			
40800025	BITUMINOUS MATERIALS (PRIME COAT)	POUND	149309	149309			
X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	24812	24812			
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	31918	31918			
X4402020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	245	245			
X5537800	STORM SEWERS TO BE CLEANED 12"	FOOT	4500	4500			
XZ043900	PREFORMED JOINT FILLER REMOVAL	FOOT	24500	24500			

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE 0005			
Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	450	450			
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	336	336			
Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4			
Z0034105	MATERIAL TRANSFER DEVICE	TON	24809	24809			
Ø Z0076604	TRAINEES - TRAINING PROGRAM GRADUATE	HOUR	500	500			

FILE NAME :	USER NAME = mdrand	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES IL ROUTE 83 (KINGERY HIGHWAY) KNOLLWOOD ROAD TO IL ROUTE 56 (BUTTERFIELD ROAD)</b>			F.A.P. RATE:	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
C:\pwworking\mdrand\mod\mod\0316286\03211-111-plan.dgn		DRAWN -	REVISED -		344	543R-3-RS	DUPAGE	51	6			
PLOT SCALE = 100.0000' / 1"		CHECKED -	REVISED -		CONTRACT NO. 60N51			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				
PLOT DATE = 6/13/2014		DATE -	REVISED -		SCALE:	SHEET NO. OF SHEETS	STA. TO STA.					

\*SPECIALTY ITEMS

0042

REV.