URBAN

| SUMMARY OF QUANTITIES | | | | CONSTRUCTION TYPE CODE | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| CODE NO | ITEM | UNIT | TOTAL QUANTITIES | 100% STATE 0005 | | | | | |
| 20100110 | TREE REMOVAL (6 TO 15 UNITS DIAMETER) | UNIT | 150 | 150 | | | | | |
| 20100210 | TREE REMOVAL (OVER 15 UNITS DIAMETER) | UNIT | 150 | 150 | | | | | |
| 21101615 | TOPSOIL FURNISH AND PLACE, 4" | SQ YD | 1039 | 1039 | | | | | |
| 25200110 | SODDING, SALT TOLERANT | SQ YD | 1039 | 1039 | | | | | |
| 40600400 | MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS | TON | 321 | 321 | | | | | |
| 40600827 | POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50 | TON | 8963 | 8963 | | | | | |
| 40600895 | CONSTRUCTING TEST STRIP | EACH | 2 | 2 | | | | | |
| 40600982 | HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT | SQ YD | 869 | 869 | | | | | |
| 40600985 | PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT | SQ YD | 17 | 17 | | | | | |
| 40603153 | POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80 | TON | 5609 | 5609 | | | | | |
| 40603340 | HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70 | TON | 9297 | 9297 | | | | | |
| 42001300 | PROTECTIVE COAT | SQ YD | 1558 | 1558 | | | | | |

12

URBAN

| SUMMARY OF QUANTITIES | | | | CONSTRUCTION TYPE CODE | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| CODE NO | ITEM | UNIT | TOTAL QUANTITIES | 100% STATE 0005 | | | | | |
| 42300400 | PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH | SQ YD | 70 | 70 | | | | | |
| 44000158 | HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4" | SQ YD | 110117 | 110117 | | | | | |
| 44000160 | HOT-MIX ASPHALT SURFACE REMOVAL, 2 3/4" | SQ YD | 50076 | 50076 | | | | | |
| 44000200 | DRIVEWAY PAVEMENT REMOVAL | SQ YD | 320 | 320 | | | | | |
| 44201851 | CLASS D PATCHES, TYPE II, 17 INCH | SQ YD | 1650 | 1650 | | | | | |
| 44201855 | CLASS D PATCHES, TYPE III, 17 INCH | SQ YD | 265 | 265 | | | | | |
| 44201857 | CLASS D PATCHES, TYPE IV, 17 INCH | SQ YD | 825 | 825 | | | | | |
| 48102100 | AGGREGATE WEDGE SHOULDER, TYPE B | TON | 2241 | 2241 | | | | | |
| 60251740 | CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 24 FRAME AND GRATE | EACH | 10 | 10 | | | | | |
| 60253100 | CATCH BASINS TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID | EACH | 1 | 1 | | | | | |
| 60260100 | INLETS TO BE ADJUSTED | EACH | 12 | 12 | | | | | |
| 60300305 | FRAMES AND LIDS TO BE ADJUSTED | EACH | 1 | 1 | | | | | |
| 60406000 | FRAMES AND LIDS, TYPE 1, OPEN LID | EACH | 6 | 6 | | | | | |
| 60406100 | FRAMES AND LIDS, TYPE 1, CLOSED LID | EACH | 26 | 26 | | | | | |

14

* SPECIALTY ITEMS

| | | | |
|---|---|---|---|
| FILE NAME = | USER NAME = qurestiya | DESIGNED - | REVISED - |
| | | DRAWN - | REVISED - |
| | PLOT SCALE = 1000.0000 ' / in. | CHECKED - | REVISED - |
| | PLOT DATE = 6/14/2014 | DATE - | REVISED - |

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
F.A.P. 343/ IL 68 (DUNDEE RD.)--IL 59 (HAWTHORNE RD.) TO US 12

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 343 | (70 & 3045) RS-2 | COOK | 57 | 3 |

CONTRACT NO. 60T02

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT