

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				100% STATE
				ROADWAY 0005 RURAL
48101200	AGGREGATE SHOULDERS, TYPE B	TON	959	959
63500105	DELINEATORS	EACH	40	40
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8
67100100	MOBILIZATION	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	7769	7769
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	94	94
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	64365	64365
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	5497	5497
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	789	789
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	348	348
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	36	36
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	862	862
78006100	PREFORMED THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	78	78

14

* SPECIALTY ITEMS

FILE NAME *	USER NAME *	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\ps_work\pvidot\carpentard\10240331\366495-shr-cover.dgn	carpentardj	DRAWN -	REVISED -					332	(6, K-15)SIRS-3	KANKAKEE	16	4	
MODELNAME*	PLOT SCALE = 1/8" = 1'-0"	CHECKED -	REVISED -		SCALE:	SHEET	OF	SHEETS	STA.	TO STA.	CONTRACT NO. 66A95		
	PLOT DATE = 6/18/2014	DATE -	REVISED -								ILLINOIS FED. AID PROJECT		