

PAVEMENT MARKING SCHEDULE													
LOCATION	LENGTH	URETHANE PVMT MARK 4"		URETHANE PVMT MARK 6"	URETHANE PVMT MARK 8"	URETHANE PVMT MARK 12"		PREFORMED THERMO PVMT MARK 24"	PREFORMED THERMO PVMT MARK LETTERS & SYMB	RAISED REFLECT PVMT MARK REM	RAISED REFLECT PVMT MARK	SHORT TERM PVMT MARK	WORK ZONE PVMT MARK REM
		WHITE FOOT	YELLOW FOOT	YELLOW FOOT	WHITE FOOT	WHITE FOOT	YELLOW FOOT	WHITE FOOT	SQ FT	EACH	EACH	FOOT	SQ FT
481+38.38 TO 600+98.57	11960.19	23920.38		2990						151	151	3588	398
600+98.57 TO 622+26.19	2127.62	4255.24	5774		788.5	26	322	36	78	91	91	638	71
622+26.19 TO 732+49.78	11023.59	22047.18	5335	2477						139	139	3307	367
732+49.78 TO 740+37.83	788.05	1576.1	1457	30						11	11	236	26
SUB TOTAL		51798.9	12566			26	322						
TOTAL		64365		5497	789		348	36	78	392	392	7769	862

TEMPORARY PAVEMENT MARKING SCHEDULE									
LOCATION	LENGTH	TEMP PVMT MARK 4"		TEMP PVMT MARK 6"	TEMP PVMT MARK 8"	TEMP PVMT MARK 12"		TEMP PVMT MARK 24"	TEMP PVMT MARK LETTERS & SYMB
		WHITE FOOT	YELLOW FOOT	YELLOW FOOT	WHITE FOOT	WHITE FOOT	YELLOW FOOT	WHITE FOOT	SQ FT
481+38.38 TO 600+98.57	11960.19	23920.38		2990					
600+98.57 TO 622+26.19	2127.62	4255.24	5774		789	26	322	36	94
622+26.19 TO 732+49.78	11023.59	22047.18	5335	2477					
732+49.78 TO 740+37.83	788.05	1576.1	1457	30					
SUB TOTAL		51798.9	12566	5497		26	322	36	
PROJECT TOTAL		64365		5497	789		348	36	94

MAINLINE SCHEDULE										
LOCATION	LENGTH	PVMT AREA	HMA SURF CSE	LEVEL BINDER (MM)	HMA SURF REM 2 1/4"	TEMP RAMP	BIT MAT (PR CT)	MIX FOR CRACKS, JOINTS & FLGWYS	LEVEL BINDER (HM)	AGG SHLD TY B
STA TO STA	FOOT	SQ YD	TON	TON	SQ YD	SQ YD	POUNDS	TON	TON	TON
481+38.38 TO 600+99	11960.62	29237.1	2455.9	1228.0	29237.1	12.2	19735	8.77	14.62	454.1
600+99 TO 603+29	230	856.1	71.9	36.0	856.1		578	0.26	0.43	8.7
603+29 TO 608+41	512	2161.8	181.6	90.8	2161.8		1459	0.65	1.08	19.4
608+41 TO 609+79	138	582.7	48.9	24.5	582.7		393	0.17	0.29	5.2
609+79 TO 610+79	100	333.3	28.0	14.0	333.3		225	0.1	0.17	3.8
610+79 TO 613+24	245	816.7	68.6	34.3	816.7		551	0.25	0.41	9.3
613+24 TO 617+59	435	1836.7	154.3	77.1	1836.7		1240	0.55	0.92	16.5
617+59 TO 621+10	351	1170.0	98.3	49.1	1170.0		790	0.35	0.59	13.3
621+10 TO 622+10	100	322.2	27.1	13.5	322.2		217	0.1	0.16	3.8
622+10 TO 731+50	10940	26742.2	2246.3	1123.2	26742.2		18051	8.02	13.37	415.3
731+50 TO 732+50	100	244.4	20.5	10.3	244.4		165	0.07	0.12	3.8
HISTORICAL MARKER	145	193.3	16.2	8.1	193.3		130			5.5
732+50 TO 739+00	650	1877.8	157.7	78.9	1877.8		1268	0.56	0.94	
739+00 TO 740+37.83	137.83	482.4	40.5	20.3	482.4	20.6	326	0.14	0.24	
TOTAL			5616	2808	66857	33	45128	20	33	959