

**MAINLINE PAVING SCHEDULE**

STA. TO STA.	LENGTH	MAINLINE		HMA SURF	HMA POLY	HMA LEVEL	HMA LEVEL	BIT MAT	MIX JTS	TEMP	AGG SHLDR
		WIDTH	AREA	REMOVAL	SURF CSE	BINDER (MM)	BINDER (HM) N50	PRIME	CRACKS. &	RAMP	TY B
		FT	SQ YD	2 1/4"	MIX D N70	IL 9.5 FG, N70	IL 9.5 FG, N70	COAT	FLANGEWAYS	SQ YD	TON
5+58 TO 10+31	479.0	28 - 36	1703.1	1703.1	143.1	71.5	0.9	1149.6	0.5	33.3	22.9
10+31 TO 12+54	223.0	36.0	892.0	892.0	74.9	37.5	0.4	602.1	0.3	194.5	10.7
12+54 TO 15+42 (COUNCIL RD)	288.0	36 - 50	1376.0	1376.0	115.6	57.8	0.7	928.8	0.4	366.7	13.8
15+42 TO 16+87	145.0	50.0	805.6	805.6	67.7	33.8	0.4	543.8	0.2		6.9
16+87 TO 18+87	200.0	50 - 40	1000.0	1000.0	84.0	42.0	0.5	675.0	0.3		9.6
18+87 TO 20+38	151.0	40 - 46	721.4	721.4	60.6	30.3	0.4	486.9	0.2		7.2
20+38 TO 23+96	358.0	varies	2675.0	2675.0	224.7	112.4	1.3	1805.6	0.8	41.7	17.1
23+96 TO 26+17 (UNYTITE DR)	221.0	varies	1949.0	1949.0	163.7	81.9	1.0	1315.6	0.6	827.8	10.6
26+17 TO 27+20	103.0	90.0	1030.0	1030.0	86.5	43.3	0.5	695.3	0.3		4.9
27+20 TO 29+50	230.0	90 - 84	2223.3	2223.3	186.8	93.4	1.1	1500.7	0.7		11.0
<b>SOUTHBOUND LANE</b>											
29+50 TO 32+80	330.0	24.0	880.0	880.0	73.9	37.0	0.4	594.0	0.3		13.2
32+80 TO 35+30	250.0	24 - 36	833.3	833.3	70.0	35.0	0.4	562.5	0.2		10.0
35+30 TO 36+01	71.0	36.0	284.0	284.0	23.9	11.9	0.1	191.7	0.1		2.8
36+01 TO 36+57	56.0	36 - 46	255.1	255.1	21.4	10.7	0.1	172.2	0.1		2.2
36+57 TO 37+27	70.0	46.0	357.8	357.8	30.1	15.0	0.2	241.5	0.1		2.8
37+27 TO 39+52 (MAY RD / TR283)	225.0	varies	917.8	917.8	77.1	38.5	0.5	619.5	0.3	238.9	
39+52 TO 40+08	56.0	26 -36	192.9	192.9	16.2	8.1	0.1	130.2	0.1		0.9
40+08 TO 40+78	78.0	36.0	312.0	312.0	26.2	13.1	0.2	210.6	0.1		1.2
40+78 TO 43+23 (I-80 WB ON RAMP)	245.0	varies	889.5	889.5	74.7	37.4	0.4	600.4	0.3	244.4	3.9
43+23 TO 47+18.2	395.2	24.0	1053.9	1053.9	88.5	44.3	0.5	711.4	0.3	33.3	6.3
BRIDGE OMISSION SN 050-0077 & 050-0078	218.0									66.7	3.5
49+36.4 TO 49+71	34.6	24.0	92.3	92.3	7.8	3.9	0.0	62.3	0.0		0.6
49+71 TO 52+21	250.0	24 -36	833.3	833.3	70.0	35.0	0.4	562.5	0.2		4.0
52+21 TO 54+14	193.0	36.0	772.0	772.0	64.8	32.4	0.4	521.1	0.2		3.1
54+14 TO 56+44 (I-80 EB OFF RAMP)	230.0	varies	810.5	810.5	68.1	34.0	0.4	547.1	0.2	455.6	
56+44 TO 67+81	1137.0	24.0	3032.0	3032.0	254.7	127.3	1.5	2046.6	0.9		18.1
67+81 TO 70+14	233.0	24 - 48	932.0	932.0	78.3	39.1	0.5	629.1	0.3		3.7
70+14 TO 71+14	100.0	48.0	533.3	533.3	44.8	22.4	0.3	360.0	0.2		1.6
71+14 TO 73+87 (38th STREET)	273.0	varies	1024.7	1024.7	86.1	43.0	0.5	691.7	0.3	318.9	
73+87 TO 87+58	1371.0	24.0	3656.0	3656.0	307.1	153.6	1.8	2467.8	1.1	33.3	21.9
87+58 TO 89+23	165.0	24 - 48	660.0	660.0	55.4	27.7	0.3	445.5	0.2		2.6
89+23 TO 91+90	267.0	48.0	1424.0	1424.0	119.6	59.8	0.7	961.2	0.4		4.3
91+90 TO 94+92 (WENZEL RD)	302.0	varies	1808.7	1808.7	151.9	76.0	0.9	1220.9	0.5	202.8	
94+92 TO 108+32	1340.0	48 - 50	7295.6	7295.6	612.8	306.4	3.6	4924.5	2.2		21.4
108+32 TO 110+23	191.0	24 - 36	636.7	636.7	53.5	26.7	0.3	429.8	0.2		3.0
110+23 TO 111+29.7	88.7	36.0	354.8	354.8	29.8	14.9	0.2	239.5	0.1		1.4
111+29.7 TO 113+98 (MIDWAY RD)	268.3	varies	2020.3	2020.3	169.7	84.9	1.0	1363.7	0.6	652.9	4.3
113+98 TO 119+17.7	519.7	24.0	1385.9	1385.9	116.4	58.2	0.7	935.5	0.4	33.3	
119+00 TO 136+00	1700.0	24.0	4533.3	4533.3	380.8	190.4	2.3	3060.0	1.4		27.1
136+00 TO 138+00	200.0	24 - 26	555.6	555.6	46.7	23.3	0.3	375.0	0.2		3.2
138+00 TO 141+21	321.0	26.0	927.3	927.3	77.9	38.9	0.5	626.0	0.3		5.1
141+21 TO 144+68	347.0	48 - 26	1426.6	1426.6	119.8	59.9	0.7	963.0	0.4		5.5
144+68 TO 147+09	241.0	48.0	1285.3	1285.3	108.0	54.0	0.6	867.6	0.4		3.8
147+09 TO 149+78 (SHOOTING PARK RD)	269.0	varies	2210.0	2210.0	185.6	92.8	1.1	1491.8	0.7	377.6	4.3
149+78 TO 178+50	2872.0	24.0	7658.7	7658.7	643.3	321.7	3.8	5169.6	2.3	33.3	45.8
178+50 TO 193+22	1472.0	12.0	1962.7	1962.7	164.9	82.4	1.0	1324.8	0.6	36.1	23.5
<b>TOTALS</b>			<b>68183.2</b>	<b>68183.2</b>	<b>5727.4</b>	<b>2863.7</b>	<b>34.1</b>	<b>46023.6</b>	<b>20.5</b>	<b>4191.1</b>	<b>369.7</b>