

RESURFACING SCHEDULE								
LOCATION		APPROX LENGTH	WIDTH	HMA SURF REM 2"	HMA SURF CSE	BIT MAT (PR CT)	MIX FOR CRACKS, JOINTS & FLGWYS	LEVEL BINDER (HM)
LOG MI		FOOT	FOOT	SQ YD	TON	LB	TON	TON
LOCATION 1 (US 45/52 WILL CO. LINE)								
0.0 TO 3.0	NB & SB LANES	15840	24	42240	4730.9	19008.0	12.67	21.12
SUBTOTAL 1				42240	4730.9	19008.0	12.67	21.12
LOCATION 2 (IL 114)								
0.2 TO 0.7	EB DRIVING LANE	2640	12	3520	394.2	1584.0	1.06	1.76
0.2 TO 0.7	WB DRIVING LANE	2640	13	3813	427.1	1716.0	1.14	1.91
0.8	EB DRIVING LANE	50	12	67	7.5	30.0	0.02	0.03
0.9	EB EOP	50	2	11	1.2	5.0	0	0.01
1.2 TO 1.3	WB EOP	528	2	117	13.1	52.8	0.04	0.06
1.2 TO 1.3	EB EOP	528	2	117	13.1	52.8	0.04	0.06
1.9 TO 2.1	CENTERLINE	1056	2	235	26.3	105.6	0.07	0.12
2.2	WB DRIVING LANE	50	12	67	7.5	30.0	0.02	0.03
2.9	WB DRIVING LANE	50	12	67	7.5	30.0	0.02	0.03
3.8 TO 3.9	CENTERLINE	528	2	117	13.1	52.8	0.04	0.06
4.7 TO 4.8	CENTERLINE	528	2	117	13.1	52.8	0.04	0.06
5.4 TO 5.5	CENTERLINE	528	2	117	13.1	52.8	0.04	0.06
5.6 TO 5.7	EB EOP	528	2	117	13.1	52.8	0.04	0.06
5.9 TO 6.0	CENTERLINE	528	2	117	13.1	52.8	0.04	0.06
6.4 TO 6.5	EB EOP	528	2	117	13.1	52.8	0.04	0.06
6.9	EB DRIVING LANE	50	12	67	7.5	30.0	0.02	0.03
7.0	WB DRIVING LANE	50	12	67	7.5	30.0	0.02	0.03
7.1 TO 7.2	WB EOP	528	2	117	13.1	52.8	0.04	0.06
7.3 TO 7.4	EB DRIVING LANE	528	12	704	78.8	316.8	0.21	0.35
7.3 TO 7.4	WB DRIVING LANE	528	12	704	78.8	316.8	0.21	0.35
SUBTOTAL 2				10375	1161.8	4669.4	3.15	5.19
TOTAL				52615	5892.7	23677.4	15.82	26.31

NOTE: NO CONSTRUCTION ACTIVITIES SHALL TAKE PLACE WITHIN 50 FEET OF ANY RAILROAD TRACKS

PAVEMENT MARKING															
LOCATION	PAINT PAVEMENT MARKING LINE				MODIFIED URETHANE MARKING LINE					RAISED REFL PVMT MARKER REMOVAL	RAISED REFL PVMT MARKER	SHORT TERM PAVEMENT MARKING	WORK ZONE PAVEMENT REMOVAL		
	4 INCH		6 INCH		4 INCH		6 INCH		24 INCH					LETTERS	
	YELLOW	WHITE	YELLOW	WHITE	YELLOW	WHITE	WHITE	YELLOW	WHITE					& SYMBOLS	
STA	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	EACH	EACH	FOOT	SQ FT		
LOCATION 1 (US 45/52 WILL CO. LINE)		63360		7920							198		1584	528	
LOCATION 2 (IL 114)					4802	10332		2319	96	234.9	83		450	150	
	0	63360		7920	4802	10332	0	2319	96	234.9	281		2034	678	
TOTALS		63360		7920	15134			2319	96	234.9	281		198	2034	678

NOTE: ADDITIONAL QUANTITY HAS BEEN INCLUDED TO ALLOW FOR TWO SEPARATE APPLICATIONS OF PAINT PAVEMENT MARKING LINE

SIDEWALK SCHEDULE					
LOCATION	SIDEWALK REMOVAL	PCC SIDEWALK 4"	COMB C&G REM	COMBINATION CC&G TYPE B-6.24	DETECTABLE WARNINGS
STREET	SQ FT	SQ FT	FT	FT	SQ FT
LOCATION 2 (IL 114)	400	400	64	64	80
TOTALS	400	400	64	64	80