

LOCATION OF WORK:	FAP 704 (I-55BUSN/VET'S PKWY)	S. N. 057-0063	S. N. 057-0064
	URBAN MULTILANE	URBAN MULTILANE	URBAN MULTILANE
	OTHER PRINCIPAL ARTERIAL	OTHER PRINCIPAL ARTERIAL	OTHER PRINCIPAL ARTERIAL
	STA. 33+30 TO STA. 89+41.79	STA. 47+06.97 TO STA. 49+10.79	STA. 72+79.68 TO STA. 75+96.94
	MCLEAN COUNTY	MCLEAN COUNTY	MCLEAN COUNTY
FUNDING BREAKOUT:	100% STATE	100% STATE	100% STATE
CONSTRUCTION TYPE CODE:	0004	0014	0014

CODE NO.	ITEM	UNIT	TOTAL QUANTITY		
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	514.8	514.8	0.0
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	50,580.0	50,580.0	0.0
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	740.0	740.0	0.0
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	3,235.0	3,235.0	0.0
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	760.0	760.0	0.0
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	100.0	100.0	0.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	22,230.0	22,230.0	0.0
• 78003100	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS AND SYMBOLS	SQ FT	514.8	514.8	0.0
• 78004210	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 4"	FOOT	4,720.0	4,720.0	0.0
• 78009004	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	45,860.0	43,510.0	920.0
• 78009006	MODIFIED URETHANE PAVEMENT MARKING - LINE 6"	FOOT	740.0	740.0	0.0
• 78009008	MODIFIED URETHANE PAVEMENT MARKING - LINE 8"	FOOT	3,235.0	3,235.0	0.0
• 78009012	MODIFIED URETHANE PAVEMENT MARKING - LINE 12"	FOOT	760.0	760.0	0.0
• 78009024	MODIFIED URETHANE PAVEMENT MARKING - LINE 24"	FOOT	100.0	100.0	0.0

• DENOTES SPECIALTY ITEM

FILE NAME *	USER NAME = dodgens	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEET NO.
c:\p\work\pvidot\dodgens\08267571\0570938-ahc-500.dgn	DESIGNED -	REVISED -	704					(57-7)RS-1&IRS-3	McLean	273	12
MODELNAME*	PLOT SCALE = 42.0000 ' / in.	CHECKED -	REVISED -		SCALE:	SHEET 6	OF 10 SHEETS	STA.	TO STA.	CONTRACT NO. 70838	
	PLOT DATE = 6/11/2014	DATE -	REVISED -		ILLINOIS FED. AID PROJECT						