

# SCHEDULE OF QUANTITIES

## PAVEMENT MARKING (SHEET 2 OF 2)

### MODIFIED URETHANE PAVEMENT MARKING, 6"

DIRECTION	LOCATION	MODIFIED URETHANE PAVEMENT MARKING LINE 6 78009006 (FOOT)	GROOVING FOR RECESSED PAVEMENT MARKING 7" X7830074 (FOOT)
LEG "A": FOX CR. RD. - HAMILTON RD. INTERSECTION			
WB	EAST SIDE ISLAND	80.0	80.0
WB	EAST SIDE X-WALKS	175.0	175.0
WB	WEST SIDE ISLAND	85.0	85.0
EB	WEST SIDE ISLAND	100.0	100.0
EB	EAST SIDE ISLAND	80.0	80.0
EB	EAST SIDE X-WALKS	70.0	70.0
	NE RAMP ISLAND:	30.0	30.0
	NW RAMP X-WALKS:	105.0	105.0
	SE RAMP ISLAND:	15.0	15.0
	TOTAL =	740.0	740.0
	ROUND TO:	740.0	740.0

### MODIFIED URETHANE PAVEMENT MARKING, 24"

DIRECTION	STATION	MODIFIED URETHANE PAVEMENT MARKING LINE 24 78009024 (FOOT)	GROOVING FOR RECESSED PAVEMENT MARKING 25" X7830090 (FOOT)
LEG "A":			
WB	19+06.75	55.0	55.0
EB	20+29	45.0	45.0
	TOTAL =	100.0	100.0
	ROUND TO:	100.0	100.0

### MODIFIED URETHANE PAVEMENT MARKING, 12"

DIRECTION	LOCATION	MODIFIED URETHANE PAVEMENT MARKING LINE 12 78009012 (FOOT)	GROOVING FOR RECESSED PAVEMENT MARKING 13" X7830078 (FOOT)
LEG "A": FOX CR. RD. - HAMILTON RD. INTERSECTION			
WB	EAST SIDE ISLAND	40.0	40.0
WB	EAST SIDE X-WALKS	305.0	305.0
WB	WEST SIDE ISLAND	65.0	65.0
EB	WEST SIDE ISLAND	40.0	40.0
EB	EAST SIDE ISLAND	55.0	55.0
EB	EAST SIDE X-WALKS	150.0	150.0
LT	NW RAMP X-WALKS:	105.0	105.0
	TOTAL =	760.0	760.0
	ROUND TO:	760.0	760.0

### MODIFIED URETHANE PAVEMENT MARKING, 8"

DIRECTION	STATION	TO	STATION	LENGTH (FEET)	MODIFIED URETHANE PAVEMENT MARKING LINE 8 78009008 (FOOT)	GROOVING FOR RECESSED PAVEMENT MARKING 9" X7830076 (FOOT)
LEG "C":						
WB	38+14		41+65	351.0	351.0	351.0
WB	53+35		57+80	445.0	445.0	445.0
EB	36+67		40+59	392.0	392.0	392.0
EB	55+23		59+55	432.0	432.0	432.0
NE RAMP:						
LT	12+63		17+08	445.0	445.0	445.0
NW RAMP:						
LT	16+50		20+00	350.0	350.0	350.0
SW RAMP:						
LT	12+73		16+62.9	389.9	389.9	389.9
SE RAMP:						
LT	17+80		22+07	427.0	427.0	427.0
	TOTAL =			3231.9	3231.9	3231.9
	ROUND TO:			3235.0	3235.0	3235.0

### PREFORMED PLASTIC PAVEVENT MARKING, TYPE B - INLAID - 4"

DIRECTION	DESCRIPTION	STATION	TO	STATION	LENGTH (FEET)	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 4 78004210 (FOOT) C.L.	RAISED REFLECTIVE PAVEMENT MARKERS 78100100 (EACH)
LEG "A" CL:							
WB	CL	29+70		20+26	944.0	236.0	24.0
WB	CL	19+05		18+75	30.0	7.5	2.0
WB	CL	335+55.87		366+35.33	3079.46	769.9	78.0
EB	CL	43+70		33+30	1040.0		26.0
EB	CL	33+30		20+31	1299.0	324.8	34.0
FOX CR.-HAMILTON RD. INTERSECTION:							
EB	CL	19+13		18+75	38.0	9.5	2.0
EB	CL	335+55.87		366+35.20	3079.33	769.8	78.0
LEG "C" CL:							
WB	CL	32+32.06		47+06.97	1474.91	368.7	38.0
WB	CL	49+10.79		72+70.53	2359.74	589.9	60.0
WB	CL	75+88.67		87+41.66	1152.99	288.2	30.0
WB	CL	87+45.84		89+41.79	195.95	49.0	6.0
WB	CL	89+41.79		99+81.79	1040.0		26.0
EB	CL	32+26.74		47+06.97	1480.23	370.1	38.0
EB	CL	49+10.79		72+89.02	2378.23	594.6	60.0
EB	CL	76+05.90		87+41.66	1135.76	283.9	30.0
EB	CL	87+45.84		89+40.28	194.44	48.6	6.0
LEG "A" TURN LANES:							
WB	LT. TURN	19+05		18+75	30		1.0
WB	LT. TURN	335+55.87		339+40.7	384.83		10.0
WB	RT. TURN	19+05		18+75	30		1.0
WB	RT. TURN	335+55.87		339+40.7	384.83		10.0
EB	LT. TURN	24+55		20+31	424		11.0
EB	RT. TURN	24+55		20+31	424		11.0
RAMP GORE AREAS:							
NE RAMP:							
LT	8" LINE	12+63		17+08	445.0		12.0
SW RAMP:							
LT	8" LINE	12+73		16+62.9	389.9		10.0
LEG "C" MAINLINE GORE AREAS							
WB	8" LINE	53+35		57+80	445.0		12.0
EB	8" LINE	36+67		40+59	392.0		10.0
SW RAMP RRPMS @ 20' ctrs.							
RT	EL	10+00		16+62.9	662.9		34.0
SW RAMP RRPMS @ 40' ctrs.							
LT	EL	16+62.9		18+20.17	157.27		4.0
NE RAMP RRPMS @ 20' ctrs.							
RT	EL	10+00		17+08	708.0		36.0
NE RAMP RRPMS @ 40' ctrs.							
LT	EL	17+08		18+79	171.0		5.0
NE RAMP LANE LINES							
LT.	OUT. LT. TURN	19+08		22+00	292.0		8.0
LT	IN. LT. TURN	17+20		21+86	466.0		12.0
	TOTAL =				4,710.5		725.0
	ROUND TO:				4,720.0		730.0