INDEX OF SHEETS

SHEET NO	DESCRIPTION
1	COVER SHEET
2	SIGNTURE SHEET
3	INDEX OF SHEETS, STANDARDS, AND MIX DESIGNS
4	GENERAL NOTES, COMMITMENTS
5-12	SUMMARY OF QUANTITIES
13	TYPICAL SECTIONS
14	PAVEMENT AND ENTRANCE SCHEDULES
15	SHOULDER SCHEDULE
16	DRAINAGE AND GUARDRAIL SCHEDULES
17	EARTHWORK AND SEEDING SCHEDULES
18	PAVEMENT MARKING SCHEDULE
19	REMOVAL QUANTITIES AND TREE REMOVAL SCHEDULE
20	EROSION CONTROL SCHEDULE
21	TEMPORARY DITCH CHECK SCHEDULE
22	PAVEMENT PATCHING SCHEDULE
23	MILLING & SUPERELEVATION RATES SCHEDULES AND DETAILS
24	GEOPAK - ALIGNMENT & PROFILE INFORMATION SHEET
25	HORIZONTAL AND VERTICAL CONTROL / TIES
26-29	PLAN AND PROFILE SHEET
30-33	EROSION CONTROL SHEETS
34	RIGHT OF WAY SHEETS
35-66	STRUCTURE PLANS
67	DETAILS - RURAL SIDE APPROACH DETAILS
68	DETAILS - BUTT JOINT, TEMPORARY DITCH CHECKS DETAILS OF CONCRETE COLLAR, ENERGY DISSAPATOR
69	DETAILS - TYPICAL CROSS SECTION SHOWING STEP CONSTRUCTION ON EXISTING FILL UNEVEN LANE SIGN (W8-11), ROUGH GROVED SURFACE SIGN (W8-[106) SEEDING - MULCHING CONTRACTS
70	DETAILS - SETTLEMENT PLATFORM DETAIL
71-112	CROSS SECTIONS
	HIGHWAY STANDARDS

LIST OF STANDARDS

000001-06 STANDARD SYMBOLS ABBREVIATIONS & PATTERNS
280001-07 TEMP EROSION CNTRL SYSTEMS
406201-01 MAILBOX TURNOUT
420001-07 PAVEMENT JOINTS
420401-10 BRIDGE APPROACH PVMT CONNECTOR
442201-03 CLASS C&D PATCHES
482001-02 HMA SHLD ADJ TO FLEX PVMT
515001-03 NAME PLATE FOR BRIDGES
542201-02 REINF CONC ENDSECT FOR PIPE CULV 15-36 IN DIA SKEWED
542301-03 PRECAST REINF CONC FLARED ENDSECT
542546-01 FLUSH INLET BOX FOR MEDIAN
542601-03 RC PIPE ELBOW
601101-01 CONC HDW FOR PIPE DRAIN
630001-10 STEEL PLATE BEAM GRDRAIL
630201-06 PCC-BIT STB @ STEEL PLATE BEAM GRDRAIL
630301-06 SHLD WIDEN FOR TYPE 1 GRDRAIL TERMS
631031-12 TRAF BAR TERM TYPE 6
635006-03 REFLECTOR & TERM MRKR PLACEMNT
635011-02 REFLECTOR MRKR & MOUNT DETAILS
642006 SHOULDER RUMBLE STRIPS 8 IN
666001-01 ROW MRKRS
667101-02 PERMANENT SURVEY MRKRS
701001-02 OFF RD OP- 2L2W - 15 FT MIN FROM EOP-45 MPH+
701006-05 OFF RD OP- 2L2W - 15 FT TO EOP-45 MPH+
701201-04 LN CLOSURE 2L2W - DAY ONLY
701301-04 LN CLOSURE 2L2W - SHORT TIME OP
701306-03 LN CLOSURE 2L2W - SLOW MOVE OP DAY ONLY 45 MPH+
701311-03 LN CLOSURE 2L2W - MOVING OP DAY ONLY
701326-04 LN CLOSURE 2L2W - PVMT WIDENING 45 MPH+
701901-03 TRAF CNTRL DEVICES
780001-04 TYPICAL PVMT MRKINGS
781001-03 TYPICAL APP RAISED REFLC PVMT MRKRS

HMA MIXTURE DESIGNS

Locations	Hot-Mix Asphalt Surface Course and Full Depth Pavement (Top Lift)
Mixture Use(s):	Hot-Mix Asphalt Surface Course, Mix D, N90
AC/PG:	PG64-22
ABR % (Max):	See Special Provision
Design Air Voids:	4.0 %, 90 Gyration Design
Mixture (Gradation Mixture)	IL-9.5 mm
Friction Aggregate:	D Surface
Quality Management Program:	QCP (Full Depth Pavement)

Locations	Hot-Mix Asphalt Binder Course, Full Depth Pavement (Lower Lifts), and Hot-Mix Asphalt Shoulders (Lower Lifts)
Mixture Use(s):	Hot-Mix Asphalt Binder Course, N90, IL-19.0mm Fine Grade
AC/PG:	PG64-22
ABR % (Max):	See Special Provision
Design Air Voids:	4.0 %, 90 Gyration Design
Mixture (Gradation Mixture)	IL-19.0mm Fine Grade
Friction Aggregate:	None
Quality Management Program:	QC/QA (Ton) QCP (Full Depth Pavement & Shoulders)

Locations	Hot-Mix Asphalt Shoulders (Top Lift)
Mixture Use(s):	Hot-Mix Asphalt Surface Course, Mix C, N90
AC/PG:	PG64-22
ABR % (Max):	See Special Provision
Design Air Voids:	4.0 %, 90 Gyration Design
Mixture (Gradation Mixture)	IL-9.5mm
Friction Aggregate:	C Surface
Quality Management Program:	QCP

INDEX OF SHEETS, STANDARDS AND MIX DESIGNS