

SUMMARY OF QUANTITIES - CONT

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	100% STATE	
				RURAL	
				FAP 42 IL 13 : 127 ROADWAY 0004	FAP 42 IL 13 : 127 SN 039-0009 0014
51202100	FURNISHING STEEL PILES HP14X117	FOOT	7775		7775
51202305	DRIVING PILES	FOOT	7775		7775
51204100	TEST PILE STEEL HP14X117	EACH	2		2
51204650	PILE SHOES	EACH	104		104
51500100	NAME PLATES	EACH	1		1
52100520	ANCHOR BOLTS, 1"	EACH	60		60
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	199	199	
542A0235	PIPE CULVERTS, CLASS A, TYPE 1 30"	FOOT	89	89	
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	44	44	
542D0229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	85	85	
54210190	PIPE ELBOW, 30"	EACH	1	1	
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	2	2	
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	1	1	
54215430	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 30"	EACH	1	1	

FILE NAME =	USER NAME = *USER*	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES: SHEET 5 OF 8	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
er:\work\p\d\l\ef\w\hd\1\2196163\78	15\p\h\c\cover*to.dgn	DRAWN -	REVISED -			42	13B-1	JACKSON	112	9	
	PLOT SCALE = 100.0000' / 1"	CHECKED -	REVISED -			CONTRACT NO. 78215					
MODEL NAME =	PLOT DATE = 6/18/2014	DATE -	REVISED -			ILLINOIS FED. AID PROJECT					