

# SHOULDER QUANTITIES

RTE 13 / 127 LOCATION STATION TO STATION		LENGTH (INFO ONLY)	SHLD NOTE	HMA SHLD 8	HMA SHLD	SUB GRAN MAT C	SHLD RUM STRIP 8"	BIT MATLS PR CT	
PROP	ALI	FEET	WIDTH	SQ YD	TON	TON		POUNDS	
LT SHLD									
207+35.00	TO 207+75.33	40.3			3		40.3	5	
207+75.33	BK = 577+31.15 AH	0.0							
577+31.15	TO 578+38.00	106.8	4' TO 6'	61		16	106.8	14	
578+38.00	TO 592+31.00	1393.0		929		228	1347.0	209	
592+31.00	TO 594+31.00	200.0	6' TO 10'	178		39	200.0	40	
594+31.00	TO 597+87.72	356.7		397		81	356.7	90	
597+87.72	TO 598+11.72	24.0	10' TO 14'	32		6	24.0	8	
598+11.72	TO 599+03.00	91.3		142		24	91.3	32	
599+03.00	TO 599+18.00	15.0		5		2		2	
599+18.00	TO 599+33.00	15.0							
599+33.00	TO 603+55.00	422.0							
603+55.00	TO 603+70.00	15.0							
603+70.00	TO 603+85.00	15.0		5		2		2	
603+85.00	TO 606+01.28	216.3		337		56	216.3	76	
606+01.28	TO 606+25.28	24.0	14' TO 10'	32		6	24.0	8	
606+25.28	TO 608+57.00	231.7		258		53	231.7	58	
608+57.00	TO 610+57.00	200.0	10' TO 6'	178		39	200.0	40	
610+57.00	TO 623+40.00	1283.0		856		210	1283.0	193	
623+40.00	TO 625+22.29	182.3	6' TO 4'	108		26	122.3	23	
625+22.29	BK = 255+61.48 AH	0.0							
255+61.48	TO 256+01.50	40.0			2		40.0	5	
RT SHLD									
207+35.00	TO 207+75.33	40.3			3		40.3	5	
207+75.33	BK = 577+31.15 AH	0.0							
577+31.15	TO 578+38.00	106.8	4' TO 6'				106.8	14	
578+38.00	TO 583+97.32	559.3			42		474.3	84	
583+97.32	TO 596+13.22	1215.9		818		199	1215.9	183	
596+13.22	TO 596+49.22	36.0	6' TO 10'	32		7	36.0	8	
596+49.22	TO 599+03.00	253.8		282		58	253.8	64	
599+03.00	TO 599+18.00	15.0		5		2		2	
599+18.00	TO 599+33.00	15.0							
599+33.00	TO 603+55.00	422.0							
603+55.00	TO 603+70.00	15.0							
603+70.00	TO 603+85.00	15.0		5		2		2	
603+85.00	TO 605+13.78	128.8		144		29	128.8	33	
605+13.78	TO 605+49.78	36.0	10' TO 6'	32		7	36.0	8	
605+49.78	TO 618+55.52	1305.7		878		213	1305.7	196	
618+55.52	TO 623+40.00	484.5			37		386.5	73	
623+40.00	TO 625+22.29	182.3	6' TO 4'		12		182.3	23	
625+22.29	BK = 255+61.48 AH	0.0							
255+61.48	TO 256+01.50	40.0			2		40.0	5	
<b>TOTALS</b>					<b>5714</b>	<b>108</b>	<b>1305</b>	<b>8490</b>	<b>1505</b>

\*\* SEE PAVEMENT SCHEDULE FOR ADDITIONAL QUANTITY

\*\*

FILE NAME =	USER NAME = \$USER\$	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SHOULDER SCHEDULE</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
et:\pw\work\p\dot\left\wchd\1\0196163\78215-shite-cover-etc.dgn		DRAWN -	REVISED -			42	13B-1	JACKSON	112	15	
\$MODELNAME\$		CHECKED -	REVISED -			CONTRACT NO. 78215		ILLINOIS FED. AID PROJECT			
		DATE -	REVISED -			SCALE:	SHEET	OF	SHEETS	STA.	TO