

## FAP 885 ( IL 146) PAVEMENT RESURFACING SCHEDULE

LOCATION STATION TO STATION			LENGTH	ROADWAY WIDTH	ROADWAY AREA	HOT-MIX ASP. SURF. REMOV. 2 1/4"	TEMP RAMP	HMA SURF. CSE., MIX C. N90 (1 1/2")	LEVELING BINDER (MM), IL-9.5mm N90 (1")	BIT. MAT. (PC)	
			FOR INFORMATIONAL PURPOSE ONLY								
			( FT )	( FT )	( SQ YD )	( SQ YD )	( SQ YD )	( TON )	( TON )	( LBS )	
FAP 885 ( IL 146) - STA. 593+00 to STA. 1266+10											
	593+00.00	TO	669+19.50	7619.5	26	22012	22012	30	1849	925	14858
	669+25.00	TO	669+42.00	17	26	49	49		5	3	33
	674+17.00	TO	692+91.00	1874	26	5414	5414	30	455	228	3654
RT	692+91.00	TO	694+82.00	191	19	393	393		33	17	265
RT	694+82.00	TO	697+06.00	224	24	597	597		51	26	403
RT	697+06.00	TO	697+54.00	48	18.5	99	99		9	5	67
RT	697+54.00	TO	703+00.00	546	13	789	789		67	34	533
LT	692+91.00	TO	694+50.00	159	19.5	345	345		29	15	291
LT	694+50.00	TO	701+68.00	718	26	2074	2074		175	88	1400
LT	701+68.00	TO	703+00.00	132	19.5	286	286		25	13	193
	703+00.00	TO	709+74.00	674	26	1947	1947	15	164	82	1315
	714+62.00	TO	815+90.00	10128	26	29259	29259	30	2458	1229	19750
	819+80.00	TO	876+10.50	5631	26	16266	16266	15	1367	684	10980
	876+20.00	TO	909+93.00	3373	26	9744	9744	15	819	410	6578
	917+08.00	TO	1252+45.00	33537	26	96885	96885	30	8139	4070	65397
	1255+71.00	TO	1259+59.50	389	26	1122	1122	15	95	48	758
	1260+26.20	TO	1260+74.00	48	26	138	138	15	12	6	93
	1262+42.00	TO	1266+10.00	368	26	1063	1063	30	90	45	718
<b>TOTALS</b>							<b>188,481</b>	<b>225</b>	<b>15842</b>	<b>7928</b>	<b>127286</b>