

# SUMMARY OF QUANTITIES

COUNTY:	WILLIAMSON	JOHNSON
ROUTE:	FAP 881 (US 45)	
FUNDING:	100% STATE	
LOCATION:	RURAL	
TOTAL QUANTITY	ROADWAY	
	0005	

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY		
40600647	LEVELING BINDER (MACHINE METHOD), IL-9, 5FG, N90	TON	2,381	963	1,418
40600990	TEMPORARY RAMP	SQ YD	160	40	120
40603320	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N90	TON	4,781	1,926	2,855
44000153	HOT-MIX ASPHALT SURFACE REMOVAL, 1"	SQ YD	327	0	327
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	66,149	26,748	39,401
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	400	160	240
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	85	34	51
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	160	64	96
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	42,524	17,195	25,329
48203100	HOT-MIX ASPHALT SHOULDERS	TON	1,191	481	710
64200108	SHOULDER RUMBLE STRIPS, 8 INCH	FOOT	42,524	17,195	25,329
67100100	MOBILIZATION	L SUM	1	0	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0	1
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	0	1

FILE NAME *	USER NAME * Stoverpg	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	P.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
z:\p\work\p\p\dot\stoverpg\d0387631784	7-ahc-plan.dgn	DRAWN -	REVISED -			881	34RS-6	v	13	5
	PLOT SCALE * 1/8"=1'-0"	CHECKED -	REVISED -		SCALE: _____					
	PLOT DATE * 6/12/2014	DATE -	REVISED -		SHEET NO. ___ OF ___ SHEETS					CONTRACT NO. 78417
					STA. _____ TO STA. _____					ILLINOIS FED. AID PROJECT