

RESURFACING SCHEDULE

LOCATION STATION TO STATION	LENGTH	HMA SURF REM, 1"	HMA SURF REM, 2 1/4"	LEVEL BIND (MM), IL-9, 5FG, N90	HMA SURF CSE, MIX "C", N90	MATERIAL TRANSFER DEVICE	HMA SHOULDERS	BIT MATL (PC)	TEMP RAMP	SHOULDER RUMBLE STRIP	RAISED REFLECTIVE PAVEMENT MARKER REM	RAISED REFLECTIVE PAVEMENT MARKERS	STRIP REFLECTIVE CRACK CONTROL
	FEET	SO YD	SO YD	TON	TON	TON	TON	POUND	SO YD	FOOT	EACH	EACH	FOOT
WILLIAMSON COUNTY													
743+38 TO 758+98.4	1560.40		4855	175	350	524	87	2809	40	3121	20	20	3121
EQUATION STATION													
758+97.7 TO 829+35	7037.30		21894	788	1576	2365	394	12667		14075	88	88	14075
WILLIAMSON COUNTY SUBTOTALS		0	26748	963	1926	2889	481	15476	40	17195	108	108	17195
JOHNSON COUNTY													
829+35 TO 838+00	865.00		2691	97	194	291	48	1557		1730	11	11	1730
EQUATION STATION													
838+28.2 TO 838+52	23.80		74	3	5	8	1	43		48	1	1	48
SN 044-0001 838+52 TO 839+50	98.00	327			18			147	80				
839+50 TO 875+23.7	3573.70		11118	400	801	1201	200	6433		7147	45	45	7147
EQUATION STATION													
875+00 TO 903+32.3	2832.30		8812	317	634	952	159	5098		5665	36	36	5665
EQUATION STATION													
903+32.7 TO 942+87.1	3954.40		12303	443	886	1329	221	7118		7909	50	50	7909
EQUATION STATION													
942+84.7 TO 957+00	1415.3		4403	159	317	476	79	2548	40	2831	18	18	2831
JOHNSON COUNTY SUBTOTALS		327	39401	1418	2855	4255	709	22943	120	25329	161	161	25329
TOTALS		327	66149	2381	4781	7144	1191	38419	160	42524	269	269	42524