


CONSTRUCTION CODE

90% FED 10% STATE

100% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE											
				MADISON CO ROADWAY 0004 RURAL	MADISON CO ROADWAY 0004 URBAN	BOND CO. ROADWAY 0004 RURAL	MADISON CO BRIDGE 0014 URBAN	BOND CO BRIDGE 0014 RURAL	MADISON CO BRIDGE 0044 URBAN	MADISON CO BRIDGE 0011 RURAL	MADISON CO RAMP 0004 URBAN	MADISON CO REST AREAS 0005 URBAN			
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	1206	15	1191										
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	839	24	815										
20100500	TREE REMOVAL, ACRES	ACRE	0.25								0.25				
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	1		1										
20200100	EARTH EXCAVATION	CU YD	13418	3196	8363	1591					268				
20300100	CHANNEL EXCAVATION	CU YD	2310		2310										
20400800	FURNISHED EXCAVATION	CU YD	216		150						66				
20700220	POROUS GRANULAR EMBANKMENT	CU YD	92								92				
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SO YD	224								224				
21400100	GRADING AND SHAPING DITCHES	FOOT	1155	200	955										
25000210	SEEDING, CLASS 2A	ACRE	6.50	1.50	4.25	0.50					0.25				



NOTE: MADISON CO. ROWY. RURAL BEGINNING OF PROJECT TO STA. 1594+56.25 (PRAIRIE RD.) AND STA. 1842+50 TO BOND CO. LINE
 MADISON CO. ROWY. URBAN STA. 1954+56.25 TO STA. 1842+50
 BOND CO. ROWY RURAL BOND CO. LINE TO END OF PROJECT
 MADISON CO. BRIDGE (0014) URBAN SN 060-0176, 0033/34, 0132, 0079
 BOND CO. BRIDGE (0014) RURAL SN 003-0042
 MADISON CO. BRIDGE (0040) URBAN SN. 060-2536, 2537
 MADISON CO. BRIDGE (0011) RURAL SN 060-2588 (NEW BOX CULVERT)
 STRUCTURES LESS THAN 20' OVER 20' * MADISON/BOND

FILE NAME	USER NAME = ch10sl	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION		SUMMARY OF QUANTITIES		F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
p:\NLR\84EBID\INTEC\Illinois.gov\FW\DOT\Documents\DOT Offices\District 8\Project\087\DRAWING>Data\EA\sheet\EDITED\CONSULTANT\REVISED\6F94-sht-500.DGN		CHECKED -	REVISED -					70	60-(13,14,15)RS-3		226	3
PLOT SCALE = 26.1816 1/2 in.		DATE -	REVISED -					SCALE:		SHEET NO. 1 OF 17 SHEETS	STA. TO STA.	CONTRACT NO. 76F94

REV. 8-31-16

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE											
				90% FED 10% STATE						100% STATE					
				MADISON CO ROADWAY 0004 RURAL	MADISON CO ROADWAY 0004 URBAN	BOND CO. ROADWAY 0004 RURAL	MADISON CO BRIDGE 0014 URBAN	BOND CO BRIDGE 0014 RURAL	MADISON CO BRIDGE 0044 URBAN	MADISON CO BRIDGE 0011 RURAL	MADISON CO BRIDGE 0011 URBAN	MADISON CO RAMP 0004 URBAN	MADISON CO REST AREAS 0005 URBAN		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	459	105	301	38					15				
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	459	105	301	38					15				
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	459	105	301	38					15				
25100115	MULCH, METHOD 2	ACRE	0.50		0.25						0.25				
25100630	EROSION CONTROL BLANKET	SO YD	35877	5684	16143	2021					12029				
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	615	126	412	49					28				
28000305	TEMPORARY DITCH CHECKS	FOOT	236		124						112				
28000400	PERIMETER EROSION BARRIER	FOOT	275		275										
28000500	INLET AND PIPE PROTECTION	EACH	1		1										
28100109	STONE RIPRAP, CLASS A5	SO YD	1942		1466		54				422				
28100207	STONE RIPRAP, CLASS A4	TON	737		737										
28100809	STONE DUMPED RIPRAP, CLASS A5	TON	98							98					
28200200	FILTER FABRIC	SO YD	2331		1804		54		51	422					
31100100	SUBBASE GRANULAR MATERIAL, TYPE A	TON	157								129		28		

19

FILE NAME *	USER NAME * chidl	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				SUMMARY OF QUANTITIES				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEET NO.
PLOT SCALE * 20.1818' / in.												CHECKED -	REVISED -	70	60-(13,14,15)RS-3
PLOT DATE * 5/6/2016				DATE -	REVISED -	SCALE:	SHEET NO. 2 OF 17 SHEETS	STA.	TO STA.	CONTRACT NO. 76F94					
												ILLINOIS FED. AID PROJECT			

△ REV. 8-31-16

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE											
				90% FED 10% STATE						100% STATE					
				MADISON CO ROADWAY 0004 RURAL	MADISON CO ROADWAY 0004 URBAN	BOND CO. ROADWAY 0004 RURAL	MADISON CO BRIDGE 0014 URBAN	BOND CO. BRIDGE 0014 RURAL	MADISON CO BRIDGE 0044 URBAN	MADISON CO BRIDGE 0011 RURAL	MADISON CO RAMPS 0004 URBAN	MADISON CO REST AREAS 0005 URBAN			
31100910	SUBBASE GRANULAR MATERIAL, TYPE A 12"	SO YD	22071	5332	14075	2664									
31200500	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4"	SO YD	22071	5332	14075	2664									
35501326	HOT-MIX ASPHALT BASE COURSE, 10 1/2"	SO YD	8780	2168	5502	1110									
35501336	HOT-MIX ASPHALT BASE COURSE, 13"	SO YD	13500	3320	8520	1660									
40600290	POLYMERIZED BITUMINOUS MATERIALS (TACK COAT)	POUND	205741	45306	128699	2898						9455	19383		
40600647	LEVELING BINDER (MACHINE METHOD), IL-9.5FG, N90	TON	1955										1955		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	222			222									
40600990	TEMPORARY RAMP	SO YD	4092									2046	2046		
40603153	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	55341	13326	38909	746						2126	234		
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	18			18									
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	2895											2895	
42100100	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 8"	SO YD	22071	5332	14075	2664									
42100615	PAVEMENT REINFORCEMENT	SO YD	22071	5332	14075	2664									
44000100	PAVEMENT REMOVAL	SO YD	22204	5332	14075	2664					133				

14

FILE NAME =	USER NAME = ehlow	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
p:\NL8848BID\INTEG\Illinois.gov\KIGOT\00	Documents\DOT Offices\District 8\Projects\DOT	DRAWN	REVISED			70	60-13.14.151RS-3	*	226	5	
PLOT SCALE = 28.899 1/4"	CHECKED -	REVISED -				CONTRACT NO. 76F94					
PLOT DATE = 5/6/2016	DATE -	REVISED -	SCALE:			SHEET NO. 3 OF 17 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT		

REV. 8-31-16

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE										
				90% FED 10% STATE										
				MADISON CO ROADWAY 0004 RURAL	MADISON CO ROADWAY 0004 URBAN	BOND CO. ROADWAY 0004 RURAL	MADISON CO BRIDGE 0014 URBAN	BOND CO BRIDGE 0014 RURAL	MADISON CO BRIDGE 0044 URBAN	MADISON CO BRIDGE 0011 RURAL	MADISON CO RAMPS 0004 URBAN	MADISON CO REST AREAS 0005 URBAN		
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	6772										6772	
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	1888											1888
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	13130	3488	7982	1660								
44000162	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"	SQ YD	37429										9494	27935
44000167	HOT-MIX ASPHALT SURFACE REMOVAL, 4 1/2"	SQ YD	1660		1660									
44000171	HOT-MIX ASPHALT SURFACE REMOVAL, 5 1/2"	SQ YD	167889	42269	125620									
44004000	PAVED DITCH REMOVAL	FOOT	34		34									
44004250	PAVED SHOULDER REMOVAL	SQ YD	16366	4303	9847	1854							211	151
44200610	CLASS A PATCHES, TYPE II, 13 INCH	SQ YD	140	21	119									
44200612	CLASS A PATCHES, TYPE III, 13 INCH	SQ YD	64		64									
44200614	CLASS A PATCHES, TYPE IV, 13 INCH	SQ YD	570	32	240									298
44200982	CLASS B PATCHES, TYPE II, 11 INCH	SQ YD	30											30
44200986	CLASS B PATCHES, TYPE III, 11 INCH	SQ YD	22											22
44200988	CLASS B PATCHES, TYPE IV, 11 INCH	SQ YD	43											43

FILE NAME *	USER NAME * chidst	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.			
p:\1\2846810\INTEG.illinois.gov\PI\DOT\Documents\1007_District_B\Projects\0877\Drawings\BADSheets\EDITEDCONSULTANT\REVISED\94-shs-500.DGN								70	60-13.14.15R5-3	*	226	6			
PLOT SCALE = 20.1818 ' / in.								CHECKED -	REVISED -	CONTRACT NO. 76F94					
PLOT DATE = 9/6/2016								DATE -	REVISED -	SCALE:	SHEET NO. 4 OF 17 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT	

REV. 8-31-16

CONSTRUCTION CODE

90% FED 10% STATE

100% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE										100% STATE	1
				MADISON CO ROADWAY 0004 RURAL	MADISON CO ROADWAY 0004 URBAN	BOND CO. ROADWAY 0004 RURAL	MADISON CO BRIDGE 0014 URBAN	BOND CO BRIDGE 0014 RURAL	MADISON CO BRIDGE 0044 URBAN	MADISON CO BRIDGE 0011 RURAL	MADISON CO RAMP 0004 URBAN	MADISON CO REST AREAS 0005 URBAN			
44200050	WELDED WIRE REINFORCEMENT	SQ YD	65											65	
44201007	CLASS B PATCHES, TYPE II, 13 INCH	SO YD	30										30		
44201299	DOWEL BARS, 1 1/2"	EACH	211										67	144	
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SO YD	133									133			
44213000	PATCHING REINFORCEMENT	SO YD	774	54	422									298	
44213100	PAVEMENT FABRIC	SO YD	65		65										
44213200	SAW CUTS	FOOT	2900	274	1641								149	836	
44213204	TIE BARS 3/4"	EACH	190		106									84	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	4318	1042	2872	60							284	60	
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SO YD	227								227				
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SO YD	324								324				
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SO YD	2265	1142	1123										
48203042	HOT-MIX ASPHALT SHOULDERS, 11 1/4"	SO YD	9											9	
48203050	HOT-MIX ASPHALT SHOULDERS, 13 1/4"	SO YD	211										211		
48203058	HOT-MIX ASPHALT SHOULDERS, 15 1/4"	SO YD	142											142	

FILE NAME	USER NAME = chidsl	DESIGNED -	REVISED -	<p align="center">STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</p>	<p align="center">SUMMARY OF QUANTITIES</p>	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
<p>FOR DRAWING DATE: 8/28/2016</p>						70	60-113.14.15RS-3	*	226	?	
<p>PLOT SCALE = 20.1818' / 1" IN.</p>						CHECKED -	REVISED -	<p>CONTRACT NO. 76F94</p>			
<p>PLOT DATE = 8/26/2016</p>						DATE -	REVISED -	<p>ILLINOIS FED. AID PROJECT</p>			

REV. 8-31-16

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE											
				90% FED 10% STATE											
				MADISON CO ROADWAY 0004 RURAL	MADISON CO ROADWAY 0004 URBAN	BOND CO. ROADWAY 0004 RURAL	MADISON CO BRIDGE 0014 URBAN	BOND CO BRIDGE 0014 RURAL	MADISON CO BRIDGE 0044 URBAN	MADISON CO BRIDGE 0011 RURAL	MADISON CO RAMPS 0004 URBAN	MADISON CO REST AREAS 0005 URBAN	△		
48203100	HOT-MIX ASPHALT SHOULDERS	TON	17082	3906	11723	388							853	212	
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1									1			
50102400	CONCRETE REMOVAL	CU YD	42.4				31.7	9	1.7						
50104000	BRIDGE RAIL REMOVAL	FOOT	888				888								
50104650	SLOPE WALL REMOVAL	SQ YD	551				551								
50105220	PIPE CULVERT REMOVAL	FOOT	374	263	53								58		
50200450	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL FOR STRUCTURES	CU YD	261									261			
50300225	CONCRETE STRUCTURES	CU YD	8.9					7.2	1.7						
50300255	CONCRETE SUPERSTRUCTURE	CU YD	41.7				32.7	9							
50300260	BRIDGE DECK GROOVING	SQ YD	1375				729	646							
50300300	PROTECTIVE COAT	SQ YD	99.4				72.4	27							
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	2970				2970								
50800105	REINFORCEMENT BARS	POUND	3770	1080	2530	160									
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	7710				4780	2760	170						

19

FILE NAME =	USER NAME = enlde1	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
\\vl2848BIDINTEG\illinois.gov\DOT\0	ements\DOT Offices\District 8\Projects\087	DRAMA\Data\AD\Sheets\EDITED\CONSULTANT	REVISED 6/9/14 - JAC-900.DGN			70	60-(13,14,15)RS-3	*	226	8
PLOT SCALE = 28.1618" / in.	CHECKED -	REVISED -				SCALE:	SHEET NO. 6 OF 17 SHEETS	STA.	TO STA.	CONTRACT NO. 76F94
PLOT DATE = 5/8/2015	DATE -	REVISED -				ILLINOIS FED. AID PROJECT				

△ REV. 8-31-16

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE											
				90% FED 10% STATE								100% STATE		△	
				MADISON CO ROADWAY 0004 RURAL	MADISON CO ROADWAY 0004 URBAN	BOND CO. ROADWAY 0004 RURAL	MADISON CO BRIDGE 0014 URBAN	BOND CO BRIDGE 0014 RURAL	MADISON CO BRIDGE 0044 URBAN	MADISON CO BRIDGE 0011 RURAL	MADISON CO RAMP 0004 URBAN	MADISON CO REST AREAS 0005 URBAN			
63200310	GUARDRAIL REMOVAL	FOOT	11110	869	9951	240						50			
63500105	DELINEATORS	EACH	383	50	112	4							140	77	
64200116	SHOULDER RUMBLE STRIPS, 16 INCH	FOOT	127883	34843	90365	2675									
66500105	WOVEN WIRE FENCE, 4'	FOOT	262		262										
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	3	9										
67100100	MOBILIZATION	L SUM	1	0.26	0.71	0.03									
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1		1										
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	20										8	12	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1		1										
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1		1										
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	0.26	0.71	0.03									
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	0.26	0.71	0.03									
70100820	TRAFFIC CONTROL AND PROTECTION, STANDARD 701451	L SUM	1		1										
70100825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	L SUM	1		1										

FILE NAME =	USER NAME = chidsl	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEET NO.		
p:\1\188488\INTEC\Illinois.gov\WIDOT\Documents\DOT Offices\District 8\Projects\087\Drawings\60\Drawings\EDITED\CONSULTANT\REVISED\6F94-shr-500.DGN						70	60-413.14,15IRS-3	*	226	12	
PLOT SCALE = 28,1818' / 1"						CHECKED -	REVISED -	CONTRACT NO. 76F94			
PLOT DATE = 5/6/2016						DATE -	REVISED -	ILLINOIS FED. AID PROJECT			

△ REV. 8-31-16

14

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE													
				90% FED 10% STATE											100% STATE		
				MADISON CO ROADWAY 0004 RURAL	MADISON CO ROADWAY 0004 URBAN	BOND CO. ROADWAY 0004 RURAL	MADISON CO BRIDGE 0014 URBAN	BOND CO BRIDGE 0014 RURAL	MADISON CO BRIDGE 0044 URBAN	MADISON CO BRIDGE 0011 RURAL	MADISON CO RAMPS 0004 URBAN	MADISON CO REST AREAS 0005 URBAN					
* 72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	42	18.00	24												
* 72400320	REMOVE SIGN PANEL - TYPE 2	SQ FT	180	62.5	98	19.5											
* 72400330	REMOVE SIGN PANEL - TYPE 3	SQ FT	2978	659	2154	165											
* 72400710	RELOCATE SIGN PANEL - TYPE 1	SQ FT	23	9	9	5											
* 72400720	RELOCATE SIGN PANEL - TYPE 2	SQ FT	12		12												
* 72501000	TERMINAL MARKER - DIRECT APPLIED	EACH	35	4	25	2					4						
* 72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	18660	4875	13575	210											
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	1194	306	854	34											
* 73000100	WOOD SIGN SUPPORT	FOOT	190	40	150												
* 73400100	CONCRETE FOUNDATIONS	CU YD	44.9	13.2	30.3	1.4											
* 73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	1		1												
* 73700100	REMOVE GROUND MOUNTED SIGN SUPPORT	EACH	63	16	45	2											
* 73700200	REMOVE CONCRETE FOUNDATION - GROUND MOUNT	EACH	40	10	28	2											
* 73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	1		1												
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	27.9													27.9	

* SPECIALTY ITEM

FILE NAME	USER NAME	DESIGNED	REVISED	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				SUMMARY OF QUANTITIES				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
p:\NLSB\EBIDINTEG\Illinois.gov\PIDOT\Documents\DOT Offices\District 8\Projects\0876\BRAND Data\EA0\meta\EDITEDCONSULTANT	onidol	REVISED	REVISED									70	60-113,14,151R5-3	*	226	14	
PLOT SCALE = 28,2871" / in.	CHECKED	REVISED	REVISED									SCALE:		SHEET NO. 12 OF 17 SHEETS		STA. TO STA.	
PLOT DATE = 3/6/2016	DATE	REVISED	REVISED									ILLINOIS FED. AID PROJECT					

REV. 8-31-16

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE													
				90% FED 10% STATE								100% STATE		▲			
				MADISON CO ROADWAY 0004 RURAL	MADISON CO ROADWAY 0004 URBAN	BOND CO. ROADWAY 0004 RURAL	MADISON CO BRIDGE 0014 URBAN	BOND CO BRIDGE 0014 RURAL	MADISON CO BRIDGE 0044 URBAN	MADISON CO BRIDGE 0011 RURAL	MADISON CO RAMP 0004 URBAN	MADISON CO REST AREAS 0005 URBAN					
X0326208	ALTERNATE ROUTE SIGNING	L SUM	1	0.26	0.71	0.03											
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SO YD	91464	24518	66946												
X5010523	REMOVE CONCRETE END SECTION	EACH	22	5	14	▲							1	2			
X5420624	PIPE CULVERTS TO BE CLEANED 24"	FOOT	733		524		81								128		
X5420630	PIPE CULVERTS TO BE CLEANED 30"	FOOT	393	278	115												
X5420636	PIPE CULVERTS TO BE CLEANED 36"	FOOT	649	56	593												
X5420642	PIPE CULVERTS TO BE CLEANED 42"	FOOT	241		241												
X5870015	BRIDGE DECK CONCRETE SEALER	SO FT	15755				15755										
X6350120	DELINEATOR REMOVAL	EACH	375	46	108	▲	4						140	77			▲
X6430120	REMOVE IMPACT ATTENUATORS, NO SALVAGE	EACH	8	2	5		1										
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	0.26	0.71	0.03											
X7010218	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	EACH	2				1					1					
X7010410	SPEED DISPLAY TRAILER	CAL MO	15	4	11												
X7200200	WIDE LOAD SIGNING	L SUM	1		1												

14

FILE NAME =	USER NAME = ch10n3	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	P.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
p:\11084581QINTEC\illinois.gov\PW1007\00	umanta\1007 OFFICIA\District 8\Projects\087	DRAWN	REVISED			70	60-(13,14,15)RS-3	.	226	16	
PLOT SCALE = 28.2071' / in.	CHECKED -	REVISED -	SCALE:			SHEET NO. 14 OF 17 SHEETS	STA.	TO STA.	CONTRACT NO. 76F94		
PLOT DATE = 5/6/2016	DATE -	REVISED -	ILLINOIS FED. AID PROJECT								

▲ REV. 8-31-16

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE													
				90% FED 10% STATE						100% STATE		MADISON CO RAMP 0004 URBAN	MADISON CO REST AREAS 0005 URBAN				
				MADISON CO ROADWAY 0004 RURAL	MADISON CO ROADWAY 0004 URBAN	BOND CO. ROADWAY 0004 RURAL	MADISON CO BRIDGE 0014 URBAN	BOND CO BRIDGE 0014 RURAL	MADISON CO BRIDGE 0044 URBAN	MADISON CO BRIDGE 0011 RURAL							
* X7360510	REMOVE OVERHEAD SIGN STRUCTURE - LIGHTING EQUIPMENT	L SUM	1		1												
* X7830074	GROOVING FOR RECESSED PAVEMENT MARKING 7"	FOOT	788		788												
X8570000	SMART TRAFFIC MONITORING SYSTEM	L SUM	1	0.26	0.71	0.03											
Z0001899	JACK AND REMOVE EXISTING BEARINGS	EACH	28				28										
Z0001905	STRUCTURAL STEEL REPAIR	POUND	12					12									
Z0005305	BOX CULVERTS TO BE CLEANED	FOOT	735		735												
* Z0007101	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 1	L SUM	1				1										
* Z0007102	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 2	L SUM	1				1										
* Z0007103	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 3	L SUM	1				1										
* Z0007104	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 4	L SUM	1				1										
* Z0007105	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 5	L SUM	1				1										
Z0010400	CLEANING BRIDGE SEATS	SQ FT	202					202									
* Z0010501	CLEANING AND PAINTING STEEL BRIDGE NO. 1	L SUM	1				1										
* Z0010502	CLEANING AND PAINTING STEEL BRIDGE NO. 2	L SUM	1				1										

* SPECIALTY ITEM

FILE NAME =	USER NAME = phidal	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
p:\11\B94E910\76F94\Illinois.gov\WIDOT\Documents\DOT Office\District 8\Projects\097\ROADWAY\GAD\Sheet\EDITED\CONSULTANT\REVISED\94-int-500.DGN	FOR ANNO TO GAD SHEETS\EDITED\CONSULTANT\REVISED\94-int-500.DGN	CHECKED -	REVISED -			70	60-113.14,15RS-3	*	226	17	
PLOT SCALE = 28.2871' / 1" in.	DATE -	REVISED -	SCALE:			SHEET NO. 15 OF 17 SHEETS	STA. TO STA.	CONTRACT NO. 76F94			
PLOT DATE = 5/6/2016	DATE -	REVISED -	ILLINOIS FED. AID PROJECT								

REV. 8-31-16

14

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE										MADISON CO RAMP REST AREAS 0004 URBAN	MADISON CO REST AREAS 0005 URBAN	△	
				90% FED 10% STATE													
				MADISON CO ROADWAY 0004 RURAL	MADISON CO ROADWAY 0004 URBAN	BOND CO. ROADWAY 0004 RURAL	MADISON CO BRIDGE 0014 URBAN	BOND CO BRIDGE 0014 RURAL	MADISON CO BRIDGE 0044 URBAN	MADISON CO BRIDGE 0011 RURAL							
* Z0010503	CLEANING AND PAINTING STEEL BRIDGE NO. 3	L SUM	1														
* Z0010504	CLEANING AND PAINTING STEEL BRIDGE NO. 4	L SUM	1														
* Z0010505	CLEANING AND PAINTING STEEL BRIDGE NO. 5	L SUM	1														
Z0012142	BRIDGE DECK SCARIFICATION 2 1/4"	SO YD	695									695					
Z0012148	BRIDGE DECK SCARIFICATION 3"	SO YD	752									752					
Z0012162	BRIDGE DECK MICROSILICA CONCRETE OVERLAY 2 1/4"	SO YD	691									691					
Z0012168	BRIDGE DECK MICROSILICA CONCRETE OVERLAY 3"	SO YD	752									752					
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SO YD	49.2									49.2					
Z0021906	SILICONE JOINT SEALER, 1.5"	FOOT	66									66					
Z0022800	FENCE REMOVAL	FOOT	204		204												
Z0023500	FILLING EXISTING CULVERTS	CU YD	32.7		20.6												
Z0034105	MATERIAL TRANSFER DEVICE	TON	55341	13326	41269	746											
Z0036200	PAINT CURB	FOOT	1941														
Z0041895	POLYMER CONCRETE	CU FT	6.5									6.5					

MADISON CO RAMP REST AREAS 0004 URBAN

20.6

12.1
124
1817

* SPECIALTY ITEM

FILE NAME =	USER NAME = chldel	DESIGNED -	REVISED -
\\NLS04EBID\INTEG\Illinois\gov\PI\DOT\Do	\\NLS04EBID\INTEG\Illinois\gov\PI\DOT\Do	DRAWN	REVISION
		CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.I. REC.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	60-(13,14,15)RS-3		226	18
			CONTRACT NO. 76F94	
ILLINOIS FED. AID PROJECT				

△ REV. 8-31-16

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE											
				90% FED 10% STATE								100% STATE		MADISON CO RAMP REST AREAS	
				MADISON CO ROADWAY 0004 RURAL	MADISON CO ROADWAY 0004 URBAN	BOND CO. ROADWAY 0004 RURAL	MADISON CO BRIDGE 0014 URBAN	BOND CO BRIDGE 0014 RURAL	MADISON CO BRIDGE 0044 URBAN	MADISON CO BRIDGE 0011 RURAL	MADISON CO RAMP REST AREAS 0004 URBAN	MADISON CO RAMP REST AREAS 0005 URBAN			
* Z0054406	ROCK FILL - FOUNDATION	CU YD	224										224		
Z0064600	SELECTIVE CLEARING	ACRE	1.50	0.90	0.10	0.50									
X1200086	SANITARY SEWER REMOVAL 4"	FOOT	284						284						
X0327979	PAYEMENT MARKING REMOVAL - GRINDING	SQ FT	11,357	2408	7811	1138									
X0327980	PAYEMENT MARKING REMOVAL - WATER BLASTING	SQ FT	68,439	48,645	13,115	6679									
φ Z0076600	TRAINEES	HOOR	3500	3500											
φ Z0076604	TRAINEES TRAINING PROGRAM GRADUATE	HOOR	3500	3500											

φ 0042 * SPECIALTY ITEM

FILE NAME =	USER NAME = qh1941	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.L. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
p:\1\10848\BIOINTEG\Illinois.gov\PI\DOT\Documents\DOT Offices\District 5\Projects\087\DRAMA\Drawings\Sheet\EDITED\CONSULTANT\REVISED\6F94.sht=500.DGN	PROJECT = 087	CHECKED -	REVISED -					70	60-113,14,15IRS-3		226	19
PLOT SCALE = 20:2671' / in.	DATE -	REVISIONS						CONTRACT NO. 76F94				
PLOT DATE = 5/6/2016	DATE -	REVISIONS						ILLINOIS FED. AID PROJECT				

△ REV. 8-31-16

3