

CODE NO.	ITEM	UNIT	TOTAL QTY.	CONSTRUCTION TYPE CODE																
				80% FED. 20% STATE ROADWAY J000-2A	80% FED. 20% STATE ROADWAY I000-2A	80% FED. 10% STATE 10% BANNOCKBURN TRAFFIC SIGNALS Y031-1F	80% FED. 20% STATE TRAFFIC SIGNALS Y031-1F	80% FED. 10% STATE 10% HIGHLAND PARK TRAFFIC SIGNALS Y031-1F	80% FED. 10% STATE 6.7% HIGHLAND PARK TRAFFIC SIGNALS Y031-1F	80% FED. 20% STATE INTERCONNECT Y031-1F	50% STATE 50% BANNOCKBURN SIDEWALK SFTY-1B	100% HIGHLAND PARK EMERGENCY PRE-EMPTION Y031-3D	100% BANNOCKBURN EMERGENCY PRE-EMPTION Y031-3D							
60624600	CORRUGATED MEDIAN	SQ FT	1,702	1,702																
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	14	14																
67100100	MOBILIZATION	L SUM	1	1																
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1																
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	323	323																
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	14	14																
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1,554	1,554																
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	72,406	72,406																
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	6,259	6,259																
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	11,123	11,123																
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	186	186																
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	40,314	40,314																
* 72000100	SIGN PANEL - TYPE 1	SQ FT	900		812		33		78.5		45		19.5							
* 72000200	SIGN PANEL - TYPE 2	SQ FT	30						30.0											
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	799	799																
* 72900100	METAL POST - TYPE A	FOOT	812	812																
* 72900200	METAL POST - TYPE B	FOOT	217	217																
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	182		182															
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1,630		1,630															
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,641		1,641															
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	484		484															
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	303		303															
* 7800 0200	<del>EPOXY</del> <sup>POLYUREA</sup> PAVEMENT MARKING - TYPE I LETTERS AND SYMBOLS	SQ FT	2,188	2,188																
* 7800 0210	<del>EPOXY</del> <sup>POLYUREA</sup> PAVEMENT MARKING - TYPE I LINE 4"	FOOT	4,437	4,437																
* 7800 0230	<del>EPOXY</del> <sup>POLYUREA</sup> PAVEMENT MARKING - TYPE I LINE 6"	FOOT	9,142	9,142																
* 7800 0250	<del>EPOXY</del> <sup>POLYUREA</sup> PAVEMENT MARKING - TYPE I LINE 12"	FOOT	1,331	1,331																
* 7800 0270	<del>EPOXY</del> <sup>POLYUREA</sup> PAVEMENT MARKING - TYPE I LINE 24"	FOOT	896	896																
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	686	686																
78100200	TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER	EACH	946	946																
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	946	946																

\* SPECIALTY ITEMS

(SHEET 5 OF 10)

FILE NAME W:\ILRTE22\2009 REVISIONS\CADD Sheets\160860-sh1-500.dgn	USER NAME = #USER#	DESIGNED - LP	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>IL. ROUTE 22 SUMMARY OF QUANTITIES</b>			F.A.P. RTE. 337	SECTION 20R-4	COUNTY LAKE	TOTAL SHEETS 232	SHEET NO. 7
PLOT SCALE = #SCALE#	DATE = 05/14/2010	DRAWN - LP	REVISED -		SCALE: NTS	SHEET NO. 7 OF 232 SHEETS	STA.	TO STA.	CONTRACT NO. 60860			
PLOT DATE = 5/16/2010		CHECKED - JP	REVISED -		ILLINOIS FED. AID PROJECT							
		DATE - 05/14/2010	REVISED -									