

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE									
CODE NO.	ITEM	UNIT	TOTAL QTY.	80% FED. 20% STATE ROADWAY J000-2A	80% FED. 20% STATE ROADWAY I000-2A	IL. RTE. 22 & TELEGRAPH RD. 80% FED./10% STATE 10% BANNOCKBURN TRAFFIC SIGNALS Y031-1F	IL. RTE. 22 & WAUKEGAN RD. 80% FED. 20% STATE TRAFFIC SIGNALS Y031-1F	IL. RTE. 22 & RIDGE RD./ TENNYSON LN. 80% FED./10% STATE 10% HIGHLAND PARK TRAFFIC SIGNALS Y031-1F	IL. RTE. 22 & RIDGE RD. 80% FED./13.31% STATE 6.7% HIGHLAND PARK TRAFFIC SIGNALS Y031-1F	80% FED. 20% STATE INTERCONNECT Y031-1F	50% STATE 50% BANNOCKBURN SIDEWALK SFTY-1B	100% HIGHLAND PARK EMERGENCY PRE-EMPTION Y031-3D	100% BANNOCKBURN EMERGENCY PRE-EMPTION Y031-3D
* 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	12,554			553	781	554	498	10,168			
* 81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	61			41	20						
* 81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	165			13	49	26	77				
* 81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	292				268	12	12				
* 81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	3,213			159	573	111	94	2,276			
* 81018600	CONDUIT PUSHED, 2 1/2" DIA., GALVANIZED STEEL	FOOT	134			7	74		53				
* 81018700	CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL	FOOT	58			58							
* 81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	1,774			452	765	365	192				
* 81100600	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	158							158			
* 81306500	REMOVE EXISTING JUNCTION BOX	EACH	2				2						
* 81400100	HANDHOLE	EACH	38			4	8	4	4	18			
* 81400200	HEAVY-DUTY HANDHOLE	EACH	10			2	5	2	1				
* 81400300	DOUBLE HANDHOLE	EACH	9			2	4	2	1				
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	13,072			607	1,118	592	587	10,168			
* 85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	2					1	1				
* 85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1			1							
* 86400100	TRANSCEIVER - FIBER OPTIC	EACH	4			1	1	1	1				
* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	3,518			839	1,207	1,112	360				
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	7,165			1,426	3,664	1,422	653				
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	10,401			1,970	5,489	1,735	1,207				
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	3,761			803	1,862	694	402				
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	13,630			2,255	7,682	2,053	1,640				
* 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	216			67	64	44	41				
* 87502430	TRAFFIC SIGNAL POST, GALVANIZED STEEL 9 FT.	EACH	1				1						
* 87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	2			1			1				
* 87502460	TRAFFIC SIGNAL POST, GALVANIZED STEEL 12 FT.	EACH	1				1						
* 87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	1						1				
* 87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	4			2	1		1				
* 87700200	STEEL MAST ARM ASSEMBLY AND POLE, 32 FT.	EACH	1			1							
* 87700220	STEEL MAST ARM ASSEMBLY AND POLE, 36 FT.	EACH	3			1		1	1				

\* SPECIALTY ITEMS

(SHEET 6 OF 10)

FILE NAME W:\ILRTE22\2010\REVISIONS\CADD Sheets\0160860-shr-500.dgn	USER NAME # USER#	DESIGNED - LP	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>IL. ROUTE 22 SUMMARY OF QUANTITIES</b>			F.A.P RTE. 337	SECTION 20R-4	COUNTY LAKE	TOTAL SHEETS 232	SHEET NO. 8
PLOT SCALE # \$SCALE#	CHECKED - JP	REVISIED -	REVISIED -		SCALE: NTS	SHEET NO. 8 OF 232 SHEETS	STA.	TO STA.	CONTRACT NO. 60860			
PLOT DATE # 5/15/2010	DATE - 05/14/2010	REVISIED -	REVISIED -		ILLINOIS FED. AID PROJECT							