

CODE #	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE					
				ROADWAY I000	TRAFFIC SIGNALS Y031-1F	CHICAGO LIGHTING Y030-1E	IDOT LIGHTING Y030-1E	BRIDGE X271-2A	SURVEILLANCE Y032-1F
Z0030340	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 2	EACH	2	2					
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	6	6					
Z0064600	SELECTIVE CLEARING	ACRE	0.18	0.18					
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	5	5					
* X0325527	REMOVE & REINSTALL SIGNAL EQUIPMENT	L SUM	1		1				
* X0324705	MAST ARM, STEEL, 12 FOOT, ^{STREET LIGHTING,} INSTALL ONLY	EACH	5				5		
* X0327044	MAST ARM, STEEL, 12 FOOT, ^{STREET LIGHTING,} FURNISH ONLY	EACH	5			5			
* B2106700	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT (MATERIAL ONLY)	EACH	5			5			
* X0327045	LIGHT POLE, STEEL, 32.5 FT. M.H. (FURNISH ONLY)	EACH	5			5			
* X0327046	ELECTRICAL FRAME AND LID, 30"	EACH	4			4			
* XX004046	AERIAL CABLE REMOVAL	FOOT	1350			350			1000
*** X0327040	COMBINED SEWER, CLASS A, TYPE 3, 24"	FOOT	63	63					
* 81100420	CONDUIT ATTACHED TO STRUCTURE, 1 1/4" PVC GALVANIZED STEEL CONDUIT	FOOT	120						120
* X8130360	JUNCTION BOX, COMPOSITE CONCRETE, EMBEDDED IN STRUCTURE, 20" X 13" X 12"	EACH	1				1		
* X0326965	ELECTRIC CABLE NO.19, 25 PAIR	FOOT	1050						1050
* X0327048	TEMPORARY CABLE INSTALLATION/REMOVAL	L SUM	1						1
* Z0076600	TRAINEES	HOUR	1500	1500					

© Y&B
 • SPECIALTY ITEM
 ** NON-PARTICIPATING
 *** 100% CITY OF CHICAGO

Rev. 9-2-10

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#		DRAWN -	REVISED -		94	0101.8B	COOK	139	7	CONTRACT NO. 60C18		
	PLOT SCALE = #SCALE#	CHECKED -	REVISED -		SCALE:	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT			
	PLOT DATE = #DATE#	DATE -	REVISED -									