

CODE *	ITEM	UNIT	90% FED. / 10% STATE TOTAL QUANTITY	CONSTRUCTION TYPE CODE					
				ROADWAY 1000	TRAFFIC SIGNALS Y031-1F	CHICAGO LIGHTING Y030-1E	.. IDOT LIGHTING Y030-1E	BRIDGE X271-2A	SURVEILLANCE Y032-1F
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	12053	12053					
70400100	TEMPORARY CONCRETE BARRIER	FOOT	2037.5	2037.5					
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	2050	2050					
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	67	67					
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2648	2648					
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1141	1141					
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	145	145					
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	37	37					
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	36	36					
78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	FOOT	5924	5924					
78003120	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 5"	FOOT	1571	1571					
78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	39	39					
78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	711	711					
78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	260	260					
78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	39	39					
78100300	REPLACEMENT REFLECTOR	EACH	157	157					
78200530	BARRIER WALL MARKERS, TYPE C	EACH	87	87					
78300100	PAVEMENT MARKING REMOVAL	SQ FT	375	375					
81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	300			300			
81017515	CONDUIT IN TRENCH, 1/4" DIA., COILABLE NONMETALLIC CONDUIT	FOOT	20						20
81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	24			24			
81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	400						400
81018700	CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL	FOOT	90						90
81018400	CONDUIT PUSHED, 2 1/2" DIA., GALVANIZED STEEL	FOOT	60				60		
81100320	CONDUIT ATTACHED TO STRUCTURE, 1" DIA., PVC COATED GALVANIZED STEEL	FOOT	400				400		
81100805	CONDUIT ATTACHED TO STRUCTURE, 3" DIA., PVC COATED GALVANIZED STEEL	FOOT	70				20		50
81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	800			800			
81200270	CONDUIT EMBEDDED IN STRUCTURE, 4" DIA., PVC	FOOT	850				450		400
81300220	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 6" X 6" X 4"	EACH	8				8		
81300530	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 10" X 6"	EACH	3				3		
81300550	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 12" X 6"	EACH	1						1
81300730	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 16" X 14" X 6"	EACH	1				1		
<del>81302500</del>	<del>JUNCTION BOX, CAST IRON, EMBEDDED IN STRUCTURE, 18" X 12" X 8"</del>	<del>EACH</del>	<del>3</del>			<del>2</del>	<del>1</del>		
81306500	REMOVE EXISTING JUNCTION BOX	EACH	2			1	1		
81400200	HEAVY DUTY HANDHOLE	EACH	2						2
81603140	UNIT DUCT, 600V, 3-1C NO.10, 1/C NO.10 GROUND, (EPR-TYPE RHW), 3/4" DIA. POLYETHYLENE	FOOT	300				300		
81603205	UNIT DUCT, 600V, 3-1C NO.4, 1/C NO.4 GROUND, (EPR-TYPE RHW), 1 1/4" DIA. POLYETHYLENE	FOOT	550				550		
81700110	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 1/C NO. 10	FOOT	1600				1600		
81800300	AERIAL CABLE, 3-1/C NO. 2 WITH MESSENGER WIRE	FOOT	510			110	400		
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	400						400
81900302	TRENCH AND BACKFILL WITH SCREENINGS OR SAND	FOOT	75			75			
82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	4				4		
82106400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT (INSTALL ONLY)	EACH	5				5		

- SPECIALTY ITEM
- NON-PARTICIPATING
- 100% CITY OF CHICAGO

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#	PLOT SCALE = #SCALE#	DRAWN -	REVISED -		SCALE:	SHEET NO. 1 OF 1 SHEETS	STA.	94	0101.8B	COOK	139	5
	PLOT DATE = #DATE#	CHECKED -	REVISED -				TO STA.					
		DATE -	REVISED -									
CONTRACT NO. 60C18												
ILLINOIS FED. AID PROJECT												