

CODE #	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE					
				ROADWAY 1000	TRAFFIC SIGNALS Y031-1F	CHICAGO LIGHTING Y030-1E	IDOT LIGHTING Y030-1E	BRIDGE X271-2A	SURVEILLANCE Y032-1F
* 82107100	UNDERPASS LUMINAIRE, 70 WATT, HIGH PRESSURE SODIUM VAPOR	EACH	8				8		
* 83050110	LIGHT POLE, ALUMINUM, 32.5 FT. M.H., 12 FT. MAST ARM (INSTALL ONLY)	EACH	5				5		
* 83057340	LIGHT POLE, WOOD, 60 FOOT, CLASS 3	EACH	3				3		
* 83057345	LIGHT POLE, WOOD, 60 FOOT, CLASS 3, WITH 15FT MAST ARM	EACH	4				4		
* 83057470	LIGHT POLE, WOOD, 90 FOOT, CLASS 3	EACH	1				1		
* 83057475	LIGHT POLE, WOOD, 90 FOOT, CLASS 3 WITH 15 FT MAST ARM	EACH	1				1		
* <del>83000200</del>	<del>LIGHT POLE FOUNDATION, 24" DIAMETER</del>	<del>FOOT</del>	<del>14</del>				<del>14</del>		
* 84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	5			5			
* <del>84200000</del>	<del>REMOVAL POLE FOUNDATION</del>	<del>EACH</del>	<del>2</del>				<del>2</del>		
* 84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	2				2		
* 89000200	TEMPORARY TRAFFIC SIGNAL INSTALLATION	L SUM	1		1				
* 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	5000			3000	1000		1000
X7830050	RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR REMOVAL	EACH	157	157					
** X0324599	ROD AND CLEAN EXISTING CONDUIT	FOOT	200			200			
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	163.9	163.9					
* X8730248	ELECTRIC CABLE IN CONDUIT, NO. 18, 4 PAIR TWISTED, SHIELDED	FOOT	1000						1000
* X0322703	TRIPLEX CABLE IN CONDUIT, 2 NO. 6 AND 1 NO. 8 (3TC)	FOOT	1000			1000			
* X0323157	REMOVE LUMINAIRE FROM UNDERPASS	EACH	2				2		
* <del>X0323364</del>	<del>ELECTRIC CABLE IN CONDUIT, NO. 19 G/C</del>	<del>FOOT</del>	<del>850</del>						<del>850</del>
* Z0033028	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	12			12			
* X0323710	REMOVE CONDUIT ATTACHED TO STRUCTURE	FOOT	380			80	300		
Z0073002	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	2505					2505	
X0324198	REMOVAL OF ASBESTOS CEMENT CONDUIT	FOOT	918					918	
X0324345	COMBINED SEWER REMOVAL 24"	FOOT	104	104					
X0324571	MAINTENANCE OF STREET LIGHTING SYSTEM (CITY OF CHICAGO)	L SUM	1			1			
** Z0010614	CLEANING EXISTING MANHOLE OR HANDHOLE	EACH	2			2			
X0325085	TEMPORARY PAVEMENT (INTERSTATE)	SQ YD	49	49					
X0325201	SHOULDER RUMBLE STRIP REMOVAL	SQ YD	658	658					
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	54					54	
X7030104	PAVEMENT MARKING WET TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	30156	30156					
X7030112	PAVEMENT MARKING WET TEMPORARY TAPE, TYPE III, 12 INCH	FOOT	40	40					
X7030124	PAVEMENT MARKING WET TEMPORARY TAPE, TYPE III, 24 INCH	FOOT	39	39					
X0326095	PIPE UNDERDRAIN REMOVAL AND REPLACEMENT	FOOT	626	626					
X7030105	PAVEMENT MARKING WET TEMPORARY TAPE, TYPE III, 5 INCH	FOOT	4520	4520					
* <del>X0306000</del>	<del>JUNCTION BOX (SPECIAL)</del>	<del>EACH</del>	<del>2</del>						<del>2</del>
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	1	1					
*** X6022400	MANHOLES, TYPE A, 3' DIA. (INCLUDING FRAMES AND LIDS)	EACH	2					2	
* <del>X0050107</del>	<del>INDUCTION LOOP</del>	<del>FOOT</del>	<del>68</del>						<del>68</del>
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1					
Z0018400	DRAINAGE STRUCTURE TO BE ADJUSTED	EACH	6	6					
Z0018940	DRILL EXISTING MANHOLE OR HANDHOLE	EACH	2				2		
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 2	EACH	2	2					
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2					

\* SPECIALTY ITEM  
\*\* NON-PARTICIPATING  
\*\*\* 100% CITY OF CHICAGO

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				SUMMARY OF QUANTITIES				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#		DRAWN -	REVISED -					SCALE:	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	94	0101.8B	COOK	139	6
	PLOT SCALE = #SCALE#	CHECKED -	REVISED -									CONTRACT NO. 60C18				
	PLOT DATE = #DATE#	DATE -	REVISED -									ILLINOIS FED. AID PROJECT				