

20800150	TRENCH BACKFILL	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	44000700	APPROACH SLAB REMOVAL
CU YD	LOCATION	SQ FT	LOCATION	SQ YD	LOCATION
109.3	STA 50+69 LT TO STA 50+80.37 RT	489	STA 48+24.59 TO BRIDGE LT	241	STA 48+79.52 TO BRIDGE
133.5	STA 50+80.37 RT TO STA 51+25 RT	155	STA 49+26.20 TO BRIDGE RT	352	BRIDGE TO STA 51+38.20
125.2	STA 51+25 RT TO STA 50+69 LT	76	BRIDGE TO STA 50+67.06 LT	593	TOTAL
368	TOTAL	502	STA 50+86.59 TO STA 51+70.17 LT		
		476	BRIDGE TO STA 51+70.06 RT		
		1698	TOTAL		
21101615	TOPSOIL FURNISH AND PLACE 4"	42400800	DETECTABLE WARNINGS	44002209	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 2 1/4"
SQ YD	LOCATION	SQ FT	LOCATION	SQ YD	LOCATION
300	ESTIMATED QUANTITY.	17	NE QUAD OF ELSTON & CICERO	40	STA 50+69 TO STA 51+25
300	TOTAL	12	SE QUAD OF ELSTON & CICERO	40	TOTAL
		29	TOTAL		
		44000100	PAVEMENT REMOVAL	44004250	PAVED SHOULDER REMOVAL
		SQ YD	LOCATION	SQ YD	LOCATION
		186	STA 48+56.17 TO STA 48+79.52	80	-112.12 LT CENTER PIER TO 18.04 RT
		183	STA 51+38.20 TO STA 41+71.05	205	-200 LT CENTER PIER TO 195 RT
		369	TOTAL	205	-200 LT CENTER PIER TO 195 RT
				490	TOTAL
		44000200	DRIVEWAY PAVEMENT REMOVAL	44201771	CLASS D PATCHES, TYPE IV, 10 INCH
		SQ YD	LOCATION	SQ YD	LOCATION
		13	STA 50+77.44 LT - CE	34	STA 50+69 TO STA 51+25
		13	TOTAL	34	TOTAL
31101000	SUB-BASE GRANULAR MATERIAL, TYPE B	44000300	CURB REMOVAL	48203053	HOT-MIX ASPHALT SHOULDERS, 14"
TON	LOCATION	FOOT	LOCATION	SQ YD	LOCATION
104	ESTIMATED QUANTITY UNDER I-94 SHOULDERS	2	STA 50+66.99 TO STA 50+68.62 LT	80	-112.12 LT CENTER PIER TO 18.04 RT
104	TOTAL	1	STA 50+85.97 TO STA 50+86.27 LT	205	-200 LT CENTER PIER TO 195 RT
		3	TOTAL	205	-200 LT CENTER PIER TO 195 RT
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	44000500	COMBINATION CURB AND GUTTER REMOVAL	490	TOTAL
SQ YD	LOCATION	FOOT	LOCATION	56106400	ADJUSTING WATER MAIN 8"
16	CE @ STA. 50+77.3 LT	82	STA 48+22.46 TO BRIDGE LT	FOOT	LOCATION
16	TOTAL	31	STA 49+26.74 TO BRIDGE RT	53	AS DIRECTED BY ENGINEER
		74	BRIDGE TO STA 51+71.05 RT	53	TOTAL
		117	BRIDGE TO STA 51+71.05 LT	60250200	CATCH BASINS TO BE ADJUSTED
		5	STA 50+58.83 TO STA 50+67.79 LT	EACH	LOCATION
		6	STA 50+90.53 TO STA 50+85.97 LT	1	STA 51+56.06 25.90' LT
		130	STA -112 TO STA 18 I-94	1	TOTAL
		445	TOTAL		
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	44000600	SIDEWALK REMOVAL	60255500	MANHOLES TO BE ADJUSTED
TON	LOCATION	SQ FT	LOCATION	EACH	LOCATION
5	STA 50+69 TO STA 51+25	427	STA 48+24.68 TO BRIDGE LT	1	STA 51.53.59 0.24' LT
5	TOTAL	154	STA 49+26.17 TO BRIDGE RT	1	TOTAL
		86	BRIDGE TO STA 50+66.44 LT		
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	507	STA 50+85.99 TO STA 51+71.05 LT		
TON	LOCATION	431	BRIDGE TO STA 51+71.05 RT		
1.8	CE @ STA. 50+77.3 LT	1605	TOTAL		
1.8	TOTAL				
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)				
SQ YD	LOCATION				
196	STA 48+56.17 TO STA 48+81.66				
303	STA 51+16.24 TO STA 51+71.05				
499	TOTAL				

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#		DRAWN -	REVISED -						94	0101.8B	COOK	139	9
		PLOT SCALE = #SCALE#	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	CONTRACT NO. 60C18		
		PLOT DATE = #DATE#	REVISED -							ILLINOIS FED. AID PROJECT			