

PAVEMENT MARKING SCHEDULE

LOCATION	78008200	78008210	78008240	78008270	78000100	78000200	78000400	78000500	78000600	78000650	78003110	78003120	70300100
	POLYUREA PAVEMENT MARKING TYPE I				THERMOPLASTIC PAVEMENT MARKING						PREFORMED PLASTIC PAVEMENT MARKING TYPE B		SHORT-TERM PAVEMENT MARKING
	LETTERS AND SYMBOLS SQ FT	LINE 4" FOOT	LINE 6" FOOT	LINE 24" FOOT	LETTERS AND SYMBOLS SQ FT	LINE 4" FOOT	LINE 6" FOOT	LINE 8" FOOT	LINE 12" FOOT	LINE 24" FOOT	LINE 4" FOOT	LINE 5" FOOT	FOOT
ELSTON													
WESTBOUND	39	74	174	39	14	412	522	0	0	0	0	0	56
CENTERLINE	0	560	0	0	0	1788	0	0	0	0	0	0	140
EASTBOUND	0	68	86	0	53	449	619	0	0	36	0	0	68
I-94													
WESTBOUND	0	0	0	0	0	0	0	0	0	0	1533	828	252
CENTERLINE	0	0	0	0	0	0	0	0	0	0	3232	0	192
EASTBOUND	0	0	0	0	0	0	0	145	37	0	1159	743	284
TOTALS	38.7	702.2	260.0	39.0	66.5	2648.2	1141.0	145.2	37.0	36.0	5924.3	1570.9	992.0

STAGING PAVEMENT MARKING SCHEDULE

LOCATION	70300240	X0325775	X0326107	X0325840	X0325841	70301000
	TEMPORARY PAVEMENT MARKING - LINE 6"	WET REFLECTIVE TEMPORARY TAPE, TYPE III				WORK ZONE PAVEMENT MARKING REMOVAL
		4 INCH	5 INCH	12 INCH	24 INCH	
ELSTON S1	0	4345	0	0	13	1473
I-94 S1	463	963	0	0	0	321
I-94 S1A	0	6552	1500	0	0	2809
I-94 S1B	0	6552	1500	0	0	2809
ELSTON S2	0	4717	0	0	26	1624
I-94 S2	463	963	0	0	0	321
I-94 S2A	0	6065	1520	40	0	2696
TOTAL	926	30157	4520	40	39	12053
EST. 3 APPLS		90471	13560	120	117	

PAVEMENT MARKING REMOVAL SCHEDULE

LOCATION	78300100	78300200	78100300
	PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	REPLACEMENT REFLECTOR
	SQ FT	EACH	EACH
ELSTON			
WESTBOUND	1171	0	0
EASTBOUND	1217	0	0
I-94			
WESTBOUND	1391	83	83
EASTBOUND	1335	74	74
TOTALS	5114	157	157