

SUMMARY OF QUANTITIES			100% STATE CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES			100% STATE CONSTRUCTION TYPE CODE							
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	STATE URBAN	TRAFFIC	INTER-CONNECT	100% VILLAGE GLENVIEW WATERMAIN	100% VILLAGE GLENVIEW SIDEWALK	100% VILLAGE MORTON GROVE OPTICOM	CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	STATE URBAN	TRAFFIC	INTER-CONNECT	100% VILLAGE GLENVIEW WATERMAIN	100% VILLAGE GLENVIEW SIDEWALK	100% VILLAGE MORTON GROVE OPTICOM
				1000-2A	Y031-1F	Y031-1F	Y060	SFTY-1B	Y031-3D					1000-2A	Y031-1F	Y031-1F	Y060	SFTY-1B	Y031-3D
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	24	24						42400800	DETECTABLE WARNINGS	SO FT	590	460					130
20200100	EARTH EXCAVATION	CU YD	1314	1247				67		44000100	PAVEMENT REMOVAL	SO YD	75	75					
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	450	450						44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	263	263					
20800150	TRENCH BACKFILL	CU YD	9	9						44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	3430	3430					
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	1890	1890						44000600	SIDEWALK REMOVAL	SO FT	2178	2178					
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	36	36						44003100	MEDIAN REMOVAL	SO FT	5619	5619					
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	36	36						44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	120	120					
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	36	36						44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	90	90					
* 25100630	EROSION CONTROL BLANKET	SO YD	1890	1890						44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1512	1512					
* 25200110	SODDING, SALT TOLERANT	SO YD	1890	1890						550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	63	63					
25200200	SUPPLEMENTAL WATERING	UNIT	19	19						56400500	FIRE HYDRANTS TO BE REMOVED	EACH	2				2		
28000305	TEMPORARY DITCH CHECKS	FOOT	24	24						60107600	PIPE UNDERDRAINS 4"	FOOT	200	200					
28000400	PERIMETER EROSION BARRIER	FOOT	800	800						60208240	CATCH BASINS, TYPE C, TYPE 24 FRAME AND GRATE	EACH	8	8					
28000510	INLET FILTERS	EACH	19	19						60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	1	1					
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SO YD	1027	1027						60250500	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	6	6					
31101600	SUB-BASE GRANULAR MATERIAL, TYPE B 8"	SO YD	198	198						60251730	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 23 FRAME AND GRATE	EACH	1	1					
35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10"	SO YD	1045	1045						60251740	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	8	8					
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SO YD	340	340						60255500	MANHOLES TO BE ADJUSTED	EACH	1	1					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	8	8						60255600	MANHOLES TO BE ADJUSTED (SPECIAL)	EACH	2	2					
40600300	AGGREGATE (PRIME COAT)	TON	39	39						60255700	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	1	1					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	15	15						60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	4	4					
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	370	370						60500040	REMOVING MANHOLES	EACH	1				1		
40600895	CONSTRUCTING TEST STRIP	EACH	1	1						60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	176	176					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	134	134						60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	2431	2431					
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SO YD	362	362						60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SO FT	198	198					
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	62	62						60620800	CONCRETE MEDIAN, TYPE SB-9.12	SO FT	313	313					
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	922	922						67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
42001300	PROTECTIVE COAT	SO YD	2265	1384				881		67100100	MOBILIZATION	L SUM	1	1					
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SO YD	53	53						70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	9650	2307				7343		70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	30	30					
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SO FT	976	393				583		70300100	SHORT-TERM PAVEMENT MARKING	FOOT	560	560					
										70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	93	93					

FILE NAME =	USER NAME = mdyja	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CLIPW.../VPIWIDT.../MID.../JADms93785/P126704-Desig.../sign	DRAWN -	REVISED -	339						584 Y-N-1	COOK	61	3	
PLOT SCALE = 500000' / IN.	CHECKED -	REVISED -	CONTRACT NO. 60D25										
PLOT DATE = 6/4/2010	DATE -	REVISED -	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT										
				S ALE:		SHEET NO. OF SHEETS STA. TO STA.							