

SUMMARY OF QUANTITIES				100% STATE CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES				100% STATE CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	STATE URBAN 1000-2A	TRAFFIC Y031-1F	INTER-CONNECT Y031-1F	100% VILLAGE	100% VILLAGE	100% VILLAGE	CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	STATE URBAN 1000-2A	TRAFFIC Y031-1F	INTER-CONNECT Y031-1F	100% VILLAGE	100% VILLAGE	100% VILLAGE
							GLENVIEW WATERMAIN Y060	GLENVIEW SIDEWALK SFTY-1B	MORTON GROVE OPTICOM Y031-3D								GLENVIEW WATERMAIN Y060	GLENVIEW SIDEWALK SFTY-1B	MORTON GROVE OPTICOM Y031-3D
* 72000100	SIGN PANEL - TYPE 1	SO FT	27		27					* 87700240	STEEL MAST ARM ASSEMBLY AND POLE, 40 FT.	EACH	1		1				
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	400.4	400.4						* 87700280	STEEL MAST ARM ASSEMBLY AND POLE, 48 FT.	EACH	1		1				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	966	966						* 87700290	STEEL MAST ARM ASSEMBLY AND POLE, 50 FT.	EACH	1		1				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1932	1932						* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	16		16				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	168	168						* 87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4		4				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	38	38						* 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	52		52				
* 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	29	29						* 87900200	DRILL EXISTING HANDHOLE	EACH	1			1			
* 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	1242		645	597				* 88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	6		6				
* 81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	87		87					* 88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	4		4				
* 81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	24		24					* 88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	4		4				
* 81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	352		352					* 88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	8		8				
* 81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	411		411					* 88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	10		10				
* 81400100	HANDHOLE	EACH	6		5	1				* 88500100	INDUCTIVE LOOP DETECTOR	EACH	10		10				
* 81400200	HEAVY-DUTY HANDHOLE	EACH	4		4					* 88600100	DETECTOR LOOP, TYPE I	FOOT	1071		1071				
* 81400300	DOUBLE HANDHOLE	EACH	1		1					* 88700200	LIGHT DETECTOR	EACH	2						2
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1353		756	597				* 88700300	LIGHT DETECTOR AMPLIFIER	EACH	1						1
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2		2					* 88800100	PEDESTRIAN PUSH-BUTTON	EACH	8		8				
* 85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1		1					* 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1		1				
* 86400100	TRANSCEIVER - FIBER OPTIC	EACH	1		1					* 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1		1				
* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1402		1402					* 89502380	REMOVE EXISTING HANDHOLE	EACH	8		7	1			
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	2159		2159					* 89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	8		8				
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1605		1605					* A2000320	TREE, ACER MIYABEI MORTON (STATE STREET MIYABE MAPLE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	2	2					
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1653		1653					Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	102.8	102.8					
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	1945		1945					* Z0033090	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	1419			1419			
* 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	172.5		172.5					* Z0033046	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 2	EACH	1			1			
* 87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	4		4					X7030104	WET TEMPORARY PAVEMENT MARKING TAPE, TYPE III, 4 INCH	FOOT	966	966					
* 87700200	STEEL MAST ARM ASSEMBLY AND POLE, 32 FT.	EACH	1		1					X7030106	WET TEMPORARY PAVEMENT MARKING TAPE TYPE III, 6 INCH	FOOT	1932	1932					
										X7030124	WET TEMPORARY PAVEMENT MARKING TAPE, TYPE III, 24 INCH	FOOT	168	168					

* SPECIALTY ITEMS

FILE NAME =	USER NAME = mdy/ja	DESIGNED -	REVISOR -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
DESIGNER =	DRAWN -	CHECKED -	REVISOR -		339	584 Y-N-1	COOK	61	4				
PLOT SCALE = 50,000' / 1" IN.	DATE -	REVISOR -	REVISOR -		SCALE: SHEET NO. OF SHEETS STA. TO STA.				FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				
PLOT DATE = 5/3/2010	DATE -	REVISOR -	REVISOR -						CONTRACT NO. 60D25				