


CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				ROADWAY	BRIDGE	RETAINING WALL	HWY LIGHTING
				1000 - 2A URBAN	X271 - 2A URBAN	Y007 URBAN	Y030-1E URBAN
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	375	375			
44000600	SIDEWALK REMOVAL	SQ FT	1,171	1,171			
Z0004552	APPROACH SLAB REMOVAL	SQ YD	532	532			
X4401980	CONCRETE BARRIER REMOVAL	FOOT	381	381			
44004250	PAVED SHOULDER REMOVAL	SQ YD	788	788			
48300400	PORTLAND CEMENT CONCRETE SHOULDERS 9"	SQ YD	788	788			
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1		
50157300	PROTECTIVE SHIELD	SQ YD	1,464		1,464		
50200100	STRUCTURE EXCAVATION	CU YD	3,397		3,397		
50300225	CONCRETE STRUCTURES	CU YD	1,084		1084		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	665		665		
50300260	BRIDGE DECK GROOVING	SQ YD	1,402		1,402		
50300300	PROTECTIVE COAT	SQ YD	1,972		1,972		
50500305	ERECTING STRUCTURAL STEEL	L SUM	1		1		
50500505	STUD SHEAR CONNECTORS	EACH	7,320		7,320		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	279,100		279,100		
50800515	BAR SPLICERS	EACH	1,240		1,240		
50901730	BRIDGE FENCE RAILING	FOOT	427		427		
51500100	NAME PLATES	EACH	1		1		
52000110	PREFORMED JOINT STRIP SEAL	FOOT	149		149		
52100210	ERECTING ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	20		20		
52100530	ANCHOR BOLTS, 1 1/4"	EACH	80		80		
550A0330	STORM SEWERS, CLASS A, TYPE 2 10"	FOOT	37	37			
550A0680	STORM SEWERS, CLASS A, TYPE 3 18"	FOOT	176	176			
550A0700	STORM SEWERS, CLASS A, TYPE 3 21"	FOOT	76	76			
55100700	STORM SEWER REMOVAL 15"	FOOT	176	176			
55100900	STORM SEWER REMOVAL 18"	FOOT	76	76			
56000300	CAST IRON SOIL PIPE 8"	FOOT	132	132			
58700300	CONCRETE SEALER	SQ FT	1,406		1,406		
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	429			429	
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	236			236	
60107700	PIPE UNDERDRAINS 6"	FOOT	383	383			

• DENOTES SPECIAL PROVISION

FILE NAME = ...ND1-60F65-shr004-S002.dgn	DESIGNED - ITY	REVISED -	 600 WEST FULTON STREET CHICAGO, ILLINOIS 60661-1259 TEL. 312 454 9100 FAX 312 599 1217 WEB www.sepstein.com	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION			SUMMARY OF QUANTITIES				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT TIME = 10:34:22 AM	DRAWN - ITY	REVISED -					SCALE: N/A	SHEET NO. 2 OF 5 SHEETS	STA.	TO STA.	94	1314B-1	COOK	110	4
PLOT DATE = 7/19/2010	CHECKED - TRP	REVISED -									CONTRACT NO. 60F65				
	DATE - 07/19/2010	REVISED -								ILLINOIS FED. AID PROJECT					

Rev.