

SUMMARY OF QUANTITIES			80% FEDERAL, 20% STATE			SUMMARY OF QUANTITIES			80% FEDERAL, 20% STATE		
CODE NO.	ITEM	UNIT	URBAN TOTAL	ROADWAY 1000-2A	BRIDGE X081-2A	CODE NO.	ITEM	UNIT	URBAN TOTAL	ROADWAY 1000-2A	BRIDGE X081-2A
20200100	EARTH EXCAVATION	CU YD	119	119		44004250	PAVED SHOULDER REMOVAL	SQ YD	54	54	
21101815	COMPOST FURNISH AND PLACE, 4"	SQ YD	734	734		<del>20004552</del>	APPROACH SLAB REMOVAL	SQ YD	107		107
25000310	SEEDING, CLASS 4	ACRE	0.2	0.2		<del>20004562</del>	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	506	506	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	18	18		44002209	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 2 1/4"	SQ YD	100	100	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	18	18		44201749	CLASS D PATCHES, TYPE I, 9 INCH	SQ YD	27	27	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	18	18		44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	33	33	
25100630	EROSION CONTROL BLANKET	SQ YD	734	734		44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	40	40	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	20	20		50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1		1
28000305	TEMPORARY DITCH CHECKS	FOOT	100	100		50102400	CONCRETE REMOVAL	CU YD	0.8		0.8
28000400	PERIMETER EROSION BARRIER	FOOT	554	554		50300100	FLOOR DRAINS	EACH	12		12
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1	1		50300225	CONCRETE STRUCTURES	CU YD	24.7		24.7
40600300	AGGREGATE (PRIME COAT)	TON	4	4		50300255	CONCRETE SUPERSTRUCTURE	CU YD	121.2		121.2
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	2	2		50300260	BRIDGE DECK GROOVING	SQ YD	490		490
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	34	34		50300300	PROTECTIVE COAT	SQ YD	829		829
40600982	HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT	SQ YD	42	42		50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SQ FT	4637		4637
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	13	13		50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	36520		36520
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	73	73		50800515	BAR SPLICERS	EACH	336		336
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	54	54		50900305	STEEL RAILING, TYPE T1	FOOT	227		227
44000100	PAVEMENT REMOVAL	SQ YD	165	165		51500100	NAME PLATES	EACH	1		1
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	659	659		59000200	EPOXY CRACK INJECTION	FOOT	78		78

\* SPECIALTY ITEMS

**LONGO INC.**  
CONSULTING ENGINEERS  
1560 WALL ST, SUITE 222  
NAPERVILLE, ILLINOIS 60563 PH: (630) 577-9100

DESIGNED - MJY	REVISED -
DRAWN - ST, TSC	REVISED -
CHECKED - MJY, SLV	REVISED -
DATE - 06/25/2010	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES  
IL ROUTE 173 OVER DES PLAINES RIVER**

SCALE: NONE SHEET NO. 1 OF 2 SHEETS STA. 98+00 TO STA. 101+80

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	136 B-1	LAKE	43	3
D-91-290-09			CONTRACT NO. 60F93	
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		