

SUMMARY OF QUANTITIES			80% FEDERAL, 20% STATE			SUMMARY OF QUANTITIES			80% FEDERAL, 20% STATE		
CODE NO.	ITEM	UNIT	URBAN TOTAL	ROADWAY 1000-2A	BRIDGE X081-2A	CODE NO.	ITEM	UNIT	URBAN TOTAL	ROADWAY 1000-2A	BRIDGE X081-2A
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	330	330		78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	8	4	4
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4		* 81100600	CONDUIT ATTACHED TO STRUCTURE, 2" DIA, GALVANIZED STEEL	FOOT	114	114	
63200310	GUARDRAIL REMOVAL	FOOT	583	583		* 81300550	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" x 12" x 6"	EACH	2	2	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	9		* 81306500	REMOVE EXISTING JUNCTION BOX	EACH	2	2	
67100100	MOBILIZATION	L SUM	1	1		Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	103	103	
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1		* X0323710	REMOVE CONDUIT ATTACHED TO STRUCTURE	FOOT	114	114	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1		* Z0033024	MAINTAIN EXISTING LIGHTING SYSTEM	L SUM	1	1	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	24	24		Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	40		40
70400100	TEMPORARY CONCRETE BARRIER	FOOT	514	514		X7030104	PAVEMENT MARKING WET TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	4057	4057	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	514	514		X7030106	PAVEMENT MARKING WET TEMPORARY TAPE, TYPE III, 6 INCH	FOOT	203	203	
78000100	THERMOPLASTIC PAVEMENT MARKING-LETTERS AND SYMBOLS	SQ FT	110	110		X7030124	PAVEMENT MARKING WET TEMPORARY TAPE, TYPE III, 24 INCH	FOOT	64	64	
* 78000200	THERMOPLASTIC PAVEMENT MARKING-LINE 4"	FOOT	3733	3733		X7030120	PAVEMENT MARKING WET TEMPORARY TAPE, TYPE III, LETTERS AND SYMBOLS	SQ FT	110	110	
* 78000400	THERMOPLASTIC PAVEMENT MARKING-LINE 6"	FOOT	289	289		X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	490		490
* 78000600	THERMOPLASTIC PAVEMENT MARKING-LINE 12"	FOOT	234	234		Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	36		36
* 78000650	THERMOPLASTIC PAVEMENT MARKING-LINE 24"	FOOT	32	32		Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
* 78008210	POLYUREA PAVEMENT MARKING ^{TYPE I} - LINE 4"	FOOT	454	454		Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2	2	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	4	4		Z0030340	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2	2	
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	4		4	* Z0076600	TRAINEES	Hour	500	500	
* 78200500	BARRIER WALL MARKERS	EACH	22	22							
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1804	1804							

Yogo
* SPECIALTY ITEMS

LONGO, INC.
CONSULTING ENGINEERS
1560 WALL ST, SUITE 222
NAPERVILLE, ILLINOIS 60563 PH: 16301 577-9100

DESIGNED - MJY
DRAWN - ST, TSC
CHECKED - MJY, SLV
DATE - 06/25/2010

REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
IL ROUTE 173 OVER DES PLAINES RIVER

SCALE: NONE SHEET NO. 2 OF 2 SHEETS STA. 98+00 TO STA. 101+80

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	136 B-1	LAKE	43	4
D-91-290-09			CONTRACT NO. 60F93	
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		