

# SUMMARY OF QUANTITIES

PERCENTAGES							
LOCATION OF WORK				80% FED. / 20% STATE URBAN			
SUMMARY OF QUANTITIES				CONSTRUCTION CODE	Y031 1F	Y031 1F	Y031 1F
CODE NO.	ITEM	UNIT	GRAND TOTAL	LAWRENCE AVE. @ 25TH STREET	LAWRENCE AVE. @ FOSTER AVE.	LAWRENCE AVE. @ DES-PLAINES RIVER RD.	INTERCONNECT
67100100	MOBILIZATION	L SUM	1	0.25	0.25	0.25	0.25
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	0.25	0.25	0.25	0.25
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	0.25	0.25	0.25	0.25
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	0.25	0.25	0.25	0.25
81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	1038			226	812
81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	1182			57	1125
81400100	HANDHOLE	EACH	5				5
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1038			226	812
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	3	1	1	1	
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	2	1	1		
85700300	FULL-ACTUATED CONTROLLER AND TYPE V CABINET	EACH	1			1	
86000100	MASTER CONTROLLER	EACH	2			1	1
86400100	TRANSCEIVER - FIBER OPTIC	EACH	3	1	1	1	
<del>20030850</del>	TEMPORARY INFORMATION SIGNING	SQ FT	102.8				102.8
87900200	DRILL EXISTING HANDHOLE	EACH	5			1	4
<del>20033090</del>	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	3530				3530
X8710020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	3530				3530
X0325096	OPTIMIZE TRAFFIC SIGNAL SYSTEM	L SUM	1				1
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	1710	300		1410	
88500100	INDUCTIVE LOOP DETECTOR	EACH	21	6	7	8	
X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH	2		1	1	
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	3	1	1	1	
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO.6 2/C	FOOT	440		140	300	
X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO.6 1/C	FOOT	440		140	300	
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	375		125	250	