

URBAN
80% FED.
20% STATE

SUMMARY OF QUANTITIES

URBAN
80% FED.
20% STATE

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	X031-2A STRUCTURE	J000-2A ROADWAY
67100100	MOBILIZATION	L SUM	1		1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1		1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1		1
70103817	TRAFFIC CONTROL SURVEILLANCE (SPECIAL)	CAL DA	90		90
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	24		24
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4449		4449
70400100	TEMPORARY CONCRETE BARRIER	FOOT	787.5	125	662.5
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	600	125	475
72000100	SIGN PANEL - TYPE 1	SQ FT	10		10
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	73		73
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	5851		5851
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	601		601
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	115		115
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	132		132
78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	37		37
78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	2007		2007
78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	139		139
78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	50		50
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	72		72
78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	10		10
78100300	REPLACEMENT REFLECTOR	EACH	50		50
78200410	GUARDRAIL MARKERS, TYPE A	EACH	12		12
78200530	BARRIER WALL MARKERS, TYPE C	EACH	212		212
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4		4
78300100	PAVEMENT MARKING REMOVAL	SQ FT	3529		3529
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	82		82
* 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	53		53
* 81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	122		122
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	53		53
* 87900200	DRILL EXISTING HANDHOLE	EACH	6		6
* 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	2		2
* 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	1992		1992

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	X031-2A STRUCTURE	J000-2A ROADWAY
Z0030050	TEMPORARY INFORMATION SIGNING	SQ FT	115		115
* Z0033090	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	1023		1023
* Z0033060	PREFORMED DETECTOR LOOP	FOOT	128		128
Z0012755	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQ FT	128	128	
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	34	34	
Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	2		2
X7030104	WET TEMPORARY PAVEMENT MARKING TAPE, TYPE III, 4 INCH	FOOT	12771		12771
X7030124	WET TEMPORARY PAVEMENT MARKING TAPE, TYPE III, 24 INCH	FOOT	96		96
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	1		1
* X8710020	FIBER OPTIC CABLE IN CONDUIT, NO.62.5/125, MM12F SM12F	FOOT	1049		1049
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	2514		2514
Z0013798	CONSTRUCTION LAYOUT	L SUM	1		1
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	4		4
Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	2		2
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	58	58	
XX008341	BRIDGE FENCE RAILING (SPECIAL)	SQ FT	364	364	
Z0076600	TRAINERS	HOURL	1000	1000	
Z3700160	CONCRETE BARRIER, SINGLE FACE, 34 INCH HEIGHT	FOOT	179		179

© Y080
*specialty items

Rev.