



TEMPORARY RADIO INTERCONNECT TO ILL. RTE. 62 (ALGONQUIN RD.) AT CARRIAGE WAY (SEE TEMPORARY INTERCONNECT PLANS)

INTERCONNECT TO ILL. RTE. 62 (ALGONQUIN RD.) AT ILL. 53 EAST RAMP

SCHEDULE OF QUANTITIES

QUANTITY	UNIT	ITEM
1	EACH	TEMPORARY TRAFFIC SIGNAL INSTALLATION
1	EACH	TEMPORARY TRAFFIC SIGNAL TIMING

I.D.O.T. TRAFFIC SIGNAL INSTALLATION ELECTRICAL SERVICE REQUIREMENTS

TYPE	NO LAMPS	WATTAGE		%OPERATION	TOTAL WATTAGE
		INCAND.	LED		
SIGNAL (RED)	9	135	17	0.50	76.50
(YELLOW)	9	135	25	0.25	56.25
(GREEN)	11	135	15	0.25	41.25
ARROW		135	12	0.10	
PED. SIGNAL		90	25	1.00	
CONTROLLER	1	100	100	1.00	100
ILLUM. SIGN	1		25	1.00	25
FLASHER				0.50	
ENERGY COSTS TO:				TOTAL =	299

ENERGY SUPPLY CONTACT: ELEANOR SARALLO
PHONE: (630) 424-5124
COMPANY: COMMONWEALTH EDISON

ILLUMINATED SIGN, L.E.D. "NO LEFT TURN" (INCIDENTAL TO TEMPORARY SIGNAL INSTALLATION)

THE TRAFFIC SIGNAL CONTROL EQUIPMENT FOR THIS PROJECT SHALL BE "ECONOLITE" TO MATCH THE EXISTING ADJACENT SYSTEM.

THE EXISTING TRAFFIC SIGNAL CONTROLLER SHALL BE DISABLED AND TRAFFIC SIGNAL HEADS SHALL BE BAGGED DURING THE TIME WHEN TEMPORARY TRAFFIC SIGNAL INSTALLATION IS IN OPERATION. NO EXTRA COMPENSATION SHALL BE ALLOWED FOR THE SAME AND SHALL BE INCIDENTAL TO PAY ITEM "TEMPORARY TRAFFIC SIGNAL INSTALLATION"