

SUMMARY OF QUANTITIES			100% STATE			SUMMARY OF QUANTITIES			100% STATE		
CODE NO.	ITEM	UNIT	URBAN TOTAL	ROADWAY 1000-2A	BOX CULVERT X028-2A	CODE NO.	ITEM	UNIT	URBAN TOTAL	ROADWAY 1000-2A	BOX CULVERT X028-2A
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	48	48		40600982	HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT	SQ YD	108	108	
20200100	EARTH EXCAVATION	CU YD	1110	4	1096	40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	30	30	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	212		212	40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	59	59	
X2090210	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	212		212	40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	129	129	
21101815	COMPOST FURNISH AND PLACE, 4"	SQ YD	1263	1263		44000100	PAVEMENT REMOVAL	SQ YD	173	173	
25000310	SEEDING, CLASS 4	ACRE	0.3	0.3		44000160	HOT-MIX ASPHALT SURFACE REMOVAL, 2 3/4"	SQ YD	467	467	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	23	23		44004250	PAVED SHOULDER REMOVAL	SQ YD	186	128	58
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	23	23		44002211	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 2 3/4"	SQ YD	195	195	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	23	23		44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	45	45	
25100630	EROSION CONTROL BLANKET	SQ YD	1263	1263		44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	60	60	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	27	27		44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	90	90	
28000305	TEMPORARY DITCH CHECKS	FOOT	66	66		48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	35	35	
28000400	PERIMETER EROSION BARRIER	FOOT	870	870		48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	461	427	34
28000510	INLET FILTERS	EACH	2	2		50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
28100109	STONE RIPRAP, CLASS A5	SQ YD	243		243	50105220	PIPE CULVERT REMOVAL	FOOT	124	124	
28200200	FILTER FABRIC	SQ YD	407		407	50200100	STRUCTURE EXCAVATION	CU YD	587		587
35501300	HOT-MIX ASPHALT BASE COURSE, 4"	SQ YD	496	496		50300300	PROTECTIVE COAT	SQ YD	17		17
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1	1		50800105	REINFORCEMENT BARS	POUND	3600		3600
40600300	AGGREGATE (PRIME COAT)	TON	1	1		50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	250		250
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	21	21							

* SPECIALTY ITEMS

LOCO INC.
CONSULTING ENGINEERS
1560 WALL ST. SUITE 222
NAPERVILLE, ILLINOIS 60563 PH (630) 577-9100

DESIGNED - MJY	REVISED -
DRAWN - ST, TSC	REVISED -
CHECKED - SLV	REVISED -
DATE - 06/25/2010	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES
WEST RIVER ROAD OVER UNNAMED TRIBUTARY (0.1 MI N OF IL RT 113)**

SCALE: NONE SHEET NO. 1 OF 2 SHEETS STA. 81+40 TO STA. 84+20

F.A.U. RTE. 0327	SECTION 112 T-2	COUNTY WILL	TOTAL SHEETS 22	SHEET NO. 3
D-91-198-10		CONTRACT NO. 60J17		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		