

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	URBAN - 100 % STATE				STRUCTURAL	
				I-JO00-2A	LIGHTING Y030-1E	SIGNING Y002-1C	SAFETY Y032-1F	SN016-1251 X271-2A	SN016-1252 X271-2A
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	147	147					
20100500	TREE REMOVAL, ACRES	ACRE	0.50	0.50					
20200100	EARTH EXCAVATION	CU YD	40,940	40,940					
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	9115	9115					
20400800	FURNISHED EXCAVATION	CU YD	42,015	42,015					
20700220	POROUS GRANULAR EMBANKMENT	CU YD	362	362					
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	224.8					224.8	
20800150	TRENCH BACKFILL	CU YD	19,272	19,272					
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	22,285	22,285					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	61718	61718					
X2130010	EXPLORATION TRENCH, SPECIAL	FOOT	220	220					
25000210	SEEDING, CLASS 2A	ACRE	13	13					
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1148	1148					
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1148	1148					
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1148	1148					
25100115	MULCH, METHOD 2	ACRE	4.25	4.25					
25100125	MULCH, METHOD 3	ACRE	8.25	8.25					
25100630	EROSION CONTROL BLANKET	SQ YD	101,648	101,648					
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1250	1250					
28000305	TEMPORARY DITCH CHECKS	FOOT	324	324					
28000400	PERIMETER EROSION BARRIER	FOOT	9046	9046					
28000500	INLET AND PIPE PROTECTION	EACH	17	17					
28000510	INLET FILTERS	EACH	190	190					
28100105	STONE RIPRAP, CLASS A3	SQ YD	130	130					
28100107	STONE RIPRAP, CLASS A4	SQ YD	110	110					
28100109	STONE RIPRAP, CLASS A5	SQ YD	145	145					
28100111	STONE RIPRAP, CLASS A6	SQ YD	70	70					
28100500	BROKEN CONCRETE RIP RAP	SQ YD	96	96					
28200200	FILTER FABRIC	SQ YD	455	455					
X3120500	STABILIZED SUBBASE- HOT-MIX ASPHALT, 4 1/2"	SQ YD	48,377	48,377					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	51.3	51.3					
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	22	22					
40600300	AGGREGATE (PRIME COAT)	TON	20	20					
40600895	CONSTRUCTING TEST STRIP	EACH	7	7					

TYLIN INTERNATIONAL

USER NAME =	DESIGNED - CAC	REVISED -
PLOT SCALE =	DRAWN - CAC	REVISED -
PLOT DATE =	CHECKED - JDF	REVISED -
	DATE - 3/18/2010	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

I-57 AT I-294 INTERCHANGE PROJECT			
SUMMARY OF QUANTITIES			
SCALE: NTS	SHEET NO. 1 OF 9 SHEETS	STA.	TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	1414.2B	COOK	516	4
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 60J27	

Rev.