

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	URBAN - 100% STATE				STRUCTURAL	
				I-57 J000-2A	LIGHTING Y030-1E	SIGNING Y002-1C	SAFETY Y032-1F	SN016-1251 X271-2A	SN016-1252 X271-2A
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	158	158					
40603148	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, STONE MATRIX ASPHALT, N80	TON	1890	1890					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1377	1377					
40603153	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	5801	5801					
42000521	PORTLAND CEMENT CONCRETE PAVEMENT 11" (JOINTED)	SQ YD	3422	3422					
42001300	PROTECTIVE COAT	SQ YD	18,878	18,878					
42100200	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 9"	SQ YD	13997	13997					
42100360	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 13"	SQ YD	2826	2826					
42100800	PAVEMENT REINFORCEMENT 9"	SQ YD	13997	13997					
42100960	PAVEMENT REINFORCEMENT 13"	SQ YD	2826	2826					
42101448	LUG SYSTEM COMPLETE 48'	EACH	2	2					
44000100	PAVEMENT REMOVAL	SQ YD	4421	4421					
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	16,384	16,384					
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	208	208					
44000700	APPROACH SLAB REMOVAL	SQ YD	512					512	
44004250	PAVED SHOULDER REMOVAL	SQ YD	23,764	23,764					
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	83	83					
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	127	127					
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	10954	10954					
48101700	AGGREGATE SHOULDERS (SPECIAL)	CU YD	27	27					
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	921	921					
48203033	HOT-MIX ASPHALT SHOULDERS, 9"	SQ YD	874	874					
48300800	PORTLAND CEMENT CONCRETE SHOULDERS 13"	SQ YD	6019	6019					
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1					1	
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1					1	
50104400	CONCRETE HEADWALL REMOVAL	EACH	3	3					
50157300	PROTECTIVE SHIELD	SQ YD	2749					2749	
50200100	STRUCTURE EXCAVATION	CU YD	18,681	3772				6889	8020
50300225	CONCRETE STRUCTURES	CU YD	2216.4					1664.7	551.7
50300255	CONCRETE SUPERSTRUCTURE	CU YD	3179.8					2128.0	1051.8
50300260	BRIDGE DECK GROOVING	SQ YD	8977					6466	2511
50300280	CONCRETE ENCASEMENT	CU YD	63.9					63.9	
50300300	PROTECTIVE COAT	SQ YD	10667					7519	3148
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1.0					0.8	0.2

TYLIN INTERNATIONAL	USER NAME =	DESIGNED - CAC	REVISED -
	PLOT SCALE =	DRAWN - CAC	REVISED -
	PLOT DATE =	CHECKED - JDF	REVISED -
		DATE - 3/18/2010	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**I-57 AT I-294 INTERCHANGE PROJECT  
SUMMARY OF QUANTITIES**

SCALE: NTS    SHEET NO. 2 OF 9 SHEETS    STA.    TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	1414.2B	COOK	515	5
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 60J27	