

| CODE NUMBER | ITEM DESCRIPTION | UNIT | TOTAL | URBAN - 100% STATE | | | | STRUCTURAL | |
|-------------|---|-----------------|-----------------|--------------------|------------------|-----------------|----------------|--------------------|--------------------|
| | | | | 1-57 J000-2A | LIGHTING Y030-1E | SIGNING Y002-1C | SAFETY Y032-1F | SNO16-1251 X271-2A | SNO16-1252 X271-2A |
| | | | | | | | | | |
| 78005140 | EPOXY PAVEMENT MARKING - LINE 8" | FOOT | 2654 | 2654 | | | | | |
| 78005150 | EPOXY PAVEMENT MARKING - LINE 12" | FOOT | 2892 | 2892 | | | | | |
| 78008210 | POLYUREA PAVEMENT MARKING TYPE 1 - LINE 4" | FOOT | 3122 | 3122 | | | | | |
| 78008220 | POLYUREA PAVEMENT MARKING TYPE 1 - LINE 5" | FOOT | 781 | 781 | | | | | |
| * 78008240 | POLYUREA PAVEMENT MARKING TYPE 1 - LINE 8" | FOOT | 3347 | 3347 | | | | | |
| 78008250 | POLYUREA PAVEMENT MARKING TYPE 1 - LINE 12" | FOOT | 1122 | 1122 | | | | | |
| 78100100 | RAISED REFLECTIVE PAVEMENT MARKER | EACH | 540 | 540 | | | | | |
| 78100105 | RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE) | EACH | 46 | 46 | | | | | |
| 78100200 | TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER | EACH | 378 | 378 | | | | | |
| * 78100300 | REPLACEMENT REFLECTOR | EACH | 1049 | 1049 | | | | | |
| * 78200100 | MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR | EACH | 2520 | 2520 | | | | | |
| * 78200410 | GUARDRAIL MARKERS, TYPE A | EACH | 32 | 32 | | | | | |
| 78300100 | PAVEMENT MARKING REMOVAL | SQ FT | 24,197 | 24,197 | | | | | |
| 81000600 | CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL | FOOT | 242 | | | 242 | | | |
| 81000800 | CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL | FOOT | 87 | | | 87 | | | |
| 81001000 | CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL | FOOT | 1620 | | | 1620 | | | |
| J1013000 | CONDUIT IN TRENCH, 4" DIA., PVC | FOOT | 870 | | | 870 | | | |
| 81025600 | CONDUIT ENCASED, REINFORCED CONCRETE, 4" DIA., PVC 2 WIDE X 1 HIGH | FOOT | 7764 | | | 7764 | | | |
| 81025700 | CONDUIT ENCASED, REINFORCED CONCRETE, 4" DIA., PVC 3 WIDE X 1 HIGH | FOOT | 1577 | | | 1577 | | | |
| 81100320 | CONDUIT ATTACHED TO STRUCTURE, 1" DIA., PVC COATED GALVANIZED STEEL | FOOT | 420 | | 420 | | | | |
| 81100605 | CONDUIT ATTACHED TO STRUCTURE, 2" DIA., PVC COATED GALVANIZED STEEL | FOOT | 20 | | 20 | | | | |
| 81101000 | CONDUIT ATTACHED TO STRUCTURE, 4" DIA., GALVANIZED STEEL | FOOT | 878 | | | 878 | | | |
| * 81101005 | CONDUIT ATTACHED TO STRUCTURE, 4" DIA., PVC COATED GALVANIZED STEEL | FOOT | 919 | | 247 | 672 | | | |
| 81200230 | CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC | FOOT | 1232 | | | 1232 | | | |
| 81200270 | CONDUIT EMBEDDED IN STRUCTURE, 4" DIA., PVC | FOOT | 7880 | | 284 | 7596 | | | |
| 81300220 | JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 6" X 6" X 4" | EACH | 14 | | 14 | | | | |
| 81300530 | JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 10" X 6" | EACH | 1 | | 1 | | | | |
| * 81300555 | JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 12" X 8" | EACH | 4 | | 4 | | | | |
| 81304200 | JUNCTION BOX EMBEDDED IN STRUCTURE 12" X 12" X 8" | EACH | 8 | | | 8 | | | |
| 81300810 | JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 18" X 12" X 8" | EACH | 3 | | | 3 | | | |
| 81400200 | HEAVY-DUTY HANDHOLE | EACH | 29 | | | 29 | | | |
| * 81603203 | UNIT DUCT, 600V, 3-1/C NO. 2, 1/C NO. 4 GROUND (EPR-TYPE RHW), 1 1/2" DIA., POLYETHYLENE | FOOT | 3037 | | 3037 | | | | |
| 81700335 | ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE USE) 3-1/C NO. 6 | FOOT | 2551 | | | 2551 | | | |
| 81800330 | AERIAL CABLE, 3-1/C NO. 6 WITH MESSENGER WIRE | FOOT | 1116 | | | 1116 | | | |
| 81800400 | AERIAL CABLE, 4-1/C NO. 2 WITH MESSENGER WIRE | FOOT | 2082 | | 2082 | | | | |

*SPECIALTY ITEMS

Rev. 5-27-10

| | | | | | | | | | | | | |
|---------------------|--------------|----------------|-----------|---|--|-------------------------|--------------|--------------------|-----------------|-------------|------------------|-------------|
| TYLIN INTERNATIONAL | USER NAME = | DESIGNED - CAC | REVISED - | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | I-57 AT I-294 INTERCHANGE PROJECT SUMMARY OF QUANTITIES | | | F.A.I. RTE. 57 | SECTION 1414.2B | COUNTY COOK | TOTAL SHEETS 516 | SHEET NO. 9 |
| | PLOT SCALE = | DRAWN - CAC | REVISED - | | SCALE: NTS | SHEET NO. 6 OF 9 SHEETS | STA. TO STA. | CONTRACT NO. 60J27 | | | | |
| | PLOT DATE = | CHECKED - JDF | REVISED - | | FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT | | | | | | | |
| DATE - 3/18/2010 | | REVISED - | | | | | | | | | | |