

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	URBAN - 100% STATE				STRUCTURAL	
				I-57 J000-2A	LIGHTING Y030-1E	SIGNING Y002-1C	SAFETY Y032-1F	SNO16-1251 X271-2A	SNO16-1252 X271-2A
X7013020	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	GAL BA	399	399					
X7040010	TEMPORARY CONCRETE BARRIER (SPECIAL)	FOOT	3790	3790					
X8160370	UNIT DUCT, WITH 3 1/4" NO. 4 AND 1/4" NO. 6 GROUND, 600V (EPR TYPE RHM), 1 1/4" DIA., POLYETHYLENE	FOOT	3242	3242					
X8360360	LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 10" X 8"	EACH	2	2					
X8710027	FIBER OPTIC CABLE 4 FIBERS, SINGLE MODE	FOOT	681			681			
X8710035	FIBER OPTIC CABLE 96 FIBERS, SINGLE MODE	FOOT	41443			41,443			
Z0034210	MECHANICALLY STABILIZED EARTH RETAINING WALL	SQ FT	14415				4860	9555	
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	53,113	53,113					
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.5			0.3	0.2	
Z0018400	DRAINAGE STRUCTURES TO BE ADJUSTED	EACH	10	10					
Z0018600	DRAINAGE STRUCTURES TO BE RECONSTRUCTED	EACH	9	9					
Z0018800	DRAINAGE SYSTEM	L SUM	1			0.80	0.20		
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	6	6					
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	13	13					
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	14	14					
Z0076600	TRAINEES	HOUR	0	0					
48300600	PORTLAND CEMENT CONCRETE SHOULDERS 11"	SQ YD	1064	1064					
48203049	HOT-MIX ASPHALT SHOULDERS, 13"	SQ YD	20,567	20,567					
60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	2	2					
60204505	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	4	4					
60224448	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 8 GRATE	EACH	1	1					
X0301892	MANHOLES, TYPE A, 8'-DIAMETER, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	2	2					
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	28,325	28,325					
550A0190	STORM SEWERS, CLASS A, TYPE 1 48"	FOOT	2	2					
550A5500	STORM SEWERS, CLASS A, TYPE 2 EQUIVALENT ROUND-SIZE 42"	FOOT	916	916					
X0322441	DIGITAL LOOP DETECTOR SENSOR UNIT (4 CHANNEL)	EACH	1						
X0322442	TONE EQUIPMENT - 3 FREQUENCY RECEIVER PROGRAMMABLE	EACH	4			4			
X0322443	TONE EQUIPMENT - 3 FREQUENCY TRANSMITTER PROGRAMMABLE	EACH	4			4			
51201800	FURNISHING STEEL PILES HP 14 X 73	FOOT	11,501	11,501					
51203800	TEST PILE HP 14 X 73	EACH	2	2					

(50Q Cont.)

Code No.	Item Description	Unit	URBAN 100% STATE TOTAL QUANTITY	I-57 J000-2A	Lighting Y030-1E
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	37,549	37,549	
*78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	10,281	10,281	
*78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	4,020	4,020	
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2,314	2,314	
X0326405	TEMPORARY FENCE (PRAIRIE PROTECTION)	FOOT	6,220	6,220	
*50200400	ROCK EXCAVATION FOR STRUCTURES	CY YD	34		34
*82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	2		2
*82105600	LUMINAIRE, SODIUM VAPOR, HIGH MAST, HORIZONTAL MOUNT, 400 WATT	EACH	40		40
*83050810	LIGHT POLE, ALUMINUM, 47.5 FT M.H., 15FT. MAST ARM	EACH	2		2
*83504700	LIGHT TOWER, 120 FT. MOUNTING HEIGHT, LUMINAIRE MT.-12	EACH	7		7
*83505700	LIGHT TOWER, 130 FT. MOUNTING HEIGHT, LUMINAIRE MT.-12	EACH	1		1
*83700250	LIGHT TOWER FOUNDATION, 44" DIAMETER	FOOT	170		170
*83700300	LIGHT TOWER FOUNDATION, 48" DIAMETER	FOOT	30		30
*X0322434	LIGHT TOWER, SERVICE PAD, SPECIAL	EACH	8		8
*X0325132	SHAPING AND GRADING AT HIGH MAST LIGHT TOWER	SQ YD	170		170
*8357595	LIGHT POLE, WOOD, 100 FT. CLASS 4, WITH 15 FT MAST ARM	EACH	8		8
*84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	12		12
*X8210015	TEMPORARY LUMINAIRE, HIGH PRESSURE SODIUM VAPOR, 400 WATT	EACH	8		8

50Q Cont

* Specialty Items