

P:\602540\57-294\Road\PI_157_BR\PI_SIGNSchedule.dgn 4/29/2010 8:09:58 AM

SIGN SCHEDULE

EXISTING LOCATION				REMAIN IN PLACE	RELOCATE SIGN PANEL	PROPOSED OVERLAY	RELOCATED SIGNS - POST QUANTITY	RELOCATED SIGNS- WOOD POST LENGTH (FT)	STRUCTURAL STEEL SIGN SUPPORT BREAKAWAY (POUND)	STRUCTURAL STEEL SIGN SUPPORT BREAKAWAY- POST TYPE	CONCRETE FOUNDATION (CU YD)	RELOCATE SIGN PANEL ASSEMBLY - TYPE B (EACH)	SIGN DESCRIPTION
LOCATION	STATION	OFFSET (FT)	MOUNTING										
NB I-57 (159th ST. Entrance Ramp)	1172+93	170.5' RT	LIGHT POLE	1									NORTH I-57 & ARROW
NB I-57 (159th ST. Entrance Ramp)	1173+55	360.0' RT	LIGHT POLE	1									NORTH I-57 & ARROW
NB I-57	1188+16	104.9' RT	LIGHT POLE	1									NORTH I-57
NB I-57	1190+56	96.0' RT	LIGHT POLE	1									SPEED LIMIT 55
NB I-57	1222+49	81.1' RT	WOOD POSTS	1									KEDZIE AVE.
NB I-57	1222+60	OVERHEAD	BRIDGE	1									EXIT 350, (IL83) 147TH ST - SIBLEY BLVD, 1 MILE
NB I-57	1228+74	79.6' RT	LIGHT POLE	1									MILE 349
NB I-57	1230+74	85.7' RT	WOOD POSTS	1									ACCIDENT INVESTIGATION SITE, 1 MILE
NB I-57	1250+21	OVERHEAD	TRUSS			4 MILES	2		2790	W16X45	4.46	1	EXIT 353, 127TH ST BURR OAK AVE, 3 1/2 MILES
NB I-57	1250+21	OVERHEAD	TRUSS			3/4 MILE	2		2790	W16X45	4.46	1	EXIT 350, (IL83) SIBLEY BLVD, 147TH ST, 1/2 MILE
NB I-57	1254+20	85.7' RT	WOOD POSTS		1	3/4 MILE	2	32.66					ACCIDENT INVESTIGATION SITE, 1/2 MILE
NB I-57	1256+85	86.0' RT	WOOD POSTS		1		2	34.66					POSEN, HARVEY, MIDLOTHIAN, EXIT 350
NB I-294	405+85	84.8' RT	WOOD POSTS		1		2	28.66					INTERSTATE 57
SB I-57 (159th ST. Entrance Ramp)	1172+26	346.4' LT	METAL POST	1									SOUTH I-57 & ARROW
SB I-57 (159th ST. Entrance Ramp)	1172+82	168.7' LT	LIGHT POLE	1									SOUTH I-57 & ARROW
SB I-57	1189+30	70.2' LT	LIGHT POLE	1									EXIT 348 & ARROW
SB I-57	1192+24	95.5' LT	LIGHT POLE	1									RAMP 30 M.P.H
SB I-57	1193+24	OVERHEAD	CANTILEVER	1									EXIT 348, 159TH ST & ARROW
SB I-57	1223+69	77.9' LT	WOOD POSTS	1									KEDZIE AVE.
SB I-57	1223+58	OVERHEAD	BRIDGE	1									EXIT 348, 159TH ST 3/4 MILES
SB I-57	1223+58	OVERHEAD	BRIDGE	1									EXIT 348, 167TH ST 1 3/4 MILES
SB I-294	406+98	72.0' LT	WOOD POSTS		1		2	28.66					INTERSTATE 57
SB I-57	1268+56	84.0' LT	LIGHT POLE	1									SPEED LIMIT 55
SB I-57	1272+03	88.5' LT	LIGHT POLE	1									SOUTH I-57

TYLIN INTERNATIONAL	USER NAME =	DESIGNED - DM	REVISED - 4/29/2010	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	I-57 AT I-294 INTERCHANGE PROJECT SIGN SCHEDULE			F.A.T. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE =	DRAWN - DM	REVISED -		57	1414.2B	COOK	516	239			
	PLOT DATE =	CHECKED - JPM	REVISED -		SCALE: SHEET NO. 1 OF 1 SHEETS STA. TO STA.			CONTRACT NO. 60J27				
		DATE - 3/18/2010	REVISED -		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT							