

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

GENERAL NOTES

Fasteners shall be AASHTO M164 Type 1, mechanically galvanized bolts.
Bolts 7/8-in.φ, holes 15/16-in.φ, unless otherwise noted.

Calculated weight of Structural Steel =
Grade 50 = 323,180 lbs
Grade 36 = 33,700 lbs

No field welding is permitted except as specified in the contract documents.

Reinforcement bars shall conform to the requirements of ASTM A 706
Gr 60. See Special Provisions.

Reinforcement bars designated (E) shall be epoxy coated.

If the Contractor elects to use cantilever forming brackets on the exterior
beams or girders, the brackets shall be placed at the same locations as
required for the hardwood blocks in Article 503.06(b) of the Standard
Specifications. If additional cantilever forming brackets are required,
hardwood blocking shall be wedged between the exterior and first interior
beam at each of these additional bracket locations.

Concrete Sealer shall be applied to the exposed surfaces of backwalls, bridge seats
and front face of pile caps at the abutments.

The Organic Zinc Rich Primer / Epoxy / Urethane Paint System shall be used
for painting of new structural steel except where otherwise noted. The entire
system shall be shop applied, with the exception that masked off connection
surfaces, field installed fasteners and damaged areas shall be touched up in the
field. The color of the final finish coat for all interior steel surfaces shall be
Gray, Munsell No. 5B 7/1. The color of the final finish coat for the exterior
and bottom flange of the fascia beams shall be Interstate Green, Munsell
No. 7.5G 4/8. See Special Provision for "Cleaning and Painting New Metal
Structures".

Slipforming of the parapet is not allowed.

The conduit shown embedded in structure and attached to structure is paid for in the Roadway Plans.

It shall be the Contractor's responsibility to verify the location of all fiber optic utilities prior to starting
construction. The Contractor shall initiate the locate process for the fiber optic cable by completing
a "Request to Locate Tollway Facilities" form (Tollway Form A-36) and submitting it to the Tollway.
Copies of Form A-36 are available from the Tollway's Utility/Permit Section (630-241-6800, ext 3306).
Completed A-36 forms shall be faxed to the Tollway to the attention of Tollway Utility Administrator
at 630-271-7568, at least four (4) business days prior to starting any underground operations,
excavations or digging of any type in general area of the fiber optic cable.

INDEX OF SHEETS

1	General Plan & Elevation
2	Gen Notes, Index of Sheets, Bill of Material
3	Stage Construction
4	Stage Construction Details
5	Temporary Concrete Barrier
6	Top of Slab Elevations - Layout
7	Top of Slab Elevations-SB 157 - 1
8	Top of Slab Elevations -SB 157 - 2
9	Top of Slab Elevations -SB & NB I-57
10	Top of Slab Elevations-NB 157 - 1
11	Top of Slab Elevations-NB 157 & C-D Road A
12	Top of Slab Elevations C-D Road A
13	Top of West Approach Slab Elevations - 1
14	Top of West Approach Slab Elevations - 2
15	Top of East Approach Slab Elevations - 1
16	Top of East Approach Slab Elevations - 2
17	Superstructure - SB 157
18	Superstructure - NB 157
19	Superstructure - C-D Road A
20	Parapet Elevations
21	Superstructure Details
22-27	West Approach Slab Details
28-33	East Approach Slab Details
34	West Anchorage Slab Details
35	East Anchorage Slab Details
36	Anchorage Slab Details
37	Drainage Details
38	Drainage Scupper, DS II
39	Preformed Joint Strip Seal
40	Framing Plan
41	Structural Steel Details
42	Bearing Details
43	West Abutment - 1
44	West Abutment - 2
45	West Abutment - 3
46	West Abutment Details
47	East Abutment - 1
48	East Abutment - 2
49	East Abutment - 3
50	East Abutment Details
51	West Mechanically Stabilized Earth Retaining Wall
52	West Mechanically Stabilized Earth Retaining Wall Details
53	East Mechanically Stabilized Earth Retaining Wall
54	East Mechanically Stabilized Earth Retaining Wall Details
55	Bar Splicer Assembly and Mechanical Splicer Details
56	HP Pile Details
57-62	Boring Logs

TOTAL BILL OF MATERIAL

ITEM	UNIT	SUPER	SUB	TOTAL
Structure Excavation	Cu Yd		8,020	8,020
Concrete Structures	Cu Yd		551.7	551.7
Concrete Superstructure	Cu Yd	1,051.8		1,051.8
Bridge Deck Grooving	Sq Yd	2,511		2,511
Protective Coat	Sq Yd	3,148		3,148
Furnishing and Erecting Structural Steel	L Sum	0.20		0.20
Stud Shear Connectors	Each	9,765		9,765
Reinforcement Bars, Epoxy Coated	Pound	239,520	58,330	297,850
Bar Splicers	Each	396		396
Furnishing Steel Piles HP12x53	Foot		3,774	3,774
Driving Piles	Foot		3,774	3,774
Test Pile Steel HP12x53	Each		2	2
Pile Shoes	Each		104	104
Name Plates	Each	1		1
Preformed Joint Strip Seal	Foot	385.0		385.0
Elastomeric Bearing Assembly, Type I	Each	31		31
Anchor Bolts, 1"	Each	124		124
Concrete Sealer	Sq Ft		3,260	3,260
Drainage Scuppers, DSII	Each	6		6
Temporary Soil Retention System	Sq Ft		6,820	6,820
Mechanically Stabilized Earth Retaining Wall	Sq Ft		9,555	9,555
Drainage System	L Sum	0.20		0.20

**GENERAL NOTES, INDEX OF SHEETS,
BILL OF MATERIAL
STRUCTURE NO. 016-1252**

TYLIN INTERNATIONAL	DESIGNED - DY	REVISIONS		SHEET NO. 2	F.A.I RTE. 57	SECTION 1414.2B	COUNTY COOK	TOTAL SHEETS 516	SHEET NO. 315
	CHECKED - AD,LS	NAME	DATE						
	DRAWN - DY,EI								
	CHECKED - LS,SP,PDF								
	DATE - 03/18/10	Δ REVISED	05/24/10						
					62 SHEETS				
					CONTRACT NO. 60J27				
					FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

F:\602540\57-294\STRUCTURE\1-57-OVER-RAMP-B.N.I.rpt.submittal_03172010\0161252-60J27-002-GENNOTES.BOM.dgn 5/21/2010 2:18:16 PM