

CONTRACT NO. 63348

CURB AND GUTTER REMOVAL AND REPLACEMENT SCHEDULE					
STA.	SIDE	44001700 COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REP. LENGTH (FT)	STA.	SIDE	44001700 COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REP. LENGTH (FT)
1+50	RT	32	22+15	RT	30
2+00	RT	18	22+50	RT	20
3+00	RT	14	22+70	LT	7
3+20	RT	5	23+00	RT	13
3+50	RT	54	23+50	RT	7
4+00	LT	21	25+00	LT	15
4+45	LT	17	25+30	RT	22
4+50	RT	5	25+30	LT	15
4+80	RT	8	25+50	LT	12
5+40	LT	30	25+70	RT	18
5+60	RT	8	25+70	LT	5
6+00	LT	20	26+15	LT	16
6+30	LT	8	26+40	RT	5
7+40	LT	8	26+60	RT	5
7+50	LT	23	27+00	RT	67
8+15	RT	22	27+50	LT	33
8+40	LT	10	27+70	RT	5
8+55	LT	12	27+90	RT	5
9+00	RT	10	28+10	LT	16
10+00	LT	32	28+15	RT	5
10+50	RT	27	28+50	RT	15
11+50	LT	22	28+80	LT	5
12+00	RT	5	29+00	RT	10
12+00	LT	10	29+20	RT	15
12+40	RT	27	29+50	RT	5
13+00	RT	7	30+00	RT	14
13+15	LT	5	30+10	RT	5
13+50	RT	9	30+30	LT	12
13+90	RT	14	30+50	LT	15
14+35	RT	10	30+65	RT	5
14+60	RT	25	31+00	RT	15
14+90	LT	35	31+00	LT	40
15+30	RT	5	31+35	RT	15
15+35	RT	22	31+60	LT	5
15+50	LT	10	31+80	LT	5
16+65	LT	10	31+90	RT	25
17+00	RT	10	32+00	LT	10
17+40	RT	5	32+15	LT	5
17+50	RT	30	32+30	RT	12
17+60	LT	15	32+40	LT	5
18+00	LT	5	32+50	LT	5
18+40	LT	15	32+80	RT	5
18+70	RT	15	33+00	LT	22
18+80	LT	25	33+45	LT	9
19+00	RT	28	33+60	LT	5
19+10	LT	21	33+80	RT	15
19+35	LT	7	34+15	LT	12
20+50	RT	20	34+20	RT	15
20+70	LT	38	34+40	LT	12
21+00	RT	8	35+60	RT	5
21+20	RT	20	35+60	LT	10
21+45	LT	20	35+80	RT	15
21+50	RT	45	VARIOUS LOCATIONS STA. 26+95 TO 27+95		140
21+60	LT	22	VARIOUS LOCATIONS STA. 28+20 TO 30+00		100
22+10	LT	30	VARIOUS LOCATIONS STA. 30+25 TO 33+25		100
			VARIOUS LOCATIONS STA. 33+50 TO 36+12		200
					2208
					FEET

PATCHING SCHEDULE									
STA.	SIDE	PATCH WIDTH (FT)	PATCH LENGTH (FT)	PATCH AREA (SQ. FT.)	20201200 REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU. YD.)	20700420 POROUS GRANULAR EMBANKMENT SUBGRADE (CU. YD.)	44201705 CLASS D PATCHES TYPE II, 5" (SQ. YD.)	44201709 CLASS D PATCHES TYPE III, 5" (SQ. YD.)	44201711 CLASS D PATCHES TYPE IV, 5" (SQ. YD.)
7+00	RT	16	34	544	15	15			60
10+15	RT	6	18	108			12		
17+45	RT	12	35	420					47
18+10	LT	6	19	114			13		
26+15	LT	5	70	350					39
27+48	RT	12	19	228				25	
27+55	LT	10	22.5	225				25	
29+20	LT	7	70	490	15	15			54
					30	30	25	50	200
					CY	CY	SQ YD	SQ YD	SQ YD

DRAINAGE AND UTILITY STRUCTURE SCHEDULE			
STA.	SIDE	60255500 MANHOLES TO BE ADJUSTED	60262700 INLETS TO BE RECONSTRUCTED
11+10	RT		1
12+55	LT	1	
19+60	LT	1	
20+10	RT		
33+75	LT		1
		2	2
		EACH	EACH

VILLAGE OF WOODRIDGE PUBLIC WORKS
 1 Plaza Drive, Woodridge IL 60517 (630) 719-4753

**WOODRIDGE DRIVE
 REHABILITATION PROJECT**

SCHEDULE OF QUANTITIES

DRAWN BY: AF CHECKED BY: SM