

Specialty Item	SP	CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	ROADWAY			SIDEWALK		LIGHTING		WATER MAIN & SANITARY SEWER
						70% STP 30% LOCAL	80% CMAQ 20% LOCAL	WASHINGTON STREET 100% LOCAL	80% CMAQ 20% LOCAL	100% LOCAL	70% STP 30% LOCAL	100% LOCAL	100% LOCAL
						I000-2A	I000-2A	I000-2A	SFTY -1B	SFTY -1B	Y030-1E	Y030-1E	Y060
X	*	X10010054	SANITARY MANHOLES TO BE REMOVED	EACH	14								14
	*	X0321158	PARK BENCHES	EACH	5		5						
X	*	X10010050	SANITARY MANHOLES TO BE ADJUSTED	EACH	18								18
	*	Z0020850	TEMPORARY INFORMATION SIGNING	SQ FT	16	16							
	*	X1010080	STORM SEWERS, (WATER MAIN QUALITY PIPE) TYPE 1, 12"	FOOT	123	123							
X	*	X1010710	WATER MAIN REMOVAL 10"	FOOT	208								208
	*	X1010099	STORM SEWERS, (WATER MAIN QUALITY PIPE) TYPE 2, 12"	FOOT	363	363							
	*	X0324627	STORM SEWER (WATER MAIN REQUIREMENTS), EQUIVALENT ROUND-SIZE 24"	FOOT	168	168							
X	*	X0325014	WATER SERVICE INSTALLATION 2"	EACH	1								1
	*	X1008401	BOX CULVERT REMOVAL	FOOT	40	40							
	*	Z0010450	TEMPORARY PAVEMENT	SQ YD	318	318							
	*	X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	96	96							
	*	X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	20	20							
X	*	X8950200	REBUILD EXISTING HANDHOLE	EACH	2	2							
	*	XX000959	TRASH RECEPTACLES	EACH	10			10					
X	*	XX001011	BICYCLE RACKS	EACH	6		6						
X	*	XX001466	SANITARY SEWER, PVC, 12"	FOOT	155								155
X	*	XX001467	SANITARY SEWERS, PVC, 15"	FOOT	333								333
X	*	XX001470	SANITARY SERVICE CONNECTION	EACH	75								75
X	*	XX005878	CAST IRON TREE GRATES	EACH	24			24					
X	*	XX006247	SANITARY SEWER REMOVAL	FOOT	822			28					794
	*	XX006931	STORM SEWER (WATER MAIN REQUIREMENTS) SPAN 53, RISE 34	FOOT	39	39							
X	*	XX007039	STREET LIGHTING ASSEMBLY COMPLETE TYPE F1	EACH	3							3	
X	*	XX007040	STREET LIGHTING ASSEMBLY COMPLETE TYPE F2	EACH	16							16	
	*	X1010077	STORM SEWERS, TYPE 1, WATER MAIN QUALITY PIPE, 6"	FOOT	97	79		18					
	*	Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	21764	21764							
	*	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1							
	*	Z0030255	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2	EACH	2	2							
X	*	Z0067900	STEEL CASINGS 24"	FOOT	21								21
Δ	*	Z0076600	TRAINEES	HOUR	2,000	2,000							

Δ Y080



FILE NAME = 003-007\_650sq01.dgn  
 USER NAME = USER3830  
 PLOT SCALE = 1:1  
 PLOT DATE = 7/15/2010

DESIGNED - M.W.	REVISED -
DRAWN - E.D.	REVISED -
CHECKED -	REVISED -
DATE - 9/23/2009	REVISED -

VILLAGE OF VILLA PARK, ILLINOIS

SUMMARY OF QUANTITIES  
 SCALE: AS NOTED SHEET NO. 5 OF 5 SHEETS STA. TO STA.

F.A. U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2652	00-00070-00-PV	DUPAGE	160	7
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 63379	