

STA	EARTH EXCAVATION	EXCAVATION FOR EMBANKMENT (ADJUSTED FOR SHRINKAGE)	EMBANKMENT	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	POROUS GRANULAR EMBANKMENT, SUBGRADE	FURNISHED EXCAVATION
	20200100			20201200	20700420	20400800
	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD
114+22.95	1	0	13	0	0	-13
114+50.00	1	1	14	0	0	-14
114+68.86	0	0	5	0	0	-5
115+00.00	1	0	12	0	0	-11
115+22.14	0	0	17	0	0	-17
115+50.00	0	0	22	0	0	-22
116+00.00	1	1	39	0	0	-38
116+50.00	1	1	31	0	0	-30
116+71.35	0	0	12	0	0	-12
<b>SUBTOTAL</b>	<b>1252</b>	<b>1064</b>	<b>906</b>	<b>592</b>	<b>116</b>	<b>158</b>
<b>STAGE 2</b>						
66+16.00	0	0	0	0	0	0
66+23.40	3	3	1	0	0	2
66+27.30	2	1	1	0	0	1
66+50.00	9	7	2	0	0	5
66+73.40	9	8	0	0	0	8
66+81.98	3	3	1	0	0	2
67+00.00	7	6	2	0	0	4
67+03.66	1	1	0	0	0	1
67+22.32	6	5	1	0	0	4
67+50.00	8	7	0	0	0	7
67+72.50	6	5	2	0	0	4
67+78.30	1	1	1	0	0	0
68+00.00	4	4	3	0	0	1
68+42.34	10	8	6	0	0	2
68+50.00	2	2	1	0	0	0
68+62.03	3	3	1	0	0	2
69+00.00	13	11	1	0	0	11
69+13.23	6	5	0	0	0	5
69+48.59	17	14	3	0	0	11
69+50.00	1	1	0	0	0	0
69+63.48	7	6	1	0	0	5
70+00.00	20	17	0	0	0	17
70+11.21	6	5	0	0	0	5
70+39.02	15	13	2	0	0	11
70+50.00	6	5	1	0	0	4
70+63.17	7	6	0	0	0	6
70+92.82	13	11	3	0	0	8
71+00.00	3	3	1	0	0	2
71+13.33	6	5	0	0	0	5
71+50.00	15	13	3	0	0	9
71+54.00	2	1	1	0	0	0
71+62.92	3	3	1	0	0	2
72+00.00	13	11	0	0	0	11
72+09.43	3	3	1	0	0	2
72+17.83	3	2	1	0	0	1
72+50.00	11	9	1	0	0	8
72+63.67	4	3	2	0	0	2
72+72.34	3	2	1	0	0	1
73+00.00	9	8	0	0	0	8
73+18.58	7	6	2	0	0	4
73+22.33	1	1	1	0	0	0

STA	EARTH EXCAVATION	EXCAVATION FOR EMBANKMENT (ADJUSTED FOR SHRINKAGE)	EMBANKMENT	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	POROUS GRANULAR EMBANKMENT, SUBGRADE	FURNISHED EXCAVATION
	20200100			20201200	20700420	20400800
	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD
73+50.00	11	9	3	0	0	6
73+73.19	10	9	0	0	0	9
74+00.00	14	12	0	0	0	12
74+23.57	12	10	2	0	0	8
74+30.59	4	3	1	0	0	2
74+50.00	10	9	0	0	0	9
74+79.27	16	13	3	0	0	11
74+93.52	8	7	3	0	0	4
75+00.00	3	3	1	0	0	2
75+29.94	14	12	2	0	0	10
75+37.74	3	3	1	0	0	2
75+50.00	4	4	1	0	0	2
75+80.23	8	7	1	0	0	6
76+00.00	4	4	1	0	0	3
76+37.90	9	8	4	0	0	3
76+39.95	1	0	0	0	0	0
76+50.00	5	4	1	0	0	3
76+65.86	32	27	0	0	0	27
76+94.26	52	44	0	0	0	44
77+00.00	2	2	0	0	0	2
77+50.00	18	15	0	0	0	15
77+98.88	18	16	3	0	0	13
78+00.00	0	0	0	0	0	0
78+50.00	21	18	3	0	0	15
78+52.95	1	1	0	0	0	1
78+62.61	4	3	0	0	0	3
79+00.00	18	15	1	0	0	15
79+02.60	1	1	0	0	0	1
79+06.59	1	1	0	0	0	1
79+46.57	14	12	2	0	0	10
79+50.00	1	1	0	0	0	1
79+70.54	8	7	0	0	0	6
80+00.00	9	7	2	0	0	6
80+04.46	1	1	1	0	0	0
80+50.00	10	9	3	0	0	6
80+71.74	7	6	0	0	0	5
80+76.83	1	1	0	0	0	1
81+00.00	4	3	1	0	0	2
81+22.31	4	4	0	0	0	4
81+50.00	5	5	0	0	0	5
81+63.31	2	2	1	0	0	1
81+79.82	3	3	1	0	0	1
82+00.00	5	4	0	0	0	4
82+19.68	5	4	2	0	0	2
82+50.00	7	6	3	0	0	3
82+61.97	2	2	0	0	0	2
82+71.43	2	1	0	0	0	1
83+00.00	5	4	0	0	0	4
83+21.29	3	2	2	0	0	0
83+27.09	1	1	1	0	0	0
83+50.00	3	3	1	0	0	1
83+83.02	6	5	2	0	0	4
83+89.37	1	1	1	0	0	0



FILE NAME = 018-015.650sched01.dgn  
 USER NAME = #USER#  
 PLOT SCALE = 1:1  
 PLOT DATE = 6/15/2010

DESIGNED -  
 DRAWN -  
 CHECKED -  
 DATE -  
 REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

**VILLAGE OF VILLA PARK, ILLINOIS**

**SCHEDULE OF QUANTITIES**

SCALE: NO SCALE SHEET NO. 3 OF 6 SHEETS STA. 63+19.78 TO STA. 116+71.35

F.A. U. RTE. 2652	SECTION 00-0070-00-PV	COUNTY DuPAGE	TOTAL SHEETS 160	SHEET NO. 12
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 63379	