

STA	EARTH EXCAVATION	EXCAVATION FOR EMBANKMENT (ADJUSTED FOR SHRINKAGE)	EMBANKMENT	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	POROUS GRANULAR EMBANKMENT, SUBGRADE	FURNISHED EXCAVATION
	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD
84+00.00	1	1	1	0	0	0
84+37.49	6	5	0	0	0	5
84+50.00	2	1	1	0	0	0
84+54.37	1	0	1	0	0	0
85+00.00	6	5	5	0	0	0
85+32.23	4	4	4	0	0	0
85+50.00	2	2	2	0	0	0
85+88.53	8	7	0	0	0	7
85+97.47	2	2	1	0	0	1
86+00.00	1	1	0	0	0	0
86+50.00	11	10	4	0	0	5
86+50.25	0	0	0	0	0	0
87+00.00	9	8	0	0	0	8
87+29.89	4	3	3	0	0	0
87+50.00	3	2	2	0	0	0
87+92.40	7	6	3	0	0	3
87+95.61	0	0	0	0	0	0
88+00.00	1	1	0	0	0	0
88+17.84	2	2	2	0	0	0
88+49.37	3	3	3	0	0	0
88+50.00	0	0	0	0	0	0
89+00.00	6	5	0	0	0	5
89+50.00	10	9	0	0	0	9
89+69.83	5	4	1	0	0	3
89+98.31	8	7	1	0	0	6
90+00.00	1	1	0	0	0	1
90+23.35	4	4	2	0	0	2
90+26.61	0	0	0	0	0	0
90+50.00	1	1	1	0	0	0
91+00.00	1	1	9	0	0	-8
91+02.91	0	0	1	0	0	-1
91+17.09	0	0	3	0	0	-3
91+50.00	1	1	4	0	0	-4
91+87.36	0	0	12	0	0	-11
92+00.00	0	0	4	0	0	-4
92+28.92	0	0	8	0	0	-7
92+50.00	0	0	7	0	0	-6
92+86.37	0	0	12	0	0	-12
93+00.00	0	0	4	0	0	-4
93+32.33	0	0	13	0	0	-12
93+50.00	0	0	7	0	0	-7
93+56.67	0	0	2	0	0	-1
93+87.60	0	0	10	0	0	-10
94+00.00	0	0	4	0	0	-4
94+09.47	0	0	2	0	0	-2
94+34.18	0	0	8	0	0	-8
94+50.00	0	0	5	0	0	-5
94+84.04	1	1	9	0	0	-8
95+00.00	0	0	4	0	0	-3
95+12.23	0	0	1	0	0	0
95+50.00	1	1	1	0	0	0
95+63.28	1	0	0	0	0	0
95+74.21	1	0	1	0	0	-1

STA	EARTH EXCAVATION	EXCAVATION FOR EMBANKMENT (ADJUSTED FOR SHRINKAGE)	EMBANKMENT	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	POROUS GRANULAR EMBANKMENT, SUBGRADE	FURNISHED EXCAVATION
	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD
96+00.00	3	2	3	0	0	-1
96+23.86	4	3	2	0	0	1
96+50.00	4	3	2	0	0	1
97+00.00	8	6	0	0	0	6
97+26.31	5	4	0	0	0	4
97+47.46	5	4	0	0	0	4
97+50.00	1	1	0	0	0	1
98+00.00	12	10	0	0	0	10
98+41.50	11	9	0	0	0	9
98+50.00	2	2	0	0	0	2
98+61.80	4	3	0	0	0	3
98+76.58	7	6	0	0	0	6
98+83.98	4	3	0	0	0	3
99+00.00	7	6	0	0	0	6
99+35.21	14	12	0	0	0	12
99+50.00	6	5	0	0	0	5
100+00.00	0	0	0	30	5	0
100+50.00	0	0	1	33	9	-1
101+00.00	0	0	1	54	35	-1
101+05.69	0	0	0	9	6	0
101+10.90	0	0	0	8	5	0
101+50.00	0	0	7	45	25	-7
101+90.82	0	0	14	25	7	-14
102+00.00	0	0	3	5	1	-3
102+50.00	0	0	7	80	39	-7
102+57.03	0	0	0	18	10	0
103+00.00	0	0	1	80	33	-1
103+45.29	0	0	4	50	0	-4
103+50.00	0	0	1	5	0	-1
104+00.00	0	0	4	58	0	-4
104+50.00	64	54	0	0	0	54
104+55.98	8	7	0	0	0	7
105+00.00	43	37	5	0	0	31
105+50.00	41	35	12	0	0	23
105+69.10	17	15	5	0	0	10
106+00.00	30	26	5	0	0	21
106+50.00	57	49	2	0	1	47
106+69.88	0	0	0	23	1	0
107+00.00	0	0	0	34	3	0
107+50.00	0	0	8	45	4	-8
107+50.50	0	0	0	0	0	0
107+93.06	0	0	14	28	0	-14
108+00.00	0	0	3	4	0	-3
108+30.43	0	0	12	18	0	-12
108+50.00	0	0	8	11	0	-8
109+00.00	27	23	16	0	0	6
109+46.68	63	54	6	0	0	48
109+50.00	7	6	0	0	0	6
110+00.00	57	49	12	0	0	37
110+50.00	2	2	40	0	0	-38
110+87.05	1	1	40	0	0	-39
110+94.12	0	0	7	0	0	-7
111+00.00	0	0	6	0	0	-5



FILE NAME = 010-015_6502sched01.dgn
 USER NAME = #USER#
 PLOT SCALE = 1:1
 PLOT DATE = 6/15/2010

DESIGNED -
 DRAWN -
 CHECKED -
 DATE -

REVISED -
 REVISED -
 REVISED -
 REVISED -

VILLAGE OF VILLA PARK, ILLINOIS

SCHEDULE OF QUANTITIES

SCALE: NO SCALE SHEET NO. 4 OF 6 SHEETS STA. 63+19.78 TO STA. 116+71.35

F.A. U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2652	00-00070-00-PV	DUPAGE	160	13
CONTRACT NO. 63379			ILLINOIS FED. AID PROJECT	