



- NOTE:**
- CONTRACTOR SHALL RE-USE EXISTING UNIT DUCT OPENINGS TO THE EXISTING HANDHOLE WHERE FEASIBLE. ANY DRILLING OF THE EXISTING HANDHOLE FOR PROPOSED UNIT DUCT SHALL BE CONSIDERED INCLUDED IN THE COST OF THE DETECTOR LOOPS.
 - CONTRACTOR SHALL RE-USE EXISTING LEAD-IN CABLE FOR PROPOSED DETECTOR LOOPS. ALL MATERIALS AND WORK NECESSARY TO CONNECT THE DETECTOR LOOPS TO THE EXISTING LEAD-IN CABLE SHALL BE INCLUDED IN THE COST OF THE DETECTOR LOOPS.

- LEGEND:**
- UD UNIT DUCT
 - CT COMMON TRENCH
 - EXISTING HANDHOLE
 - PROPOSED CONDUIT IN TRENCH



FILE NAME = 051_650pm03.dgn	USER NAME = #USER#	DESIGNED - J.G.	REVISED -
PLOT SCALE = 1:200	CHECKED -	DRAWN - E.D.	REVISED -
PLOT DATE = 6/15/2010	DATE - 9/23/2009		REVISED -

VILLAGE OF VILLA PARK, ILLINOIS

PAVEMENT MARKING PLAN			
SCALE: 1"=20'	SHEET NO. 3	OF 4 SHEETS	STA. 63+19.78 TO STA. 116+71.35

F.A. U. RTE. 2652	SECTION 00-00070-00-PV	COUNTY DuPAGE	TOTAL SHEETS 160	SHEET NO. 59
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 63379	