		EY.	DATE
LAN LAN	SURVEYED		
	PLOTTED		
NOTE BOOK	ALIGNMENT CHECKED		
	RT. OF WAY CHECKED		
	CADD FILE NAME		



SUMMARY OF QUANTITIES			PAVEMENT	MARKINGS		LANDSCAPE	LIGHTS	SIGNALS	TRAINING	
. CODE NO.		UNIT	QUAN							
			+		SFTY-1D	Y002-1C	Y003	Y030-1E	Y031	Y080
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	. UNIT	58	58						
20200100	EARTH EXCAVATION	CU YD	396	396						
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	932	932						
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	12	12						
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	12	12						
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	12	12						
25200100	SODDING	SQ YD	932	932						
25200200	SUPPLEMENTAL WATERING	UNIT	10	10			1			
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	1268	1268						
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	25	25						
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	10645	10645						
42400400	PORTLAND CEMENT CONCRETE SIDEWALK 7 INCH	SQ FT	765	765						
42400800	DETECTABLE WARNINGS	SQ FT	72	72						
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	150	150		0 00 1 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	The bill of the Indiana the Indiana the Indiana			
44000300	CURB REMOVAL	FOOT	15	15						1
44000600	SIDEWALK REMOVAL	SQ FT	750	750						
Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	90	90						
44201725	CLASS D PATCHES, TYPE I, 7 INCH	SQ YD	20	20						
56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	1	1						
60255500	MANHOLES TO BE ADJUSTED	EACH	1	1						
60266600	VALVE BOXES TO BE ADJUSTED	EACH	1	1						
67100100	MOBILIZATION	L SUM	1	1						
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1						
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L, SUM	1	1		a a committee de la committee	h	and the second second		
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1.	Mr. 7-M 90-7-1-1-10-11	***************************************				Management and all a control of the
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	250	250	£		and residence of the control of the			
Z0066500	STABILIZED DRIVEWAYS 7"	SQ YD	68	68						-

GENERAL NOTES:

- UTILITIES INDICATED ON THE PLANS ARE PROVIDED FOR THE CONTRACTORS USE AND ARE BASED UPON INFORMATION AVAILABLE AT THE TIME OF THE ADVERTISEMENT FOR BIDS. THE OWNER AND ENGINEER DO NOT GUARANTEE THE ACCURACY OF UTILITIES INFORMATION.
- BEFORE ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT 1-800-892-0123 FOR FIELD LOCATIONS OF BURIED UTILITIES. (48 HOUR NOTIFICATION IS REQUIRED)
- THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES AND THE VILLAGE OF ALSIP.
- 4. BARRICADES: THE CONTRACTOR SHALL PROVIDE AND INSTALL TWO (2)
 WEIGHTED SANDBAGS ON EACH TYPE I OR TYPE II BARRICADE. USE ONE
 (1) WEIGHTED SAND BAG ACROSS EACH BOTTOM RAIL.
- 5. ALL PAVEMENT, CURB AND SIDEWALK REMOVALS SHALL BE MADE BY MEANS OF STRAIGHT SAW CUT JOINT. THE COST FOR SAW CUTTING SHALL BE INCLUDED IN THE COST OF THE INDIVIDUAL ITEMS BEING REMOVED
- THE CONTRACTOR MAY PROSECUTE WORK BETWEEN THE HOURS OF 7:00 A.M. AND DUSK EACH WORKDAY. NO WORK WILL BE PERMITTED ON SUNDAYS, OR ON HOLIDAYS, WITHOUT PRIOR WRITTEN PERMISSION FROM THE ENGINEER.

BENCH MARK:

TOP FLANGE HYDRANT NW CORNER 119TH ST. & KOSTNER AVE. ELEVATION=599.95

ARROW ON A HYDRANT S.W. CORNER OF 119TH ST & KEDVALE AVE. ELEVATION=598.03

EARTHWORK SCHEDULE

LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE OR SHORTAGE		
STATION	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD		
0+98 TO 26+83	396	336	0	336		

FILE NAME = 10246-QUAN-01 - IDOT P01	USER NAME =	DESIGNED TRL	REVISED		119TH STREET SIDEWALK PLAN		F.A.U. SECTION	COUNTY	TOTAL SHEET NO.
•		CHECKED TRL	REVISED	STATE OF ILLINOIS	1.5	SUMMARY OF QUANTITIES	1585 10-00088-00-SW	соок	10 2
	PLOT SCALE = N/A	DRAWN RG	REVISED	DEPARTMENT OF TRANSPORTATION		ALSIP, ILLINOIS	CONTRACT		VO. 63491
	PLOT DATE = 05-28-10	CHECKED . — AG	REVISED	<u>.</u>	SCALE: N/A	SHEET NO. 2 OF 10 SHEETS STA. TO STA.	FED. ROAD DIST. NO. 1 ILLINOIS FED.	AID PROJECT ARA-90	9003(663)

* - INDICATES SPECIALTY ITEMS